

Direct Testimony and Schedules
Daniel W. Gunderson

Before the Minnesota Public Utilities Commission

State of Minnesota

In the Matter of the Application of Minnesota Power
for a Certificate of Need and Route Permit for the HVDC Modernization Project
in Hermantown, Saint Louis County

OAH Docket No. 5-2500-39600
MPUC Docket Nos. E015/CN-22-607
and E015/TL-22-611

PROJECT OVERVIEW AND RISKS OF ALTERNATIVE PROPOSAL

February 14, 2024

TABLE OF CONTENTS

	Page
I. INTRODUCTION AND QUALIFICATIONS.....	1
II. PROJECT BACKGROUND.....	3
A. THE HVDC System.....	3
B. Arrowhead Substations	6
C. HVDC Modernization Project.....	9
III. STATE AND FEDERAL FUNDING.....	13
A. Federal Funding	14
B. State Funding	17
IV. RISKS ASSOCIATED WITH THE ATC ARROWHEAD ALTERNATIVE.....	19
A. State and Federal Funding Risks.....	19
B. Overall Procurement and Construction Timing Risks	22
1. Deliverability Concerns	22
2. Procurement and Performance	24
3. Transmission – Transmission Agreement Negotiations	27
C. Project Costs and Customer Cost Recovery.....	29
1. Cost of Alternatives Comparison and Rate Impact.....	29
2. Recovery through Transmission Cost Recovery Rider.....	34
V. CONCLUSION.....	36

1 **I. INTRODUCTION AND QUALIFICATIONS**

2 **Q. Please state your name and business address.**

3 A. My name is Daniel (“Dan”) W. Gunderson, and my business address is 30 West
4 Superior Street, Duluth, Minnesota 55802.

6 **Q. By whom are you employed and in what position?**

7 A. I am employed by ALLETE, Inc., doing business as Minnesota Power (“Minnesota
8 Power” or the “Company”) as the Vice President of Transmission and Distribution.

10 **Q. Please summarize your qualifications and experience.**

11 A. I hold a Bachelor of Science degree in Electrical Engineering from Michigan
12 Technological University. I obtained a master’s degree in business administration with
13 an emphasis in business operations from the Carlson School of Management at the
14 University of Minnesota in 2006. I completed requirements for obtaining Professional
15 Engineers licensure in Minnesota in 2007 and have also held a Minnesota Class A
16 Master Electrician’s license since 2004. I began my career with Minnesota Power in
17 2006 as a Meter Engineer and later a Supervising Engineer of the Electric Meter
18 Department, where I was responsible for providing project management and oversight
19 for the Smart Grid Investment Grant project, the Advanced Metering Infrastructure
20 (“AMI”) System technology and implementation and managing work for technicians
21 that maintain all metering systems. In 2013, I served as Manager of Technical Systems,
22 where I was responsible for oversight of Substation Maintenance, Substation
23 Construction, and Relay and Protection Systems. In this role, I also managed
24 transmission substation asset management programs. I have also worked as the Manager
25 of Distribution Resources where I led our Distribution Services area—including line
26 operations, operations planning, trouble, and dispatch—before being promoted to
27 Director of Distribution Operations in 2015. In 2019, I was promoted to Vice President
28 of Transmission and Distribution where I have led the Transmission and Distribution
29 operations, support and strategy. These areas include approximately 373 employees,

1 with nearly 200 of those employees as members of International Brotherhood of Electric
2 Workers Local 31.

3
4 **Q. What is the purpose of your testimony?**

5 A. The purpose of my Direct Testimony is to provide background on the Company's
6 Square Butte high-voltage, direct-current ("HVDC") system and the American
7 Transmission Company, LLC ("ATC") Arrowhead Substation. I also discuss the
8 Company's diligent efforts to obtain funding via state and federal programs to mitigate
9 costs of the HVDC Modernization Project ("Project") for Minnesota Power customers.
10 Finally, I discuss funding, in-service, rate impact, and cost recovery risks associated
11 with the system alternative proposed by ATC, which I will refer to as the "ATC
12 Arrowhead Alternative."

13
14 **Q. Who are the other Company witnesses filing Direct Testimony?**

15 A. The other Company witnesses providing Direct Testimony on behalf of Minnesota
16 Power are:

- 17 • Daniel McCourtney, Manager Strategic Environmental Initiatives – provides an
18 overview of the routing efforts undertaken by Minnesota Power prior to filing
19 the Certificate of Need and Route Permit Application ("Application") for the
20 Project and discusses the environmental considerations for the Proposed Route.
21 Mr. McCourtney addresses feedback that Minnesota Power has received on the
22 Project since filing the Application and the Company's mitigation measures to
23 limit potential natural and socioeconomic impacts of the Project. Mr.
24 McCourtney provides testimony regarding environmental and permitting
25 considerations related to the ATC Arrowhead Alternative.
- 26 • Christian Winter, Manager Regional Transmission Planning – describes the
27 need for the Project and Minnesota Power's existing transmission system from
28 a technical perspective. Mr. Winter also discusses how the Project interacts with
29 the planning process of the Midcontinent Independent System Operator, Inc.
30 ("MISO"). Mr. Winter also provides testimony regarding Minnesota Power's

1 evaluation of transmission system alternatives to the Project and explains why
2 Minnesota Power's proposed Project is the most technically-sound, reasonable,
3 and prudent alternative that will continue to provide the greatest benefit to
4 Minnesota Power's customers for decades and is the most consistent with local
5 and long-term regional transmission planning needs.
6

7 **Q. Are you sponsoring any exhibits in this proceeding?**

8 A. Yes. I am sponsoring the following schedules to my Direct Testimony:

- 9 • MP Exhibit ____ (Gunderson), Direct Schedule 1 – ATC Response to Minnesota
10 Power Information Request No. ("MP IR") 009;
- 11 • MP Exhibit ____ (Gunderson), Direct Schedule 2 – ATC Response to MP IR 007;
12 and
- 13 • MP Exhibit ____ (Gunderson, Direct Schedule 3 – Minnesota Power Response to
14 ATC Information Request No. ("ATC IR") 031.

15 16 **II. PROJECT BACKGROUND**

17 **A. The HVDC System**

18 **Q. When was the HVDC system constructed?**

19 A. The Square Butte Cooperative ("Square Butte") was created under a joint agreement
20 between Minnesota Power and Minnkota Power Cooperative in May of 1972. The
21 HVDC system was subsequently constructed by Square Butte and has been operating
22 continuously since 1977.
23

24 **Q. Please explain how the HVDC System delivers power to the AC system in
25 northeastern Minnesota.**

26 A. The HVDC system is designed to convert alternating-current ("AC") generated power
27 from the 230 kV Square Butte East Substation in Center, North Dakota into ±250kV
28 high-voltage, direct-current ("HVDC") via a converter station. Power is then
29 transmitted by HVDC over approximately 465 miles of line ("HVDC Line") east to
30 Minnesota Power's 230 kV/115 kV Arrowhead Substation and converted back into AC

1 power at that location. The transmitted power is then primarily injected into Minnesota
2 Power's transmission system in northeastern Minnesota to serve Minnesota Power's
3 customers. These assets are collectively referred to as the "HVDC System."

4
5 **Q. Why did Minnesota Power acquire the Square Butte HVDC System?**

6 A. Minnesota Power was a 50 percent owner of Square Butte, which was the sole owner of
7 the HVDC System from 1977 through 2009. Minnesota Power fully acquired the HVDC
8 assets in 2009 through a mutual agreement with Square Butte Cooperative and is now
9 the sole owner of the HVDC System. The system was acquired by Minnesota Power as
10 part of its transition to carbon-free energy and allowed for the transition from coal-fired
11 generation resources in North Dakota to high-capacity factor wind resources delivered
12 through the HVDC System.

13
14 **Q. What approvals did the Company seek in acquiring the Square Butte HVDC
15 System?**

16 A. The Company was required to submit a FERC 203 Application for a straight-forward
17 purchase of transmission facilities that is utilized by two users (FERC Docket No.
18 EC09-108-000 – Order dated November 24, 2009). The Company also received
19 approval of the Minnesota Public Utilities Commission ("Commission") to acquire the
20 assets (MPUC Docket No. E015/PA-09-526). Therefore, Minnesota Power obtained all
21 necessary approvals, including those of the Midcontinent Independent System Operator,
22 Inc. ("MISO").¹

23
24 **Q. What has the Company proposed in this proceeding?**

25 A. On June 1, 2023, Minnesota Power filed a combined Application for the HVDC
26 Modernization Project with the Commission. In that Application, Minnesota Power
27 proposed to replace and modernize HVDC terminal equipment that has operated for
28 more than 47 years, well beyond its 30-year design life. In recent years, Minnesota
29 Power has experienced HVDC terminal outages due to failures in the control system,

¹ At the time, MISO was known as the Midwest Independent Transmission System Operator, Inc.

1 power electronics, transformers, and other components of the HVDC terminals. The
2 HVDC System is an important asset for Minnesota Power and its customers. The HVDC
3 Line connecting the HVDC terminals transmits electricity from the generation of wind
4 at Minnesota Power assets located in North Dakota directly to Minnesota Power
5 customers in northeastern Minnesota.

6
7 To modernize the HVDC System, Minnesota Power proposed to construct new HVDC
8 terminals (containing HVDC/345 kV equipment) near existing HVDC terminals in
9 Hermantown, Minnesota and Center, North Dakota. Additionally, Minnesota Power
10 proposed to construct a new St. Louis County 345 kV/230 kV Substation, construct a
11 short (less than one mile) 345 kV transmission line between the HVDC terminal and the
12 St. Louis County 345 kV/230 kV Substation, and construct two short 230 kV circuits
13 (less than one mile) between the St. Louis County 345 kV/230 kV Substation and the
14 existing Minnesota Power 230 kV/115 kV Arrowhead Substation.² The decades-old
15 connection between the existing HVDC terminal and the existing Minnesota Power 230
16 kV/115 kV Arrowhead Substation would then be replaced by this connection to the new
17 HVDC terminal.

18
19 **Q. Were any alternatives suggested as part of the Environmental Assessment (“EA”)**
20 **scoping process for the Project?**

21 **A.** Yes. While no route alternatives were suggested, Minnesota Power did request that a
22 portion of the Route Width for the Project be expanded to allow for sufficient space for
23 Project construction. Minnesota Power also requested that the crossing of the West
24 Rocky Run Creek be evaluated as a double-circuit 230 kV transmission line crossing
25 instead of two parallel transmission lines. Company witness, Mr. McCourtney,
26 discusses both of these requests in more detail in his Direct Testimony. Additionally,
27 during the EA development process, ATC requested that an electrical system alternative
28 to Minnesota Power’s proposed configuration be evaluated. ATC requested that, instead

² In his Direct Testimony, Company witness, Mr. McCourtney discusses the Company’s revision to include a double-circuit 230 kV transmission line instead of two separated 230 kV transmission lines.

1 of the Project connecting to Minnesota Power's local AC transmission system at 230
2 kV at Minnesota Power's Arrowhead 230 kV/115 kV Substation, that the Project
3 connect to ATC's Arrowhead 345 kV/230 kV Substation at 345 kV and that the St.
4 Louis County 345 kV/230 kV Substation not be constructed as part of the HVDC
5 Modernization Project. ATC's proposed Arrowhead Alternative is inferior to the Project
6 and does not serve the Project need for reasons discussed in my Direct Testimony and
7 the Direct Testimony of Company witnesses Mr. McCourtney and Mr. Winter.

8
9 **B. Arrowhead Substations**

10 **Q. Please describe the two Arrowhead Substations in Hermantown, Minnesota.**

11 A. There are two distinct substation facilities located adjacent to each other in
12 Hermantown, MN. The first facility is Minnesota Power's Arrowhead 230 kV/115 kV
13 Substation. This substation is wholly-owned by Minnesota Power and is the current
14 interconnection point for the existing HVDC System to Minnesota Power's AC
15 transmission system. The HVDC System has interconnected at this location to directly
16 serve Minnesota Power's customers at 230 kV for decades.

17
18 The second facility in this area is ATC's Arrowhead 345 kV/230 kV Substation. This
19 substation was energized in February 2008 as part of Minnesota Power and ATC's joint
20 Arrowhead – Weston 345 kV Transmission Project for the purpose of facilitating
21 increased transfer capability to Wisconsin to improve the reliability of the Wisconsin
22 transmission system.

23
24 **Q. What is the purpose of Minnesota Power's 230 kV/115 kV Arrowhead Substation?**

25 A. Minnesota Power's Arrowhead 230 kV/115 kV Substation serves multiple purposes.
26 First, it is interconnected with the 230 kV AC network in northeastern Minnesota and
27 is used to provide service to Minnesota Power customers. Second, the facility is the
28 interconnection point for the existing HVDC system and is the primary facility for
29 energy delivery from Minnesota Power's renewable assets in North Dakota. Lastly, this
30 facility is an interconnection from the Minnesota Power 230 kV system to the

Arrowhead 345 kV system that is regulated by a phase shifter designed to limit flow due to the demand of the transmission network in Wisconsin.

Q. What is the purpose of ATC's 345 kV/230 kV Arrowhead Substation?

A. The purpose of ATC's 345 kV/230 kV Arrowhead Substation is to be the interconnection point between the northwestern Wisconsin and northeastern Minnesota AC transmission systems. The ATC 345 kV/230 kV Arrowhead Substation was constructed as part of the Arrowhead – Weston 345 kV transmission project ("Arrowhead – Weston Project") as a critical path to support the transmission network in Wisconsin and help resolve some of the constraints on the Minnesota – Wisconsin transmission interface. The purpose of this facility was explained by ATC as follows:

First, Arrowhead – Weston improves electric system reliability by reducing the strain on Wisconsin's single transmission connection to the west, the Eau Claire – Arpin transmission line. Second, this project increases import and transfer capability into Wisconsin, a state that depends on imports to meet its power needs. Third, it provides needed support for WPS Weston 4 power plant and helps all of Central Wisconsin be less vulnerable to outages. Fourth, the Stone Lake Substation provides critical support for Xcel customers in Northwestern Wisconsin, and lastly the line improves access to lower cost, Western energy markets, which is an unanticipated advantage.³

In summary, the ATC 345 kV Arrowhead Substation was built to benefit the Wisconsin AC transmission system and Wisconsin electrical users.

Q. What was Minnesota Power's role in the permitting and construction of ATC's 345 kV/230 kV Arrowhead Substation?

A. Minnesota Power supported the development and Minnesota permitting process for the Arrowhead – Weston Project in the 1990s in collaboration with Wisconsin Public Service (which was acquired by what is now WEC Energy Group in 2007, eventually creating ATC). After the creation of ATC, Minnesota Power worked collaboratively

³ *Arrowhead – Weston Transmission Line Energized*, T&D World, <https://www.tdworld.com/overhead-transmission/article/20957492/arrowhead-weston-transmission-line-energized> (Feb. 20, 2008), accessed Feb. 13, 2024.

1 with the new entity to complete the Arrowhead – Weston Project, including acting as
2 the construction manager for ATC’s Arrowhead 345 kV/230 kV Substation. Minnesota
3 Power led the efforts with Minnesota regulators and agencies associated with
4 construction of the substation and provided resources to ensure the safe completion of
5 the facility in compliance with Minnesota regulatory requirements.
6

7 **Q. Were any limitations imposed on the Arrowhead – Weston Project when it was**
8 **permitted for construction in Minnesota?**

9 A. Yes. The Minnesota Environmental Quality Board put a limitation of 800 MVA on the
10 transfer of power for the Arrowhead – Weston 345 kV transmission line. The
11 requirement was set such that ATC would need to seek authorization from the
12 Commission⁴ to increase the capabilities at the ATC Arrowhead 345 kV/230 kV
13 Substation. No such authorization has been requested in this proceeding to date, as
14 Minnesota Power’s proposed HVDC Modernization Project configuration would have
15 no impact on this 800 MVA limitation at ATC’s Arrowhead 345 kV/230 kV Substation.
16

17 **Q. Please explain how the operation of ATC’s 345 kV/230 kV Arrowhead Substation**
18 **relates to the 800 MVA limitation for the Arrowhead – Weston 345 kV**
19 **transmission line.**

20 A. Currently, the flow on the Arrowhead - Weston line is maintained within the 800 MVA
21 limitation through the use of a phase-shifting transformer at ATC’s Arrowhead 345
22 kV/230 kV Substation. Company witness, Mr. Winter, discusses concerns with the
23 impacts of the ATC Arrowhead Alternative on this operational limitation.
24

25 **Q. Are there any such limitations on the Minnesota Power 230 kV/115 kV Arrowhead**
26 **Substation?**

27 A. No, there are no similar regulatory limitations on Minnesota Power’s Arrowhead 230
28 kV/115 kV Substation. This facility does not have a direct connection to the Wisconsin

⁴ Transmission line permitting authority was transferred from the Environmental Quality Board to the Commission and the Minnesota Department of Commerce after the permit to construct was issued by the Environmental Quality Board.

1 AC system (any electricity must flow, first, through ATC's 345 kV/230 kV Arrowhead
2 Substation). Instead, Minnesota Power's 230 kV/115 kV Arrowhead Substation has, for
3 decades, been the connection point between the HVDC System and Minnesota Power's
4 AC transmission system, which connects to and serves Minnesota Power's customers.
5

6 Minnesota Power planned the HVDC Modernization Project to take advantage of the
7 existing 230 kV transmission backbone infrastructure for its AC system by maintaining
8 the connection between the HVDC System and the Minnesota Power 230 kV/115 kV
9 Arrowhead Substation via the St. Louis County 345 kV/230 kV Substation. This
10 configuration ensures that the electricity transmitted by the HVDC Line remains
11 preferentially on the Minnesota Power AC system for the benefit of Minnesota Power's
12 customers. This configuration is discussed in more detail in the Direct Testimony of
13 Company witness Mr. Winter.
14

15 **Q. What is the appropriate time for upgrading the ATC Arrowhead 345kV**
16 **Substation in the future?**

17 A. The expansion of the ATC Arrowhead Substation should be considered as part of long-
18 term regional planning between MISO, Minnesota Power, and ATC. Upgrades to this
19 facility should have costs allocated appropriately to all those who receive benefits from
20 the upgrades and surrounding facilities have been appropriately jointly studied and
21 agreed upon by all stakeholders.
22

23 **C. HVDC Modernization Project**

24 **Q. How long has Minnesota Power been evaluating system needs for the Square Butte**
25 **HVDC Modernization System?**

26 A. Minnesota Power has been actively evaluating the needs associated with the HVDC
27 System since 2012. This has been a long and iterative process that Minnesota Power has
28 approached carefully and collaboratively with stakeholders, such as MISO and other
29 transmission owners in northeastern Minnesota, including ATC. Given the significant
30 value of the HVDC System to provide carbon-free wind energy from Minnesota

Power's North Dakota wind facilities and purchases directly to Minnesota Power's customers, and the level of investment necessary to modernize the HVDC System, the Company has taken this process very seriously and has been very diligent in its evaluation and development of the HVDC Modernization Project.

Q. What system studies and evaluations were necessary to prepare for filing the Certification of Need Application with the Commission for the HVDC Modernization Project?

A. Since 2012, the Company has undertaken multiple, iterative studies and analyses. The most definitive of these studies for the currently-proposed HVDC Modernization Project began in 2020. These are discussed in more detail in the Direct Testimony of Company witness Mr. Winter.

Q. During this evaluation process, what external coordination did Minnesota Power undertake with other utilities or MISO?

A. Minnesota Power has been engaged with MISO throughout the planning process and has paced with MISO on our current plan filed with the Commission. The Company has also coordinated with MISO on long-term planning, particularly regarding the value of the HVDC System and the future role of HVDC transmission within MISO's operating territory. The HVDC Modernization Project is a critical component in support of the transition to carbon-free electricity for Minnesota Power customers.

Q. Why was 230 kV selected as the connecting voltage for the Square Butte HVDC System?

A. When the HVDC System was designed, 230 kV was selected as it was the high voltage standard for the Minnesota Power transmission network in northeastern Minnesota. It was the logical choice for the power transfer requirements on the transmission network at the time of construction. Prior to and following the establishment of the connection to the HVDC System, Minnesota Power's AC transmission system in northeastern Minnesota developed around 230 kV to establish the backbone of the local transmission

1 network used to serve the needs of Minnesota Power's customers. In his Direct
2 Testimony, Company witness Mr. Winter discusses the importance of maintaining the
3 230 kV connection to the Minnesota Power transmission system.
4

5 **Q. What is the purpose of the HVDC Modernization Project?**

6 A. The primary purpose of the HVDC Modernization Project is to replace the aging HVDC
7 terminal assets in both North Dakota and Minnesota. The HVDC Modernization Project
8 is also intended to ensure that Minnesota Power's customers continue to receive the
9 HVDC System benefits to the greatest extent practical, especially in light of the fact that
10 they will be responsible for the cost of the HVDC Modernization Project. Therefore,
11 Minnesota Power has closely aligned those facilities identified in the Application with
12 this asset renewal need to extend and enhance the important investments made by
13 Minnesota Power customers in both the HVDC System and existing North Dakota wind
14 facilities.
15

16 **Q. Please explain the Company's reasons for proposing to use VSC technology instead**
17 **of the traditional LCC technology for the HVDC Modernization Project.**

18 A. Voltage Source Converter ("VSC") technology offers several benefits over the
19 traditional Line Commutated Converter ("LCC") technology and positions Minnesota
20 Power in line with the global market as the industry positions for a clean energy future.
21 The grid-supporting benefits of VSC include voltage regulation to support the
22 interconnecting grids, frequency response, and blackstart capability. These benefits will
23 enable Minnesota Power and the region to continue to reliably support its clean energy
24 transition. Globally, most systems being designed and constructed are utilizing VSC
25 due to the range of benefits provided over LCC, which will ensure support throughout
26 the operating life of the HVDC system. VSC is also more flexible for the conditions in
27 which it can operate, so it is better suited to work where future system conditions are
28 less predictable.
29

1 **Q. What are key considerations in the future operability and potential expandability**
2 **of the HVDC Modernization Project?**

3 A. As Minnesota Power approached its planning for the HVDC Modernization Project, it
4 was very thoughtful in evaluating design to build both expandability and optionality
5 into the Project to maximize value for Minnesota Power customers. The Company took
6 steps to work with HVDC vendors as well as taking into consideration long-term
7 planning to source the highest-capacity renewable energy in the region to thoughtfully
8 plan for a flexible facility over its operating life. As a result of this innovative approach,
9 Minnesota Power was eligible to apply for federal funding (and supporting state
10 funding) to mitigate Minnesota Power customer costs for integrating future
11 considerations for a system that could provide the foundation for that flexibility over its
12 operating life to support the clean energy transition. These designed-for-flexibility
13 features allow Minnesota Power to leverage its existing HVDC System to provide even
14 greater transfer capabilities for additional carbon-free electricity from North Dakota in
15 the future, when needed.

16
17 **Q. Can you describe the sequence of decisions that led to the company to deciding on**
18 **upgradability and designing the HVDC system in this way?**

19 A. As Minnesota Power approached the decision of upgradability of its HVDC System,
20 several factors came into consideration. The first was the availability of federal funding
21 for a unique potential upgrade of capacity and voltage at the facility, where the rate
22 impacts of such a project could be substantially reduced. The most optimal solution for
23 an upgraded HVDC facility would be to interconnect at a higher voltage today to avoid
24 future reconfiguration related to that voltage. As such, the Company opted for a higher
25 voltage in this Certificate of Need filing as a prudent measure to avoid future re-
26 configuration at this site. The Company then studied the best way to interconnect given
27 the voltage upgrade and found that the most optimal use of this site is the configuration
28 proposed in the filing, which was in line with appropriate planning processes for a
29 facility of this type. It was this configuration and innovative thinking that allowed

1 Minnesota Power to access state and federal grant funding opportunities for the HVDC
2 Modernization Project.

3
4 **III. STATE AND FEDERAL FUNDING**

5 **Q. What has Minnesota Power done to mitigate costs of the HVDC Modernization**
6 **Project for its customers?**

7 A. In addition to working with our HVDC supplier on thoughtful long-term Project
8 savings, Minnesota Power has done extensive work seeking grants to mitigate costs
9 associated with the HVDC Modernization Project, particularly those costs related to the
10 innovative technology and forward-thinking future considerations that have been
11 integrated into the design of the Project. Minnesota Power has been selected for \$75
12 million in total grant funding for the Project, the details of which I discuss below.

13
14 **Q. Are there conditions that Minnesota Power must meet in order to receive this grant**
15 **funding for the Project?**

16 A. Yes. As I discuss later in my testimony, the awarding of certain funds is contingent upon
17 two significant milestones: (1) negotiating and entering into an award contract for the
18 federal funding portion of our awarded grants and (2) the delivery of the Project on
19 established federal timelines. Minnesota Power believes both of these milestones can be
20 achieved if the Commission approves Minnesota Power's proposed configuration of the
21 HVDC Modernization Project. The second of these milestones is of concern for
22 Minnesota Power if the Commission orders it to construct the ATC Arrowhead
23 Alternative because the Company will no longer have full control of the Project
24 schedule, which may prevent the Company from meeting the timeline requirements for
25 the federal award.

26
27 **Q. Is Minnesota Power considering any other grant applications?**

28 A. Minnesota Power continues to evaluate if there are any additional grant opportunities
29 that would be available for the HVDC Modernization Project to reduce overall Project
30 costs for Minnesota Power customers. On January 12, 2024, Minnesota Power

submitted the HVDC Interconnection Facilities concept paper for the U.S. Department of Energy (“DOE”) second round funding opportunity of the Grid Resilience and Innovation Partnerships (“GRIP”) Program for Fiscal Years 2024 and 2025.

Submitting a concept paper in response to the funding opportunity announcement is the required first step for submitting a full application for the second round of GRIP funding. If Minnesota Power receives a letter of encouragement to apply from the DOE, which is expected in the first quarter of 2024, the Company will submit a full application in May 2024 to request grant funding to support the 345 kV/230 kV interconnections needed to connect Minnesota Power’s upgraded converter stations to the AC grid. If Minnesota Power’s full application is selected for DOE award negotiation, the Company could apply up to \$50 million in additional DOE grant funding toward the new 345 kV/230 kV substations and AC interconnection facilities proposed for the HVDC Modernization Project, including Minnesota Power’s proposed St. Louis County 345 kV/230 kV Substation. If awarded, this federal funding could only be applied to Minnesota Power’s Project configuration for the HVDC Modernization Project and would not be available if the Commission orders construction of the ATC Arrowhead Alternative, which I discuss in further detail in Section IV.A of my Direct Testimony.

In the event that any additional grants are awarded to Minnesota Power or other cost mitigation opportunities become available, the Company will provide an update to the Commission.

A. Federal Funding

Q. What federal funding opportunities has Minnesota Power been awarded for the Project to date?

A. During the first round DOE GRIP funding opportunity, Minnesota Power had an opportunity to apply for federal funding and developed the HVDC Terminal Expansion Capability Project (“HTEC”) concept as an innovative idea to create expandability of the HVDC terminal capacity for future use, including elements of the interconnection

1 components at the HVDC converter stations that were also within the scope of the
2 project submittal. HTEC includes innovative technology components of the HVDC
3 Modernization Project that have specifically been designed to preserve future
4 expandability options for the new HVDC converter stations over their multi-decade
5 operating life.

6
7 The DOE's Grid Deployment Office ("GDO") recommended the HTEC concept for
8 negotiation of a \$50 million grant during the first round of DOE GRIP funding, which
9 would reduce customer costs associated with the Company's proposed configuration of
10 the HVDC Modernization Project. The Company is currently working with the DOE to
11 finalize contract requirements for the first round federal grant and the cooperative
12 agreement with the DOE is anticipated to be executed in the second quarter of 2024.
13 Once that agreement is executed, the Company can commence the performance of the
14 Project and submit for reimbursement up to the \$50 million awarded. The HVDC
15 Modernization Project (including the HTEC components) must proceed on the agreed-
16 upon milestones within 60 months after the execution of the Cooperative Agreement
17 with the DOE.

18
19 **Q. What was the application process for this federal grant?**

20 A. Applicants for GRIP funding were required to submit a concept paper which described
21 the project and its benefits, the approach to be taken with the community benefits plan,
22 and an overview of the project team qualifications and experience. Only applicants who
23 submitted an eligible concept paper were eligible to submit a full application. Following
24 DOE's review of the concept paper, DOE encouraged the Company to submit a full
25 application. Full applications were comprised of over a dozen separate files including a
26 technical volume, the community benefits plan, environmental questionnaires, and a
27 budget workbook. These documents were all developed by Minnesota Power over a
28 period of several months to complete the extensive work necessary just for DOE to
29 consider the HTEC concept for federal grant funding.

30

1 **Q. Please explain the process Minnesota Power must go through to receive this grant.**

2 A. On October 17, 2023, the Company was notified that DOE had completed its evaluation
3 of the full application and that the HTEC project had been recommended by the GDO
4 for negotiation of a financial award. The notification letter further stated the notification
5 does not guarantee federal funding, as funding will only be obligated upon completion
6 of successful negotiations. Receipt of the notification letter does not authorize the
7 Company to commence with performance of the concept. Only an award document
8 signed by the Contracting Officer obligates DOE to provide the awarded
9 reimbursements under the grant program. As part of the pre-award process, the
10 Company was required to submit a pre-award information sheet, Davis Bacon
11 Assurances, a cybersecurity plan, a community benefits plan, and other information and
12 documents as requested. Key award negotiation elements include a detailed statement
13 of project objectives, technical evaluation of the project budget, development of an
14 environmental questionnaire, and DOE completing its required environmental review.

15
16 This process has required a significant amount of time and effort by Minnesota Power
17 to provide information necessary to receive this federal funding. This process has also
18 necessitated Minnesota Power making commitments related to cybersecurity,
19 community benefits, and Davis Bacon Assurances that must be implemented for all
20 aspects of the HVDC Modernization Project, whether Minnesota Power's configuration
21 is approved by the Commission or the Commission orders construction of the ATC
22 Arrowhead Alternative. Therefore, in the event that the Commission orders construction
23 of the ATC Arrowhead Alternative, the Commission's order should direct ATC to
24 follow all compliance requirements including responsibility for the aforementioned
25 project reporting for awarded grant funding within the required timeline.

26

1 **Q. Is Minnesota Power capable of meeting all of the conditions required to maximize**
2 **the federal grant if the Company's HVDC Modernization Project is granted a**
3 **certificate of need and route permit from the Commission?**

4 A. Yes. The Company has established a Government Funding & Compliance Steering
5 Committee and employs individuals whose roles and responsibilities relate specifically
6 to the administration of, and compliance with, this grant. Additionally, Minnesota
7 Power has established, or is in the process of establishing, specific processes for
8 ensuring compliance with grant obligations and legal requirements as well as internal
9 and external audits. Should the Commission order construction of the ATC Arrowhead
10 Alternative, Minnesota Power may need to be granted independent audit rights related
11 to ATC's construction, procurement, and contracting activities for any portions of the
12 HVDC Modernization Project it would own or be responsible for constructing. Further,
13 any arrangement would likely require filing, and Commission approval, of an affiliated
14 interest under Minn. Stat. Section § 216B.48.

15
16 **B. State Funding**

17 **Q. What Minnesota state funding opportunities has Minnesota Power been awarded**
18 **for the Project to date?**

19 A. In 2023, the Minnesota legislature passed, and Governor Walz signed, HF 2310 which
20 appropriated \$15 million for a grant to Minnesota Power to increase the capacity and
21 improve the reliability of the HVDC system.

22
23 Additionally, on January 8, 2024, the Minnesota Department of Commerce ("DOC")
24 informed the Company that its application for the State Competitiveness Fund Match
25 Program had been deemed complete and that pursuant to procedure in statute, the DOC
26 was reserving \$10 million for the purpose of cost-share (or match) for the federal
27 funding.

1 **Q. What are the requirements associated with the Minnesota legislative award?**

2 A. The Company is working closely with the DOC to complete the transfer of these dollars,
3 which are only to be spent as a cost share as federal funds are accessed. This is a onetime
4 award and must be used to support the cost-share component of a federal grant
5 application to a program enacted in the federal Infrastructure Investment and Jobs Act,
6 Public Law 117-58 (“IIJA”), to reduce the cost of the HVDC Modernization Project and
7 to reimburse the reasonable costs incurred by the DOC to administer the grant.

8
9 **Q. What are the requirements associated with the Minnesota DOC grant?**

10 A. Execution of a final grant contract with the DOC for reserved funds requires:

- 11 • Written notice from the federal granting agency that funds have been awarded.
- 12 • The Statement of Project Objectives and the payment schedule for the federal
- 13 award.
- 14 • The name and e-mail address of the person qualified to sign the grant contract.
- 15 • The name, title, and e-mail address for the grantee’s project manager.

16
17 **Q. What North Dakota state funding opportunities has Minnesota Power been**
18 **awarded for the Project to date?**

19 A. To help strengthen Minnesota Power’s federal application for DOE grant funds
20 authorized through the IIJA, the North Dakota Legislature passed, and Governor
21 Burgum signed, HB1014, which included state support for the HVDC Modernization
22 Project by stating:

23 “It is the intent of the sixty-eighth legislative assembly that the state
24 provide support for [Minnesota Power’s] application for federal funding
25 to upgrade a high-voltage direct current transmission line in the state
26 and that the state provide support for energy development projects in the
27 state through the state’s energy-related programs.”⁵
28

29 In addition to this statement of support from North Dakota, the Company is working
30 with the Bank of North Dakota to determine whether North Dakota’s low-interest loan

⁵ https://ndlegis.gov/assembly/68-2023/regular/bill-overview/bo1014.html?bill_year=2023&bill_number=1014

1 conditions are appropriate for the HVDC Modernization Project and in the interest of
2 Minnesota Power's customers.

3
4 **Q. What are the requirements of the North Dakota loan conditions?**

5 A. The requirements will ultimately depend on the loan conditions established by the Bank
6 of North Dakota. At this time, Minnesota Power is exploring financial options.

7
8 **Q. Are any of the state grants dependent on the federal grant?**

9 A. Yes. The \$10 million grant from the Minnesota State Competitiveness Fund,
10 administered by the DOC, is appropriated as part of the Company's cost-share
11 requirements for the \$50 million from the round one federal GRIP funding. This funding
12 can only be accessed by Minnesota Power for the HVDC Modernization Project after a
13 cooperative agreement is signed with the DOE for the GRIP funding and must be
14 expended over a specified time period.

15
16 **Q. Is Minnesota Power capable of achieving all the requirements required to
17 maximize the state grants at this time if the HVDC Modernization Project in the
18 Company's proposed configuration is granted a certificate of need and route
19 permit from the Commission?**

20 A. Yes.

21
22 **IV. RISKS ASSOCIATED WITH THE ATC ARROWHEAD ALTERNATIVE**

23 **A. State and Federal Funding Risks**

24 **Q. Are any of the grant monies at risk if the ATC Arrowhead Alternative is ordered
25 by the Commission for the Project?**

26 A. Federal funding through the GRIP program round one will be awarded based on the
27 submitted HTEC concept for the HVDC Modernization Project. Alterations to the
28 project concept would need to be addressed with the DOE given the total HTEC project
29 concept. Initiating project changes now could alter project timing and create
30 unnecessary delays in execution.

1
2 Minnesota Power believes that the round one DOE GRIP funding has a low probability
3 of being impacted and the Company does not believe that any funding dollars for the
4 state grants described above would be withheld in total in the event the Commission
5 orders the Company to proceed with the ATC Arrowhead Alternative instead of the 230
6 kV interconnection, as the grant funding selections to date have all related to the HVDC
7 equipment and its expandability capabilities. However, grant funds may be at risk or
8 delayed if ATC cannot deliver all aspects of the ATC Arrowhead Alternative on the
9 requisite timeline, including the concerns related to studies and equipment procurement
10 discussed in the Direct Testimony of Company witness Mr. Winter. The GRIP round
11 one federal grant period is only 60 months from the time of award expected in the second
12 quarter of 2024. Minnesota Power continues to make all practicable efforts to achieve
13 an in-service date of the fourth quarter of 2027 for the HVDC equipment with an earlier
14 completion date for the 230 kV interconnection infrastructure and is well-situated to
15 achieve this in-service date, as discussed in more detail by Company witness Mr.
16 Winter.

17
18 However, Minnesota Power has been working toward achieving this in-service date
19 since 2020, and has completed significant study, engineering, power flow analyses,
20 design, and procurement work to date for the HVDC equipment and 230 kV
21 interconnection infrastructure.

22
23 The Company is actively continuing this important work to make all efforts to achieve
24 an in-service date earlier than 2030. ATC has only just proposed its alternative for the
25 345 kV interconnection infrastructure as of September 2023. The Company is
26 concerned about the ability to deliver the ATC Arrowhead Alternative on the 2030
27 timeline, let alone by 2028, given the planning work that still needs to occur if the
28 Commission orders construction of the ATC Arrowhead Alternative. These concerns
29 are discussed in detail in the Direct Testimony of Company witness Mr. Winter.
30

1 According to the procedural schedule for this proceeding, the earliest this decision
2 would be made by the Commission would be late July 2024. I discuss these concerns in
3 more detail in Section IV.B of my Direct Testimony. Not being able to deliver the
4 HVDC Modernization Project on these timelines could put portions of the funding at
5 risk under the various grant programs.

6
7 Additionally, if Minnesota Power is encouraged to submit a full application for the DOE
8 GRIP round two funding and selected for an award for the HVDC Interconnection
9 Facilities concept, up to \$50 million in additional federal funding would be lost if the
10 Commission orders construction of the ATC Arrowhead Alternative. This is because
11 Minnesota Power's DOE GRIP round two application will only support interconnection
12 components of Minnesota Power's Project configuration, including the St. Louis
13 County 345 kV/230 kV Substation. Minnesota Power is working hard to secure as much
14 federal funding as practical for the HVDC Modernization Project to reduce overall
15 customer rate impacts associated with the Project. To date, the Company has identified
16 up to \$100 million in potential federal funding available for the HVDC Modernization
17 Project. Not receiving this funding means Minnesota Power customers must make up
18 the difference in Project costs. I discuss estimated rate impacts with federal and state
19 funding applied to the Project in Section IV.C of my Direct Testimony.

20
21 **Q. What efforts has ATC undertaken to obtain federal or state grants to reduce the**
22 **overall costs of the ATC Arrowhead Alternative?**

23 A. In its response to MP IR 009, ATC has stated that it has not applied for any federal or
24 state grants to reduce the costs of the Arrowhead Alternative. A copy of this response is
25 attached to my Direct Testimony as Schedule 1.

1 **B. Overall Procurement and Construction Timing Risks**

2 1. Deliverability Concerns

3 **Q. How long has Minnesota Power been working on achieving the 2030 in-service date**
4 **for the HVDC Modernization Project?**

5 A. Minnesota Power began the current concept design implementing VSC going back to
6 2020-21. Procurement activities for this Project were able to be advanced in 2022, after
7 outreach efforts with major HVDC suppliers revealed that demand for HVDC systems
8 was skyrocketing globally given their critical role in renewable-based energy grids. As
9 a result of the outreach, Minnesota Power set an in-service goal of 2028 for this facility
10 and immediately began procurement activities to meet that date. Minnesota Power has
11 been seeking the earliest possible in-service date for the HVDC facilities from the
12 origination of the current HVDC Modernization Project. The extensive work completed
13 by Minnesota Power to achieve this in-service goal is discussed in the Direct Testimony
14 of Company witness Mr. Winter.

15
16 **Q. Please describe the actions Minnesota Power has taken to ensure that the 2030 in-**
17 **service date is achievable.**

18 A. During the procurement process, the Company secured the earliest “guaranteed” date of
19 delivery available from the manufacturer, which was April 2030. As part of this
20 arrangement, the HVDC supplier may also propose an earlier in-service date should
21 such an opportunity become available in its manufacturing queue, which the Company
22 could then evaluate and accept if it is in a position to do so. The Company believes there
23 is a strong probability of accelerating the delivery schedule for the HVDC
24 Modernization Project HVDC components.

25
26 **Q. Has ATC initiated design and procurement collaboration with Minnesota Power**
27 **in the event the Commission orders the construction of the ATC Arrowhead**
28 **Alternative?**

29 A. No. ATC has not engaged meaningfully with Minnesota Power to coordinate or plan for
30 the ATC Arrowhead Alternative. The communication and minimal planning

1 information that ATC has shared with Minnesota Power has primarily taken place
2 through the regulatory process. If ATC has undertaken any design, engineering, or
3 procurement activities to meaningfully advance planning for the ATC Arrowhead
4 Alternative in the event the Commission orders its construction, ATC has done so
5 without any collaboration with, or requested input from, Minnesota Power. Such
6 collaboration is critical to ensure that the facilities will be properly designed and
7 delivered consistent with required system performance.

8
9 **Q. What information has ATC provided in this proceeding about its engineering,**
10 **design, and procurement activities for the ATC Arrowhead Alternative?**

11 A. ATC has provided very limited information about these activities. As part of MP IR
12 007, attached to my Direct Testimony as Schedule 2, Minnesota Power asked ATC
13 about the status of ATC's engineering and procurement activities for each component
14 of Arrowhead Alternative. ATC declined to provide this detailed information and
15 instead referred Minnesota Power to its response to another information request, MP IR
16 012, that only provided ATC's proposed overall schedule for the Arrowhead
17 Alternative. Of note, this schedule states that ATC will not even commence procurement
18 activities for any materials required for the construction of the Arrowhead Alternative
19 until May 2024. A copy of ATC's response to MP IR 012 is attached to the Direct
20 Testimony of Mr. Winter as Schedule 37.

21
22 **Q. What concerns does Minnesota Power have with achievement of a 2030 in-service**
23 **date in the event the Commission orders construction of the ATC Arrowhead**
24 **Alternative?**

25 A. Given the fact that ATC failed to present any meaningful alternatives to Minnesota
26 Power during various conversations and meetings prior to Minnesota Power filing its
27 Application and, instead, provided only a conceptual plan in September 2023, absent
28 (1) updated studies that evaluate the ATC Arrowhead Alternative to determine if the
29 Arrowhead phase shifting transformer is necessary and what impact it may have on the
30 800 MVA limitation placed on the facility by the Minnesota Environmental Quality

1 Board or (2) front-end collaboration on things as basic as interconnection configurations
2 for the ATC Arrowhead Alternative where it connects to Minnesota Power facilities and
3 inter-utility cooperation agreements, Minnesota Power has significant concerns with the
4 achievement of the 2030 in-service date for the ATC Arrowhead Alternative, as well as
5 any possibilities of moving the in-service date forward to 2028, as desired. The
6 Company also has concerns with the time and collaboration required for completing and
7 updating necessary project design and integration studies, negotiating project
8 agreements, and procuring major AC interconnection facility equipment at such a late
9 planning stage of the project and a known strained supply chain for these types of
10 materials.

11
12 2. Procurement and Performance

13 **Q. What steps has Minnesota Power undertaken to procure the equipment necessary**
14 **for the HVDC Modernization Project with a 230 kV interconnection?**

15 A. Minnesota Power has determined the required equipment and has issued a Request for
16 Proposal and selected a vendor for the longest lead time equipment, which can be as
17 long as three years from the time initial design and specification work is completed and
18 the order is placed with a vendor. The Company has followed a procurement process
19 that will allow Minnesota Power to achieve an in-service date for the AC
20 interconnections of the Company's proposed HVDC Modernization Project
21 configuration by the end of 2027 and the in-service date of the entire HVDC
22 Modernization Project by 2028. Minnesota Power detailed its design, engineering,
23 procurement, and construction schedule for the HVDC Modernization Project in
24 response to ATC IR 031 which is attached to my Direct Testimony as Schedule 3. This
25 process is detailed in the Direct Testimony of Company witness Mr. Winter.

1 **Q. Why did the Company start the procurement process for the 230 kV**
2 **interconnection infrastructure before receiving a certificate of need and route**
3 **permit from the Commission?**

4 A. When the Company began the planning for the Project, both external consultants and
5 those vendors associated with high-voltage interconnection equipment, the Company
6 was advised in these early planning processes that lead times were increasing and that
7 it would be critical to plan for early procurement in order to avoid delays related to
8 manufacturing capacity. Given the need for modernization of this facility at the earliest
9 possible date to provide the maximum benefit to customers, the Company took action
10 towards initiating the procurement process.
11

12 **Q. What steps has ATC undertaken to procure the equipment necessary for its**
13 **proposed 345 kV interconnection for the HVDC Modernization Project?**

14 A. As I noted earlier, based on ATC's response to MP IR 012, ATC has not started the
15 procurement process for the proposed 345 kV interconnection.
16

17 **Q. Has the Company identified any performance concerns with a 345 kV**
18 **interconnection versus a 230 kV interconnection for the HVDC Modernization**
19 **Project?**

20 A. Yes, the Company has concerns that the ATC Arrowhead Alternative has not been
21 studied or worked on in a broader planning setting with MISO or Minnesota Power.
22 This is concerning as the proposed configuration by ATC has a strong probability of
23 providing a tremendous benefit to Wisconsin ratepayers through increased flows onto
24 their constrained Wisconsin AC transmission system, while being fully funded by
25 Minnesota Power customers. This dynamic detailed performance concerns, are further
26 detailed in Mr. Winter's testimony.
27

1 **Q. Please explain your overall concerns with procurement and performance of the**
2 **345 kV interconnection.**

3 A. As an initial matter, it is concerning that between the time ATC asked that its ATC
4 Arrowhead Alternative be considered in this proceeding and early January, ATC had
5 already changed its proposed alignment for the 345 kV transmission line more than once
6 as discussed in detail in the Direct Testimony of Company witness Mr. McCourtney.
7 This means that the alignment proposed by ATC and presented to the Commission when
8 it considered this matter in November 2023 was changed to a new location for purposes
9 of the EA evaluation the DOC, Energy Environmental Review and Analysis and more
10 changes may be necessary in the future. This highlights how little planning has gone
11 into this alternative proposed by ATC in this proceeding.

12
13 Second, given that there has been no long term planning for this option with either the
14 Company or MISO, the need for and procurement of additional equipment such as a
15 phase shifting transformer and the procurement of other long lead time equipment
16 (specialized high voltage transformer and apparatus have 36-month (or more) lead times
17 at current date) could result in both delays in the project timeline as well as unanticipated
18 outage times. This has significant additional potential financial risk to the rates paid for
19 by Minnesota Power customers for both the initial construction cost of the ATC
20 Arrowhead Alternative and through the Fuel and Purchased Energy Adjustment Clause
21 for replacement energy as the existing HVDC converter stations continue to experience
22 outages due to failure. Both delays in overall schedule as well as unanticipated outages
23 are major challenges at the current time.

24
25 Lastly, the Company is concerned that the ATC Arrowhead Alternative, while funded
26 by Minnesota ratepayers, will result in greater power transfers to Wisconsin. The need
27 for increased Wisconsin transfer capability has not been demonstrated by ATC and the
28 impacts of these greater power flows on the system have not been properly evaluated
29 by MISO, ATC, or Minnesota Power. Should the Commission order the ATC
30 Arrowhead Alternative to be constructed as a part of the HVDC Modernization Project,

1 Wisconsin ratepayers would receive the benefit of this increased transfer capability at
2 the expense Minnesota Power's customers, who would be solely responsible to pay for
3 it.

4
5 3. Transmission – Transmission Agreement Negotiations

6 **Q. What are transmission – transmission agreements?**

7 A. Transmission-transmission agreements are necessary to define the terms, conditions,
8 and characteristics by which transmission connections are performed when connecting
9 facilities of disparate ownership. They are required as every interconnection between
10 different utilities requires contractual requirements for ownership, operations, and
11 maintenance over the life of a given facility.

12
13 **Q. Do Minnesota Power and ATC have a transmission – transmission agreement in
14 place?**

15 A. Minnesota Power has a Transmission Interconnection Agreement between itself, ATC,
16 and MISO with an execution date of January 22, 2008, that encompasses the current
17 configuration and operation of the ATC Arrowhead 345 kV/230 kV Substation

18
19 **Q. Why does a new transmission – transmission agreement need to be negotiated if
20 the Commission orders the Company to construct the ATC Arrowhead
21 Alternative?**

22 A. The circumstances at ATC Arrowhead Substation would be materially changed and
23 would require a new interconnection between Minnesota Power's 345 kV double-circuit
24 transmission line required by the ATC Arrowhead Alternative and the ATC 345 kV
25 system as well as an updated connection between the ATC 345 kV system and the
26 Minnesota Power 230 kV system. A new transmission – transmission agreement would
27 have to be reached on the development, ownership, operations and maintenance of the
28 facilities being added.

1 **Q. Who would own the 345 kV transmission line proposed in ATC's Arrowhead**
2 **Alternative?**

3 A. Minnesota Power would own the 345 kV transmission line as the first interconnection
4 to the AC system from the HVDC system.
5

6 **Q. What would the ownership be of the other 345 kV transmission infrastructure if**
7 **the ATC Arrowhead Alternative is ordered to be constructed?**

8 A. If ordered, Minnesota Power would own the 345 kV transmission infrastructure from
9 the new St. Louis County HVDC/345 kV Converter Station to a new line termination
10 structure at the ATC Arrowhead 345 kV/230 kV Substation, and ATC would own the
11 additional 345 kV and 345 kV/230 kV transmission infrastructure inside the ATC
12 Arrowhead 345 kV/230 kV Substation. Minnesota Power has also determined that the
13 ATC Arrowhead Alternative would require modifications within the Minnesota Power
14 Arrowhead 230 kV/115 kV Substation, as described by Mr. Winter, which would be
15 owned by Minnesota Power.
16

17 **Q. Are there any ownership issues to be determined if the 230 kV interconnection**
18 **proposed by Minnesota Power is ordered to be constructed by the Commission?**

19 A. No. If the 230 kV interconnection included in Minnesota Power's proposed HVDC
20 Modernization Project configuration is ordered, there are no ownership determinations
21 needed, interconnection agreement required, or Transmission - Transmission
22 agreements required.
23

24 **Q. How long do the companies believe it will take to negotiate a new transmission –**
25 **transmission agreement?**

26 A. Transmission – transmission agreements can be highly variable in the amount of time
27 required to negotiate a new agreement. If there is a high level of mutual agreement the
28 time required could be four to six months. However, if there is significant disagreement
29 on terms, agreements can take more than a year to negotiate.
30

1 **Q. Why has Minnesota Power not started negotiating a transmission – transmission**
2 **agreement with ATC for the ATC Arrowhead Alternative at this time?**

3 A. Minnesota Power provided ATC an overview of this site and our intention related to the
4 design of Minnesota Power's proposed HVDC Modernization Project proposed
5 configuration more than nine months before filing the Application. Minnesota Power
6 provided a summary of the AC interconnection configuration for the Project,
7 particularly the challenges and uncertainty described in Company witness Mr. Winter's
8 Direct Testimony. After Minnesota Power met with ATC in 2022, ATC chose not to
9 advance any meaningful discussions on the feasibility of an ATC Arrowhead
10 Alternative or even present its own proposal to Minnesota Power for consideration until
11 it presented its conceptual proposal (absent prior coordination with Minnesota Power or
12 feasibility analysis) via letter filing in the Commission's Dockets on September 15,
13 2023. Due to the significant challenges the Company has identified related to ATC's
14 Arrowhead Alternative, both in the near term and in the future, the ATC Arrowhead
15 Alternative is not a more prudent or reasonable alternative to the Company's proposed
16 HVDC Modernization Project configuration.

17
18 **C. Project Costs and Customer Cost Recovery**

19 1. Cost of Alternatives Comparison and Rate Impact

20 **Q. How did the Company prepare its cost analysis for the HVDC Modernization**
21 **Project with the 230 kV interconnection?**

22 A. The Company went through preliminary engineering design of the site, which included
23 all components necessary to connect the new interconnection for the Project and was
24 based on current construction cost estimates both from the most recent MISO estimates
25 as well as updates from vendor quotes for major equipment.

26
27 **Q. What are some examples of the Company's history in estimating transmission**
28 **project costs?**

29 A. The Company has a very successful history of estimating transmission project costs
30 including substation assets. Most recently, the Company completed its Great Northern

1 Transmission Line project, which is an example of a transmission project that was well-
2 estimated and was constructed on time and under budget with a co-developer.

3
4 **Q. How do the costs for the HVDC Modernization Project with the 230 kV**
5 **interconnection compare to the ATC Arrowhead Alternative?**

6 A. The interconnection costs for the ATC Arrowhead Alternative are significantly higher
7 when the costs for a phase shifting transformer are included. One phase shifting
8 transformer is currently installed within the ATC Arrowhead 345 kV/230 kV
9 Substation, though ATC has proposed to remove this piece of equipment as part of the
10 ATC Arrowhead Alternative. Currently, the ATC Arrowhead phase shifting transformer
11 is needed to provide flow control on the interface between Minnesota Power's 230 kV
12 system and ATC's Wisconsin 345 kV system, limiting power flows and maintaining
13 reliability on the Arrowhead – Weston 345 kV line. Given that ATC has not
14 demonstrated that this need is alleviated by implementation of the ATC Arrowhead
15 Alternative, the existing phase shifting transformer may need to remain in place and a
16 second phase shifting transformer may need to be installed for the ATC Arrowhead
17 Alternative to maintain the flow control on this interface. As discussed in the Direct
18 Testimony of Company witness Mr. Winter, the determination of whether or not this
19 critical transmission asset is necessary as part of the ATC Arrowhead Alternative is not
20 trivial and cannot be finalized without thorough and coordinated regional transmission
21 planning studies involving MISO, ATC, Minnesota Power and other impacted utilities.
22 To date, the Company is not aware that ATC has completed or even initiated any such
23 studies to justify excluding a phase shifting transformer from its alternative. The
24 Company estimates the facility cost for its proposed configuration of the HVDC
25 Modernization Project is \$40 to \$70 million, whereas the cost for the facilities needed
26 for the ATC Arrowhead Alternative, including a potential phase shifting transformer, is
27 \$60 to \$110 million.

28

1 **Q. Has the Company prepared a comparison from a customer rate perspective?**

2 A. Yes and even assuming that the ATC Arrowhead Alternative is able to apply the same
3 federal and state grant funding as Minnesota Power’s proposed configuration of the
4 HVDC Modernization Project, the ATC Arrowhead Alternative has higher rate impacts
5 for Minnesota Power’s customers (with the phase shifting transformer).

6
7 Minnesota Power has prepared several different rate impact scenarios depending on
8 whether or not federal and state grants are awarded for the Project and ATC Arrowhead
9 Alternative. Assuming that \$75 million in DOE and state awards are applied to
10 Minnesota Power’s Project, the rate impact for the average residential customer for the
11 first 12 months following Project in-service would range from \$7.64 to \$9.13 per month.
12 For Large Power customers, the estimated rate impact for Minnesota Power’s Project
13 for the first 12 months following in-service would range from approximately 1.022¢ to
14 1.221¢ per kilowatt-hour (“kWh”) of energy.

15
16 To calculate the rate impact of the ATC Arrowhead Alternative, Minnesota Power first
17 needed to develop a cost estimate for this alternative. Minnesota Power’s cost estimate
18 and assumptions that were included in its rate impact calculations for the ATC
19 Arrowhead Alternative are outlined in the Company’s supplemental response to LPI IR
20 12 which is attached to the Direct Testimony of Mr. Winter as Schedule 2. Even
21 assuming that the \$75 million in DOE and state awards are applied to the ATC
22 Arrowhead Alternative, the rate impact for the average residential customer for the first
23 12 months following Project in-service would range from \$7.93 to \$9.55 per month. For
24 Large Power customers, the estimated rate impact for the ATC Arrowhead Alternative
25 for the first twelve months following in-service would range from approximately 1.061¢
26 to 1.277¢ per kWh of energy.

1 **Q. Do you have any concerns with ATC's proposed costs for the 345 kV**
2 **interconnection?**

3 A. Yes, the Company has significant concerns with ATC's estimated cost for the 345 kV
4 interconnection and believes it is both underdeveloped and may be inaccurately low.
5 Some of the concerns relate to the handling and management of the phase shifting
6 transformer issue, appropriate costs for procurement of new 345 kV assets, ensuring
7 labor costs reflect those costs required by current scope of the DOE GRIP Grant the
8 Company is negotiating.

9
10 **Q. Please explain the disagreement regarding whether or not a phase shifting**
11 **transformer is necessary for the ATC Alternative.**

12 A. It is Minnesota Power's position that a phase shifting transformer is needed at the
13 Arrowhead Substation if the ATC Arrowhead Alternative is selected whereas ATC has
14 stated that this transformer is not needed. The 800 MVA transfer constraint still exists
15 at this time and control of East-West power flow would likely still be necessary for the
16 ATC Alternative. Mr. Winter provides more technical detail relating to the need of the
17 phase shifting transformer in his Direct Testimony.

18
19 **Q. What is the basis of your concerns that ATC's cost estimate provided in this**
20 **proceeding is too low?**

21 A. The accuracy of cost estimates improves as a project moves further along in the planning
22 and design phase. ATC has not completed detailed planning related to the ATC
23 Arrowhead Alternative to the same level as Minnesota Power has for its proposed
24 Project. In particular, ATC has not coordinated with Minnesota Power to design the
25 connections to the new HVDC converter station or the Minnesota Power Arrowhead
26 230 kV/115 kV Substation and does not have specific cost estimates related to detailed
27 construction elements. This lack of detailed planning and design for the ATC
28 Arrowhead Alternative is demonstrated by the fact that ATC's design of the facility has
29 continued to change during this regulatory proceeding. The lack of detailed plans, as
30 well as the lack of interaction with the Company on configurations and construction

1 details at the site, creates real concerns that significant costs are missing from the ATC's
2 cost estimate for the ATC Arrowhead Alternative.

3
4 **Q. Please explain how ATC's cost recovery is different from Minnesota Power's cost**
5 **recovery.**

6 A. Minnesota Power would intend to recover costs for this Project through the
7 Transmission Cost Recovery Rider and applicable FERC recovery through MISO
8 Attachment O, where ATC stated they would seek recovery through a lump sum
9 payment with a tax gross-up.

10
11 **Q. Are there any other cost concerns you have with ATC's Arrowhead Alternative?**

12 A. ATC's originally proposed construction for the ATC Arrowhead Alternative proposes
13 to locate the 345 kV transmission line along much of the existing HVDC Line right-of-
14 way. This may result in prolonged outages for Minnesota Power customers – much
15 longer than would be anticipated for construction of Minnesota Power's proposed
16 configuration of the HVDC Modernization Project. Any replacement power costs for
17 outages would be paid entirely by Minnesota Power customers through the Fuel and
18 Purchased Energy Adjustment Rider, while these customers would not be receiving the
19 benefits from the Company's low cost North Dakota wind facilities.

20
21 However, ATC revised its proposed alignment and no longer would require overtaking
22 the full length of the HVDC Line right-of-way in this area. ATC has stated that any
23 outage of the HVDC Line would be limited to the five days needed by Minnesota Power
24 to reconfigure the HVDC Line termination to the new St. Louis County HVDC
25 Converter Station. While this revised alignment appears to avoid outages of the HVDC
26 Line, this revised alignment would require crossing Minnesota Power's Arrowhead –
27 Bear Creek 230 kV transmission line and an outage of this line during construction. No
28 such crossing is necessary for Minnesota Power's configuration of the HVDC
29 Modernization Project. This is discussed further in the Direct Testimony of Company
30 witness Mr. Winter.

1
2 Due to this additional outage requirement for the ATC Arrowhead Alternative,
3 Minnesota Power respectfully requests that the Commission consider an order point that
4 would require ATC to cover the cost of any replacement power costs necessary for the
5 construction of this crossing.
6

7 2. Recovery through Transmission Cost Recovery Rider

8 **Q. Would Minnesota Power propose to recover the costs of the HVDC Modernization**
9 **Project through the TCR?**

10 A. Yes, Minnesota Power would seek recovery of HVDC Modernization Project costs
11 through the TCR, whether Minnesota Power's proposed configuration is approved or if
12 the Commission orders construction of the ATC Arrowhead Alternative.
13

14 **Q. What would this mean for recovery of costs if the Commission orders the ATC**
15 **Arrowhead Alternative be constructed for the HVDC Modernization Project?**

16 A. The Company would need to compensate ATC for the construction of their facilities
17 with the tax gross-up and then it would be added to the HVDC Modernization project
18 costs with Minnesota Power ratepayers paying the entire cost of the project, despite the
19 likely significant benefits to Wisconsin ratepayers. These costs would then be added to
20 the TCR.
21

22 **Q. Are there any conditions Minnesota Power would ask be included in a certificate**
23 **of need if the Commission orders the Company to construct the HVDC**
24 **Modernization Project with the ATC 345 kV Arrowhead Alternative?**

25 A. Yes. In the event the Commission orders Minnesota Power to construct the 345 kV
26 interconnection that ATC has proposed as the ATC Arrowhead Alternative, Minnesota
27 Power respectfully requests that the Certificate of Need or Route Permit include the
28 following conditions:

- 29 • a condition affirming the ownership of the various equipment necessary for the
30 HVDC Modernization Project equipment consistent with what has been

1 included in my Direct Testimony and applicable discovery responses attached
2 to the Direct Testimony of Mr. Winter;

- 3 • a condition affirming that ATC is subject to all Certificate of Need and Route
4 Permit standard and project-specific conditions;
- 5 • a condition that ATC must comply with all compliance requirements set forth in
6 the Cooperative Agreement for the federal grant from the DOE. In the event that
7 ATC's action or inaction results in any loss of funding, ATC should be required
8 to provide the financial support to make up for any loss of funding;
- 9 • a condition that ATC agree that Minnesota Power be granted any and all
10 independent audit rights related to ATC's construction, procurement, and
11 contracting activities for any portion of the ATC Arrowhead alternative to
12 ensure Minnesota Power can comply with all administrative conditions of the
13 federal grant process;
- 14 • a condition that ATC shall be responsible for any replacement power costs
15 incurred in the event ATC requires outages of any Minnesota Power DC or AC
16 transmission facilities longer than the estimates provided by ATC in this
17 proceeding;
- 18 • a condition that ATC shall provide monthly project status and cost updates to
19 Minnesota Power with the first update to be provided no later than fourteen days
20 after the date of the Commission order; and
- 21 • a condition that any cost overruns from estimates provided in this proceeding
22 for the 345 kV interconnection be recoverable in the TCR and when the
23 Company moves the HVDC Modernization Project to base rates. Given that
24 Minnesota Power would be required to pay ATC for the 345 kV interconnection
25 facilities and the Commission has no ratemaking or cost oversight of ATC at
26 this time, Minnesota Power would be required to pay whatever the final cost is
27 of the ATC Arrowhead Alternative to ATC, whether or not that amount is within
28 the estimate that ATC has provided in this proceeding. In the alternative, in the
29 event the Commission orders construction of the ATC Arrowhead Alternative
30 345 kV interconnection infrastructure, that Minnesota Power cannot pay (and

ATC cannot charge Minnesota Power for) any amount in excess of the estimate that ATC has provided in this proceeding, even if additional costs are necessary to study, design, construct, and interconnect the 345 kV alternative.

V. CONCLUSION

Q. Does this complete your testimony?

A. Yes.

MINNESOTA POWER

Utility Information Request

☐ Nonpublic ☒ Public

Docket No.: **E015/CN-22-607**
E015/CN-22-611

Date of Request: December 22, 2023

Requested From: American Transmission Company
LLC

Response Due: January 2, 2024
Extension To: January 5, 2024

SEND RESPONSE VIA EMAIL TO: discoverymanager@mnpower.com

Request by: David Moeller
Email Address(es): dmoeller@allete.com
Phone Number(s): (218)723-3963

Request Number: 009
Topic: Information Requests
Reference:

If your response includes any executable files or spreadsheets, please provide those attachments in both searchable PDF and original form with all formulas and links intact.

REQUEST: Please describe any efforts ATC has undertaken to obtain state or federal grants to reduce the overall costs of the ATC Arrowhead Alternative. Please provide all disclosures MP made to ATC personnel regarding applying for federal funding for the HVDC Terminal Expansion option at 345kV. Please describe all efforts made to coordinate efforts to obtain state or federal grants for this alternative. Please describe ATC's general practices and incentives to reduce costs on capital projects including for projects outside the State of Wisconsin.

RESPONSE: ATC objects to this request as seeking information that is irrelevant to this proceeding, overbroad as to time, vague, compound, and to the extent it seeks information that is publicly available or equally available to Minnesota Power. Subject to these objections, ATC responds as follows:

ATC has not applied for any state or federal grants related to Docket Numbers E015/CN-22-607 and 611.

To be completed by responder

Response Date: January 5, 2024
Response by: Robert McKee, Strategic Projects & Execution Director
Email Address: rmckee@atcllc.com
Phone Number: (608) 877-7052

MINNESOTA POWER

Utility Information Request

☐ Nonpublic ☒ Public

Docket No.: **E015/CN-22-607**
E015/CN-22-611

Date of Request: December 22, 2023

Requested From: American Transmission Company
LLC

Response Due: January 2, 2024
Extension To: January 5, 2024

SEND RESPONSE VIA EMAIL TO: discoverymanager@mnpower.com

Request by: David Moeller
Email Address(es): dmoeller@allete.com
Phone Number(s): (218)723-3963

Request Number: 007
Topic: Information Requests
Reference:

If your response includes any executable files or spreadsheets, please provide those attachments in both searchable PDF and original form with all formulas and links intact.

REQUEST: Please provide a summary of any and all high-voltage transmission projects ATC has participated in constructing (as sole owner, joint owner, or operator) that required either a Certificate of Public Convenience and Need from the Public Service Commission of Wisconsin or a Certificate of Need and/or Route Permit from the Minnesota Public Utilities Commission.

- a. State regulatory docket number;
- b. Cost estimate for the project approved by the state regulatory authority (or as-provided to the state regulatory authority prior to obtaining such approval to proceed with the project if the state regulatory authority did not explicitly approve the cost estimate);
- c. The proposed in-service date contemplated at the time of the state regulatory authority approval;
- d. The final costs incurred for the project (or incurred as of the date of this information request, if not yet complete); and
- e. The final in-service date for the project (or the planned in-service date as of this information request, if not yet complete).

Please also provide a summary of any transmission project proceedings where either (i) ATC offered an alternative project that was not the primary project proposed by another entity; or (ii) another entity offered an alternative project that was not the primary project proposed by ATC.

- i. State regulatory docket number
- ii. When the alternative project was introduced into the proceeding
- iii. Justification for introduction of the alternative project by either ATC or another entity
- iv. How (or if) the alternative project was evaluated by the state regulatory authority
- v. If the alternative project was ultimately selected by the state regulatory instead of the proposed project, and why

MINNESOTA POWER

Utility Information Request

☐ Nonpublic ☒ Public

Docket No.: **E015/CN-22-607**

Date of Request: December 22, 2023

E015/CN-22-611

Requested From: American Transmission Company
LLC

Response Due: January 2, 2024

Extension To: January 5, 2024

IR Number 007

-
- vi. The final cost and in-service date of the approved alternative project, compared to the cost and in-service date for the alternative project at the time it was approved by the state regulatory authority

RESPONSE: ATC objects to this request as seeking information that is irrelevant to this proceeding, overbroad as to time, vague, compound, and to the extent it seeks information that is publicly available or equally available to Minnesota Power. Subject to these objections, ATC responds as follows:

This information request does not specify a time period for which information is being sought, and ATC limits its responses to proceedings before the Public Service Commission of Wisconsin ("PSCW") or Minnesota Public Utilities Commission ("MPUC") within the last five years. ATC has made no filings for a Certificate of Need and/or Route Permit from the MPUC. Dockets in which ATC has applied for a certificate of public convenience and necessity from the PSCW are publicly available online on the PSCW's Electric Records Filing system (<https://apps.psc.wi.gov/>). The docket numbers are 137-CE-194 and 137-CE-195. Information concerning the cost estimate, proposed in-service date, final costs, final in-service date, and any alternatives under consideration for the projects that were the subject of those proceedings are also publicly available in filings made within those publicly available electronic filing systems.

Within the last five years, ATC has not participated in any transmission project proceedings before the PSCW or MPUC in which ATC offered an alternative project that was not the primary project proposed by the applicant in that proceeding.

To be completed by responder

Response Date: January 5, 2024

Response by: Patrisha Smith, Manager State Regulatory Affairs & Associate General Counsel

Email Address: psmith@atcllc.com

Phone Number: (262) 506-6145

**AMERICAN TRANSMISSION COMPANY LLC AND ATC
MANAGEMENT INC.**

UTILITY INFORMATION REQUEST

Docket Numbers: OAH 5-2500-39600; Date of Request: January 17, 2024
 MPUC E-015/CN-22-607;
 MPUC E-015/TL-22-611

Requested From: Minnesota Power Response Due: January 29, 2024

By: American Transmission Company LLC

Information Request No. 31.

Please provide an overall design, engineering, planning, right-of-way acquisition, procurement, and construction schedule for the HVDC Modernization Project. As part of that schedule, please provide the following information:

- a. Have You begun procuring equipment and materials for the Project? If so, please provide a detailed description of the current status of those procurement activities and identify the approximate date for delivery of those equipment and/or materials. If not, please identify the approximate date You intend to commence procuring equipment and materials for the Project.
- b. Please identify the Project equipment and/or materials that have the longest individual leadtime and the approximate leadtime for obtaining delivery of such equipment and/or materials.
- c. Do You intend to conduct any additional routing studies, environmental studies, or other field work for the Project after the Commission makes a decision in this proceeding? If so, please describe what additional studies or field work You intend to conduct and the approximate date that such studies and/or field work will be completed.

Response:

See ATC IR 031.01 Attach for a high-level Project schedule.

Response by: Peter Schommer

Title: Manager – Power Delivery & Asset Management

Department: Transmission

Telephone: 218-355-2639

**AMERICAN TRANSMISSION COMPANY LLC AND ATC
MANAGEMENT INC.**

UTILITY INFORMATION REQUEST

Docket Numbers: OAH 5-2500-39600; Date of Request: January 17, 2024
 MPUC E-015/CN-22-607;
 MPUC E-015/TL-22-611

Requested From: Minnesota Power Response Due: January 29, 2024

By: American Transmission Company LLC

-
- a. Minnesota Power has commenced procurement activities for the Project. Our procurement strategy has been to have all AC equipment on site and installed, including substation and transmission line sections, by Q3 2028 as shown in attachment ATC IR 031.01 Attach. The early completion of this work is needed to realize any potential schedule acceleration by the HVDC supplier should they offer an in-service date that is better than the currently guaranteed April 2030. See Minnesota Power's response to ATC IR 004 part (b) for details pertaining to the procurement of the 345 kV/230 kV St. Louis County Substation transformers. Minnesota Power has issued a Request for Proposal for 230 kV breakers for the Nelson Lake Substation and expects to issue a Purchase Order in the first quarter of 2024. Minnesota Power will issue a Request for Proposal for the remaining breakers necessary for AC interconnecting facilities, including the St. Louis County substation breakers, in the second quarter of 2024 for an expected delivery in 2027. Notably, some of these breakers require special considerations such as pre-insertion resistors that substantively increase their lead time. Pre-insertion resistors will be necessary for any breakers that will be utilized to energize large power transformers.
- b. The equipment with the longest individual lead times for the Project are the transformers and breakers. Currently, the lead time for the 345 kV/230 kV transformers is three years. The lead time for standard 230 kV breakers is two years. The most recent feedback Minnesota Power has received on the lead time for standard 345 kV breakers is 150 weeks (nearly three years), with an extra 10-15 weeks of additional lead time for breakers that have special considerations like pre-insertion resistors.

Response by: Peter Schommer

Title: Manager – Power Delivery & Asset Management

Department: Transmission

Telephone: 218-355-2639

**AMERICAN TRANSMISSION COMPANY LLC AND ATC
MANAGEMENT INC.**

UTILITY INFORMATION REQUEST

Docket Numbers: OAH 5-2500-39600; Date of Request: January 17, 2024
 MPUC E-015/CN-22-607;
 MPUC E-015/TL-22-611

Requested From: Minnesota Power Response Due: January 29, 2024

By: American Transmission Company LLC

-
- c. Upon receiving a decision from the Commission, normal permitting activities with federal, state, and local agencies will commence, if not already in process. This will also include final staking and survey work for the HVDC and AC facilities. Route studies and environmental studies are complete.

Response by: Peter Schommer

Title: Manager – Power Delivery & Asset Management

Department: Transmission

Telephone: 218-355-2639

Capital Project High-Level Timeline

Project	Capital Cost	Task	Duration	Start	End	Status	2023				2024				2025				2026				2027				2028				2029				2030				Notes:
							Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4					
High-Voltage Direct Current Modernization (HVDC)	L: \$660M T: \$800M Hi: \$940M	Preferred Supplier Agreement - Siemens DOE Funding Application	Milestone 15 Months		Q1 2023 Q4 2022	✓ In Process																																	
		DOE Grant Application Submitted	Milestone		Q1 2023	✓																																	
		Receive DOE Funding Award Notification	Milestone		Q3 2023	✓																																	
		Negotiate DOE Funding	Milestone	Q3 2023	Q1 2024	In Process																																	
		MN & ND Land Acquisition	18 Months	Q1 2023	Q2 2024	In Process																																	
		MN PUC Certificate of Need	21 Months	Q1 2023	Q3 2024	In Process																																	
		Submit MN CON	Milestone		Q2 2023	✓																																	
		Order accepting application as complete		Q3 2023	Q3 2023	✓																																	
		Public info/scoping meeting	6 Months	Q3 2023	Q4 2023	✓																																	
		MPUC Hearings	3 Months	Q4 2023	Q4 2023	✓																																	
		Administrative Law Judge Report Due	3 Months	Q2 2024	Q2 2024																																		
		MN PUC Approval	Milestone		Q3 2024																																		
		ND Permit Application	18 Months	Q3 2023	Q4 2024	In Process																																	
		Submit ND Permit	Milestone		Q1 2024	In Process																																	
		ND Permit Approval	Milestone		Q4 2024																																		
		Nelson Lake Scoping / GRE Coordination	9 Months	Q3 2023	Q1 2024	In Process																																	
		St. Louis County Scoping	6 Months	Q4 2023	Q1 2024	In Process																																	
		T-Line Upgrade Scoping	6 Months	Q4 2023	Q1 2024	In Process																																	
		Contract T-Line Detail Engineer	6 Months	Q4 2023	Q1 2024	In Process																																	
		Contract Substation Detail Engineer	6 Months	Q4 2023	Q1 2024	In Process																																	
		Critical Long-Lead Time Material Procurement	48 Months	Q4 2023	Q3 2027	In Process																																	
		Order Nelson Lake Breakers (2 yr. lead)	9 Months	Q3 2023	Q1 2024	In Process																															(9) 230 kV breakers; delivery February 1, 2026. Needed for '26 in-service.		
		Order St. Louis County Breakers (2 yr. lead)	9 Months	Q3 2023	Q1 2024	In Process																														(3+1 spare) 230kv breakers, delivery 2027			
		Order Nelson Lake Transformers (3 yr. lead)	9 Months	Q3 2023	Q1 2024	In Process																														(3+1 spare) 345/230kV, delivery August 2027, Hyundai			
		Order St. Louis County Transformers (3 yr. lead)	9 Months	Q3 2023	Q1 2024	In Process																														(3+1 spare) 345/230kV, delivery August 2027, Hyundai			
		Red River Flood Diversion Project (T-Line)				In Process																																	
		Planning, Scoping, Engineering	30 months	Q3 2024	Q4 2025	In Process																																	
		Construction	9 months	Q1 2026	Q3 2026																																		
		Nelson Lake 230 kV Substation Construction	18 Months	Q1 2026	Q2 2026																																		
		Nelson Lake 345 kV Substation Construction	18 Months	Q3 2026	Q4 2027																																		
		St. Louis County 345/230 kV Substation Construction	18 Months	Q3 2026	Q4 2027																																		
		East Oliver Switching Station construction	18 Months	Q3 2026	Q4 2027																																		
		North Dakota interconnection line construction	18 Months	Q3 2026	Q4 2027																																		
		Minnesota interconnection line construction	18 Months	Q3 2026	Q4 2027																																		
		MP Studies	24 Months	Q1 2023	Q4 2024	In Process																																	
		Technical Workstream (MP & Siemens)	12 Months	Q2 2023	Q1 2024	In Process																																	
		Siemens FEED Study Coordination	33 Months	Q2 2024	Q4 2026																																		
		Final Notice to Proceed (Siemens)	Milestone		Q4 2026																																		
		Converter Station Manufacturing (Siemens)	33 Months	Q4 2026	Q2 2029																																		
		MN & ND Converter Station Construction	33 Months	Q3 2027	Q1 2030																																		
		MN & ND Converter Station Commissioning	3 Months	Q1 2030	Q1 2030																																Siemens guaranteed substantial completion April 2030		
		Operation / COD	Milestone	Q2 2030	Cont.																																		
																																					Operation ->		