Docket No. E999/CI-15-755 Information Request MPUC-005 Attachment B.2., Pages 1 of 180

Standard for Electric Installation and Use





TABLE OF CONTENTS

INTRODUCTION	3
FOREWORD	4
EXCEPTION FORM	5
REVISION FORM	6
1. DEFINITIONS	7
2. GENERAL INFORMATION	.13
2.1. EFFECTIVE DATE	.13
2.2. INTENT	.13
2.3. APPLICATION FOR SERVICE	. 14
2.4. RATE SCHEDULES	
2.5. SERVICE AND LIMITATIONS	
2.6. CLOSED LOOP / FLAT TAP / JUMPERED	
2.7. CONNECTION	. 16
2.8. CUSTOMER-OWNED METER EQUIPMENT RESTRICTIONS	
2.10. EASEMENTS FOR COMPANY'S FACILITIES	
2.11. CUSTOMER'S RESPONSIBILITY 2.12. CUSTOMER-OWNED FACILITIES	
2.12. COSTOMER-OWNED FACILITIES	
2.13. SAFETT	. 19
3. CHARACTER OF SERVICE AVAILABLE	
3.1. TYPES OF SERVICE	.23
3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE	.23 .24
3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE	.23 .24 .24
3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE	.23 .24 .24
3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE	.23 .24 .24 .24
 3.1. TYPES OF SERVICE	.23 .24 .24 .24 .24 .25
 3.1. TYPES OF SERVICE	.23 .24 .24 .24 .24 .25 .25
 3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE 4. SERVICE FACILITIES 4.1. SERVICES 4.2. OVERHEAD SERVICE 4.3. UNDERGROUND SERVICE 	.23 .24 .24 .24 .25 .25 .26 .29
 3.1. TYPES OF SERVICE	.23 .24 .24 .24 .25 .25 .26 .29 .31
 3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE 4. SERVICE FACILITIES 4.1. SERVICES 4.2. OVERHEAD SERVICE 4.3. UNDERGROUND SERVICE 4.4. SERVICE LATERAL SIZES (FOR BALANCED LOAD): 4.5. CONDUIT SIZING CHART: 	.23 .24 .24 .24 .25 .25 .26 .29 .31 .31
 3.1. TYPES OF SERVICE	.23 .24 .24 .24 .25 .25 .26 .29 .31 .31 .32
 3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE 4. SERVICE FACILITIES 4.1. SERVICES 4.2. OVERHEAD SERVICE 4.3. UNDERGROUND SERVICE 4.4. SERVICE LATERAL SIZES (FOR BALANCED LOAD): 4.5. CONDUIT SIZING CHART: 4.6. TRANSFORMER INSTALLATIONS - NETWORK VAULTS 4.7. TRANSFORMER INSTALLATIONS - PAD-MOUNTED 	.23 .24 .24 .24 .25 .25 .26 .29 .31 .31 .32 .33
 3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE 4. SERVICE FACILITIES 4.1. SERVICES 4.2. OVERHEAD SERVICE 4.3. UNDERGROUND SERVICE 4.4. SERVICE LATERAL SIZES (FOR BALANCED LOAD): 4.5. CONDUIT SIZING CHART: 4.6. TRANSFORMER INSTALLATIONS - NETWORK VAULTS 4.7. TRANSFORMER INSTALLATIONS - PAD-MOUNTED. 4.8. POINT OF DELIVERY 	.23 .24 .24 .24 .25 .25 .26 .29 .31 .32 .33 .33
 3.1. TYPES OF SERVICE. 3.2. METER SOCKETS FOR TYPES OF SERVICE	.23 .24 .24 .25 .25 .26 .29 .31 .31 .32 .33 .33 .34
 3.1. TYPES OF SERVICE. 3.2. METER SOCKETS FOR TYPES OF SERVICE. 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE. 4. SERVICE FACILITIES. 4.1. SERVICES. 4.2. OVERHEAD SERVICE. 4.3. UNDERGROUND SERVICE. 4.4. SERVICE LATERAL SIZES (FOR BALANCED LOAD): 4.5. CONDUIT SIZING CHART: 4.6. TRANSFORMER INSTALLATIONS - NETWORK VAULTS 4.7. TRANSFORMER INSTALLATIONS - PAD-MOUNTED. 4.8. POINT OF DELIVERY 4.9. CUSTOMER-OWNED SERVICE CONDUCTORS (NOT APPLICABLE IN WI/MI) 4.10. METERING 	.23 .24 .24 .25 .26 .29 .31 .32 .33 .33 .33 .34 .35
 3.1. TYPES OF SERVICE. 3.2. METER SOCKETS FOR TYPES OF SERVICE. 3.3. DISTRIBUTION (PRIMARY) SERVICE	.23 .24 .24 .25 .26 .29 .31 .32 .33 .33 .34 .35 .42
 3.1. TYPES OF SERVICE. 3.2. METER SOCKETS FOR TYPES OF SERVICE. 3.3. DISTRIBUTION (PRIMARY) SERVICE. 3.4. TRANSMISSION SERVICE. 4. SERVICE FACILITIES. 4.1. SERVICES. 4.2. OVERHEAD SERVICE. 4.3. UNDERGROUND SERVICE. 4.4. SERVICE LATERAL SIZES (FOR BALANCED LOAD): 4.5. CONDUIT SIZING CHART: 4.6. TRANSFORMER INSTALLATIONS - NETWORK VAULTS. 4.7. TRANSFORMER INSTALLATIONS - PAD-MOUNTED. 4.8. POINT OF DELIVERY. 4.9. CUSTOMER-OWNED SERVICE CONDUCTORS (NOT APPLICABLE IN WI/MI) 4.10. METERING. 4.11. TEMPORARY SERVICE. 4.12. PRIMARY METER INSTALLATIONS 	.23 .24 .24 .25 .26 .29 .31 .32 .33 .33 .34 .35 .42 .44
 3.1. TYPES OF SERVICE	.23 .24 .24 .25 .26 .29 .31 .32 .33 .34 .35 .42 .44
 3.1. TYPES OF SERVICE 3.2. METER SOCKETS FOR TYPES OF SERVICE 3.3. DISTRIBUTION (PRIMARY) SERVICE 3.4. TRANSMISSION SERVICE 4. SERVICE FACILITIES	.23 .24 .24 .25 .26 .29 .31 .32 .33 .33 .34 .35 .42 .44 .45 .48
 3.1. TYPES OF SERVICE	.23 .24 .24 .25 .26 .29 .31 .32 .33 .33 .34 .42 .44 .45 .50

4.17. COLD SEQUENCE METERING	
5. TRANSFORMERS	55
5.1. GROUNDING	55 56
6. UTILIZATION EQUIPMENT6	35
6.1. THREE-PHASE VOLTAGE UNBALANCE66.2. HARMONICS66.3. POWER FACTOR ADJUSTMENT66.4. MOTORS66.5. NON-LINEAR LOADS66.6. WATER PIPE THAWING66.7. SPECIAL APPARATUS76.8. LOAD BALANCE77. SPECIAL TYPES OF SERVICE7	55 57 59 59 70 70
7.1. NON-STANDARD CONSTRUCTION	
7.2. DATA PULSES	
8. DISTRIBUTED GENERATION	72
8.1. INTERCONNECTION REQUIREMENTS	73

<u>Drawings</u>

Section TR: Transformer Rated Metering Drawings. 2.1-2.8 Section PM: Primary Metering Drawings. 3.1-3.8 Section TM: Temporary Metering Drawings. 4.1-4.6 Section IR: Interruptible Rate Drawings. 5.1-5.6 Section CC: Connection Cabinet Drawings. 6.0-6.6 Section CC: Transformer Pad Drawings. 6.7-6.106 Section CR: Clearance Requirements Drawings. 7.1-7.13	Section SC: Self-Contained Metering Drawings	
Section TM: Temporary Metering Drawings 4.1-4.6 Section IR: Interruptible Rate Drawings 5.1-5.6 Section CC: Connection Cabinet Drawings 6.0-6.6 Section CC: Transformer Pad Drawings 6.7-6.106	Section TR: Transformer Rated Metering Drawings	2.1-2.8
Section IR: Interruptible Rate Drawings	Section PM: Primary Metering Drawings	
Section CC: Connection Cabinet Drawings	Section TM: Temporary Metering Drawings	
Section CC: Transformer Pad Drawings		
	Section CC: Connection Cabinet Drawings	6.0-6.6
	Section CC: Transformer Pad Drawings	6.7-6.106

INTRODUCTION

Xcel Energy is dedicated to providing safe, economical, and reliable service to its customers. It is the policy of the Company to serve all its customers in an orderly manner and assist in securing a more beneficial use of electricity. The "Xcel Energy Standard for Electric Installation and Use" contains the requirements and uniform standards necessary to achieve this policy. Uniform enforcement of these standards throughout the Company will expedite service connections and treat each of our customers equally and fairly. Therefore, our employees are instructed and obligated to require adherence to these standards and procedures.

The "Xcel Energy Standard for Electric Installation and Use" is a valuable timesaving publication that will help to determine the necessary requirements for customers' wiring intended to be connected to the Company's distribution system. This publication will help you work more efficiently and aid in getting a utility connection established with minimum inconvenience. It also provides for the safety and reliability of our customers and safe working conditions for our personnel.

The Company's complete Rules and Regulations are contained in its tariffs as filed with the various state regulatory agencies. Service furnished by the Company is subject to the Company's "Xcel Energy Standard for Electric Installation and Use", the National Electrical Safety Code, and the Rules and Regulations of these Regulatory Commissions.

Xcel Energy, Inc.

Briston Jones, Manager*System Performance & Standards

FOREWORD

This publication has been prepared to assist you in planning your electrical installation. The uniform standards contained in this publication are necessary to enable the Company to serve all its customers in an orderly manner and expedite service connections.

New, rewired, altered, or repaired wiring installations intended for connection to the Company's distribution system shall comply with the rules of the Company, the *National Electrical Code*[®], and any other codes or regulations in effect in the area served. The Company does not assume the function of inspecting customers' wiring for adequacy, safety, or compliance with the electrical codes. Such responsibility remains with the customer and inspectors.

Questions concerning large and/or complicated electrical projects should be directed to the Company's Builders Call Line *in advance of construction and/or purchase of equipment* @ 800.628.2121 or Meter Technical Support @ 800.422.0782. This will reduce the risk of project delays or expensive changes during construction.

A Company Representative will discuss requests for exceptions to these standards with the customer. Only requests for exceptions based on extenuating circumstances will be evaluated. The exception request shall be submitted in writing *in advance of construction and/or purchase or equipment*. Exception requests are evaluated on a case-by-case basis and will be responded to in writing. Exceptions will not be granted verbally. The written response will indicate whether the request has been granted or denied. Exceptions shall be submitted to the following:

- > To request an exception to our policy in MN, ND, or SD, please send completed form to:
 - Service Policy Consultant 825 Rice Street St. Paul, MN 55117
- > To request an exception to our policy in WI or MI, please send completed form to:
 - Service Policy Consultant P.O. Box 8 Eau Claire, WI 54702
- > To request an exception to our policy in CO, TX, or NM, please send completed form to:
 - Service Policy Analyst 5460 W. 60th Street Arvada, CO 80003

Customers may email exception requests to <u>EMStandardsExceptionRequest@xcelenergy.com</u>.

Due to constant progress in the development of materials and processes, the Company reserves the right to revise this publication from time to time. Users of this book who notice better processes of providing services are encouraged to submit suggestions and/ or revisions for changes to these standards. Revisions are necessary for continued application of work practices.

If the proposed suggestions and/or revisions to the standards offer equal or better safety and reliability than the current policy, the policy will be reviewed for possible revision.

The Company's complete Rules and Regulations are contained in its Tariffs as filed with the Commission in your state.

This publication is Available at: http://www.xcelenergy.com/

Docket No. E999/CI-15-755 Information Request IRUC-005-Attachment B.2., Liges 6 of 180

Exception Form xcel energy standard for electric installation and use

APPLICATION

This form is to be used when requesting an exception to the "Xcel Energy Standard For Electric Installation and Use". Make sure to include all details and/or any additional documentation, such as installation information, one-lines or plot maps. Please print legibly, type or complete on line. Exceptions will not be granted if reliability or safety is compromised.

Project Information				
Address of job		City	State	_ ZIP
I seek an exception to the following section	(s):			
l request the following exception:				
This practice will maintain/improve safety a	nd reliability by:			
Submitter Information				
Submitter name	Company name			_ Date
Company address		_ City	State	ZIP
Phone ()	Fax ()			
Mail to the OpCo address below or Email to	EMStandardsExceptionRequest	@xcelenergy.com		
For: Wisconsin, Michigan Service Policy PO Box 8 Eau Claire, WI 54702 Fax: 715-852-5456	Minnesota, South Dakota Service Policy 825 Rice Street St. Paul, MN 55117 Fax: 612-573-1708	and North Dakota	Colorado, Texas and No Service Policy 5460 W. 60th Ave. Avarda, CO 80003 Fax: 303-425-3888	ew Mexico

xcelenergy.com | © 2013 Xcel Energy Inc. | Xcel Energy is a registered trademark of Xcel Energy Inc. | Northern States Power Company-Minnesota, Northern States Power Company-Wisconsin, Public Service Company of Colorado and Southwestern Public Service Company, Xcel Energy Companies. | 13-03-226

Revision Form xcel energy standard for electric installation and use

This form is to be used when requesting a revision to the "Xcel Energy Standard For Electric Installation and Use". Make sure to include all details and/or any additional documentation, such as Section, page number and illustrations. Please print legibly, type or complete on line. Revisions will not be granted if reliability or safety is compromised.

I seek a revision to the following section(s):

I request the following revision:

This practice will maintain/improve safety and reliability by:

Submitter Information)	
Submitter name	Company name	Date
Company address	City	State ZIP
Phone ()	Fax ()	

Mail to the address below or Email to EMStandardsExceptionRequest@xcelenergy.com

For: Wisconsin, Michigan Service Policy PO Box 8 Eau Claire, WI 54702 Fax: 715-852-5456

. .

. .

Minnesota, South Dakota and North Dakota Service Policy 825 Rice Street St. Paul, MN 55117 Fax: 612-573-1708 Colorado, Texas and New Mexico Service Policy 5460 W. 60th Ave. Avarda, CO 80003 Fax: 303-425-3888

SECTION 1

1. DEFINITIONS

Note: The following definitions are furnished for the appropriate interpretation of this document and are not necessarily universally accepted definitions.

1.1. ACCESS POINT

The point defined by the intersection of the customer's property line and the Company-owned conductors crossing it, which serves that customer. When a customer is to be served from a distribution line in an easement on the customer's property, the access point is the pole for overhead (OH), the switch cabinet bay for primary underground (UG), or the splice box or pedestal for secondary underground (UG) from which the Company-owned conductors will be fed.

1.2. <u>AGENT</u>

One who is authorized to act for another under a contract or relation of agency, for the Company or the customer.

1.3. ALTERED

Replacing major components or any integral part of a meter socket, current transformer cabinet, riser, mast, line or load side conductor, relocating electric service equipment, (including storm damage).

1.4. AMR - AUTOMATED METER READING

An automated method of reading electric registers (indexes).

1.5. APPLICANT

The property owner, lessee, sub-lessee, their agent and/or contractor applying for electric service from the Company.

1.6. AUTHORIZED CLOSED LOOP

Authorized use of electric service that is temporarily not being metered. See definition for CLOSED LOOP).

1.7. BUS DUCT

A preassembled unitized device containing secondary electrical bus.

1.8. CAPTIVE FASTENER

A fastener that is loosely held in place and can not separate from fastened object. Usually manufactured from metal with various designs.

1.9. CLASSIFICATION OF METERING

Commercial and Industrial (See definition for COMMERCIAL AND INDUSTRIAL METERING). Residential (See definition for RESIDENTIAL METERING).

1.10. CLOSED LOOP

Temporary unmetered electric service. (See definitions for FLAT TAP and JUMPERED).

1.11. COLD SEQUENCE METERING

The utilization of a disconnect device between the electric meter and the supply source. Refer to Section 4, <u>COLD SEQUENCE METERING</u>.

1.12. COMMERCIAL AND INDUSTRIAL METERING

Metering of any service used for the operation of a business, whether or not for profit, shall be considered as a commercial or industrial enterprise. Includes metering of all services other than residential.

1.13. COMMISSION

Public Utilities Commission of Colorado, Michigan Public Service Commission, Minnesota Public Utilities Commission, New Mexico Public Regulation Commission, North Dakota Public Service Commission, South Dakota Public Utilities Commission, Public Utility Commission of Texas and Wisconsin Public Service Commission.

1.14. <u>COMPANY</u>

The operating Companies of Xcel Energy SM.

1.15. COMPANY PROPERTY

All lines, wires, apparatus, instruments, meters, load management equipment, transformers, and materials supplied by the Company at its expense or under its standard policies.

1.16. COMPANY REPRESENTATIVE

The Company employee authorized to perform specific tasks.

1.17. CONDUIT

Standard tubular material used for mechanical protection of electrical systems which may be exposed, buried beneath the surface of the ground, or encased in a building structure as required. (See definition for DUCT).

NOTE: For the purpose of this publication, the terms Conduit and Duct are used interchangeably.

1.18. CONSTRUCTION ALLOWANCE

The portion of the construction cost performed by the Company at its expense.

1.19. CONSTRUCTION TRAILER

A structure built on a permanent chassis designed to be transportable which is intended for installation on a site without permanent foundation.

1.20. CONTRACTOR

Any person, company or corporation acting under contractual agreements for either the Company or for the customer.

1.21. CURRENT TRANSFORMER (CT)

An instrument transformer designed for the measurement or control of current.

1.22. CUSTOMER

The applicant or user of electric service in whose name the service with the Company is listed.

1.23. DATA PULSES

Output pulses (KYZ) generated by the electric meter for use by the Customer.

1.24. DEAD-END EQUIPMENT

Various devices used to terminate service conductors.

1.25. DIVERSION OF ELECTRICITY

Unauthorized connection to the Company's electric facilities where electric service is being used and not metered (e.g. when the electric meter has been bypassed without a closed loop authorization from the Company).

1.26. <u>DUCT</u>

Standard tubular material used for mechanical protection of electrical systems which may be exposed, buried beneath the surface of the ground, or encased in a building structure as required. (See definition for CONDUIT).

NOTE: For the purpose of this publication, the terms Conduit and Duct are used interchangeably.

1.27. <u>EMT</u>

Electric Metallic Tubing (National Electrical Code[®]).

1.28. EXCESS FACILITIES

In those instances where the Company provides distribution or metering facilities at the customer's request, in excess of the facilities necessary to supply service to the customer, the customer shall be required to contract to pay the Company for such facilities and to pay the Company annually an amount to cover the cost of insurance, replacement (or cost of removal), licenses, fees, taxes, operation, maintenance, and appropriate allocable administrative and general expenses of such excess distribution facilities.

1.29. FLAT TAP

Temporary unmetered electric service. (See definitions for CLOSED LOOP and JUMPERED).

1.30. <u>GAIN</u>

Cutting a flat spot into a pole or attaching a metal device to a pole which has a flat surface on one side.

1.31. <u>GRC</u>

Galvanized Rigid Conduit (National Electrical Code[®]).

1.32. HIGH-LEG, WILD LEG, POWER LEG

The phase having the higher phase voltage to ground on a 4-wire delta-connected service, where the midpoint of one phase winding is grounded.

1.33. HOT SEQUENCE METERING

The electric meter is connected directly to the service conductors without the use of a fault-current limiting disconnect or meter safety-switch device between the electric meter and the supply source.

1.34. ICE AND SNOW SHIELD, METER

A protective device used to prevent falling ice or snow from damaging the electric meter.

1.35. IMC

Intermediate Metallic Conduit (National Electrical Code®).

1.36. INSPECTOR

The electrical inspector of the Public Authority.

1.37. INSTRUMENT TRANSFORMER

A transformer that reproduces in its secondary circuit, the voltage or current proportional to its primary circuit.

1.38. ISOLATED TRANSFORMER BANK

A transformer bank which provides electrical service to a single customer.

1.39. JOINT USE AGREEMENT

A contractual agreement made between the Company and a third party allowing the use of Company property or facilities.

1.40. JUMPERED

Temporary unmetered electric service. (See definitions for CLOSED LOOP and FLAT TAP).

1.41. MANUFACTURED HOME

A structure which is transportable and intended for installation on a permanent foundation meeting the definition of a Manufactured Home as defined in 2011 *National Electrical Code[®]* Article 550.2, or as may be amended.

1.42. MEANS OF ATTACHMENT

Fittings used to attach service-drop conductors.

1.43. METER/METERING EQUIPMENT

The equipment necessary to measure the customer's electric energy use and demand including meter socket, instrument transformers, protective device and meter.

1.44. MOBILE HOME

A structure built on a permanent chassis designed to be transportable and intended for installation on a site without permanent foundation.

1.45. MULTIPLE METER CENTER

A pre-assembled multiple metering unit or fabricated meter center using meter sockets where two or more customers are metered at a common location.

1.46. NEC[®] - NATIONAL ELECTRICAL CODE[®] 1

A publication of the National Fire Protection Association, Inc.

1.47. <u>NESC[®] - NATIONAL ELECTRICAL SAFETY CODE[®]²</u>

A publication of the Institute of Electrical and Electronic Engineers, Inc. as adopted by ANSI.

1.48. NOMINAL VOLTAGE

Designation of the value of the normal effective difference in potential between any two appropriate conductors of the circuit.

1.49. NON-STANDARD DESIGN

Construction not conforming to the Company's standard method of design because of the customer's request. The customer may be charged for the additional cost incurred by the Company.

1.50. NRTL

Nationally Recognized Testing Laboratory

1.51. POINT OF ATTACHMENT

The point at which the service-drop conductors are attached to a building or other structure.

1.52. POINT OF DELIVERY

Point where the Company's electric facilities are first connected to the electric facilities of the customer.

1.53. PRIMARY METERING

Metering of service voltages above 480V nominal.

¹ *National Electrical Code*[®] and *NEC*[®] are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269

² National Electrical Safety Code[®] and NESC[®] are registered trademarks and service marks of the Institute of Electrical and Electronics Engineers, Inc., New York, NY 10017

1.54. PUBLIC AUTHORITY

The municipal, county, or state authorities having inspectors and jurisdiction to inspect electrical installations.

1.55. <u>PVC</u>

Polyvinyl Chloride (*National Electrical Code*[®]).

1.56. RACEWAY

Any channel for holding bus bars, cables, or wires, which is designed for this purpose.

1.57. RESIDENTIAL METERING

Metering of services used for the exclusive use of the individual customer for domestic purposes.

1.58. READILY ACCESSIBLE

An area that can be readily and safely accessed through a doorway, ramp, or stairway by a person on foot who neither exerts extraordinary physical effort nor employs special tools or devices to gain entry is considered readily accessible.

1.59. REPAIRED

Service equipment in need of any repair such as damaged meter socket, riser, mast (including storm damage).

1.60. <u>REWIRED</u>

Upgrading of any existing service equipment including secondary conductors within meter sockets, CT enclosures, cold sequence disconnects, and Primary Metering Installations.

1.61. RULES AND REGULATIONS

The rules, regulations and condition of service as filed with the Commission.

1.62. SECONDARY CONDUCTORS

That part of the Company's distribution system, which connects the secondaries of the Company's distribution transformers to the service drop or service lateral.

1.63. SECONDARY CONNECTION CABINET

Cabinet required when the number and/or size of conductors exceeds the Company's limit for terminating in a specified pad-mounted transformer.

1.64. SERVICE

The furnishing of electric energy for the exclusive use of the individual customer.

1.65. SERVICE DROP

The overhead service conductors from the last distribution pole or other aerial distribution support to and including the splices connecting to the service-entrance conductors at the building or other structure.

1.66. SERVICE-ENTRANCE CONDUCTORS, OVERHEAD SYSTEM

The service conductors between the terminals of the customer's service equipment and the point of connection to the service drop conductors.

1.67. SERVICE-ENTRANCE CONDUCTORS, UNDERGROUND SYSTEM

The service conductors between the terminals of the customer's service equipment and the point of connection to the service lateral.

1.68. SERVICE EQUIPMENT

Necessary equipment, usually consisting of a circuit breaker or fusible disconnect switch and their accessories, located near the point of entrance of the supply conductors to a building and intended to constitute the main control and means of cutoff for the supply to that building.

1.69. SERVICE LATERAL

The underground service conductors between the Company secondary distribution system and/or transformer terminals and the connection to the service-entrance conductors in a terminal box or meter socket located outside the building wall. Where the meter is located in the building and no terminal box exists outside the building, the point of connection shall be considered the point of entrance of the service conductors into the building.

1.70. SERVICE MAST

The service mast is the conduit containing the service-entrance conductors where the point of attachment and the connection between the service drop and the service-entrance conductors is located **above** the roofline. The conduit extends to a point, and the weather head is located, above the roof eave. The conduit passes through the eave of the building or extends past the roofline without passing through the eave. The means of attachment is attached to the service mast.

1.71. SERVICE RISER

The service riser is the conduit containing the service-entrance conductors where the point of attachment and the connection between the service drop and the service-entrance conductors is located on a pole or **below** the roofline of the building being served. The conduit extends to a point, and the weather head is located, below the roof eave. The means of attachment is secured to the pole or building and is not attached to the service riser.

1.72. SERVICE TERRITORY

Colorado (CO), Michigan (MI), Minnesota (MN), New Mexico (NM), North Dakota (ND), South Dakota (SD), Texas (TX) and Wisconsin (WI).

1.73. VOLTAGE TRANSFORMER (VT)

An instrument transformer intended for use in the measurement or control of a circuit and designed to have its primary winding connected in parallel with the circuit.

1.74. VOLTAGE UNBALANCE

Maximum voltage deviation from average voltage.

SECTION 2

2. GENERAL INFORMATION

The Company has filed its Rules and Regulations with the Commission as a part of the Tariffs of the Company, which set forth the terms and conditions under which electric service is supplied and govern all classes of service in all the territory served by the Company. The Rules and Regulations are subject to termination, change, or modification, in whole or in part, at any time as provided by the rules of said Commission. Copies of the Rules and Regulations are available for any customer's inspection at the offices of the Company.

Service furnished by the Company is also subject to: The Xcel Energy Standard for Electric Installation and Use, the *National Electrical Code*[®] and the *National Electrical Safety Code*[®].

The Company assumes no responsibility whatsoever for the manufacturer's, supplier's, electrician's or engineering consultant's compliance with all applicable *NEC*[®] and *NESC*[®] codes as well as all local and state codes.

Any waiver at any time of the Company's rights or privileges under the Rules and Regulations will not be deemed a waiver as to any breach or other matter subsequently occurring.

The following are brief statements of those operating rules and practices, which affect the majority of connections made to the Company's lines. Where information not included herein is needed, a Company Representative will provide assistance.

2.1. EFFECTIVE DATE

This edition of the Xcel Energy Standard for Electric Installation and Use may be used at any time on or after the publication date. Additionally, this edition shall become effective no later than April 15, 2015 in all service areas.

2.2. <u>INTENT</u>

The word "shall" indicates provisions that are mandatory.

The word "should" indicates provisions that are normally and generally practical for the specified conditions.

The word "may" indicates possibility.

The words "recommend" and "recommended" indicate provisions considered desirable, but not intended to be mandatory.

Exceptions to a rule have the same force and effect required or allowed by the rule to which the exception applies. All requests for exceptions shall be submitted in writing and will be responded to in writing. Verbal exceptions will not be granted.

Requirements of the *National Electrical Code*[®], *National Electric Safety Code*[®], or the Public Authority which are more stringent than the requirements of this document will take precedence.

2.3. APPLICATION FOR SERVICE

The customer may contact the Company's Builders Call Line to secure information relative to any application for new electric service connections or changes in existing service. Service telephone numbers for the Company can be found at the end of this Section.

Before an electric service connection can be made to the customer's (applicant's) wiring system, it is necessary that:

- 1. The customer has made application for service.
- 2. The applicant has met all requirements of The Xcel Energy Standard for Electric Installation and Use and the Rates, Rules, Regulations and Extension Policy in effect and on file with the Commission at the time of application.
- 3. The Company has completed its construction.
- 4. The Public Authority has notified the Company of approval of the installation by providing an inspection release.

Where no Public Authority has jurisdiction, the Company, for the customer's protection, may require written confirmation from the wiring electrician that the customer's installation conforms to the *National Electrical Code*[®].

In WI and MI, the Proof of Compliance form in this Section shall be completed and presented to the Company before electric service is energized.

The Company does not assume responsibility for the design, operation or condition of the customer's installation.

The Company may make service available from either overhead or underground facilities. In cases where there are aesthetic considerations or where complicated overhead physical situations exist, the Company may recommend the installation of underground facilities.

The Company will not install facilities to serve a customer until the customer agrees to take the service under the applicable Rate Schedule and all applicable charges for construction and service, as required by the Company's Extension Policy, are paid to the Company. Additional costs incurred for digging in frost conditions when insufficient time was provided to estimate, plan, schedule and construct the necessary facilities prior to the onset of frost conditions will be paid by the customer as a nonrefundable charge.

The Company shall not under any circumstances be required to make an extension, which would be unprofitable and thereby cause undue hardship upon other customers of the Company.

It is extremely important that the Company be consulted in advance of the finalization of the customer's plans regarding the Company's electric service requirements.

Email:BCLWI@xcelenergy.com

Electric Inspection Certificat

BUILDERS CAL	LL LINE PHONE:	1-800-628-2121	FAX: 1-888-742-5623	

Date:	_		
Owner/Builder			
Site Address:		City	
Phone Number: Cell Phone:			
Electric Contractor:			
Phone Number:			
General Contractor:			
Phone Number:			
Check Appropriate Boxes:			
Residential	□ Temporary Service	□ Overhead Service	
□ Farm	□ Permanent Services	□ Underground Service	
Commercial	□ Rewire/Upgrade		
NO. OF PHASES	VOLTAGE: EN	ITRANCE SIZE:	
Remarks:			
At the above-described premise, the installati service rules. The installation is now ready fo	on was done in compliance with the provision of all appl r connection.	licable codes, safety standards and Xcel Energy	
For Proof of Compliance Type In Signature of Electrical Contractor:			

License #_____

Contractor Phone#:_____

Date:

FOR UDC& COMMERCIAL INSPECTIONS ONLY

***Uniform Dwelling Code (UDC) Inspection is a requirement for new construction 1 and 2 family dwellings.

Signature of Electrical Inspector:

Certifie Inspection Number:_____

Date Approval:_____

***Before electricity can be furnished this form must be completely filled out, signed and returned to Xcel Energ . <u>Per WI State Statute</u> <u>101.862 effective April 1, 2014 the electrical license number must accompany the electrician's signature to be valid.</u> Please make sure the document is legible.

FAX: 1-888-742-5623 OR MAIL: Xcel Energy, Builders Call Sky Park, PO Box 8, Eau Claire, WI 54702 Or Email: BCLWI@xcelenergy.com

2.4. RATE SCHEDULES

Electric service is supplied to customers under the Company's established rates, rules, regulations, and marketing programs as approved by the applicable Commission having jurisdiction in each state. Rate brochures for residential, commercial, and industrial customers, covering rate schedules and their application are available from the Company upon request. Company Representatives will assist the customer in understanding the Company's rates and in applying them to the customer's load conditions.

2.5. SERVICE AND LIMITATIONS

Service will be rendered to the customer from the Company's nearest suitable power line of sufficient capacity to furnish adequate service at the service voltage available. Service shall not be used by the customer for purposes other than those specified in the applicable Rate Schedule.

2.6. CLOSED LOOP / FLAT TAP / JUMPERED

Closed loops may or may not be allowed in the service territory or locale where service is needed. Refer to Section 4, <u>METERING</u>, <u>Existing Services</u>.

2.7. CONNECTION

Connection to or disconnection from the Company's distribution system shall be made by the Company. Under no circumstances will the customer be permitted to climb the Company's poles, access the Company's underground facilities, or make connections to the Company's lines, except as specified in <u>SAFETY</u>, <u>Unlock</u>, <u>Open and/or De-energize any Electric Power Equipment Procedures</u> in this Section.

The Company shall be notified when it is necessary to cut the meter seal due to situations where the electric service must be disconnected during an emergency or where it necessary to access the meter socket by a qualified person. No persons, other than employees or agents of the Company, may relocate meters or other equipment owned by the Company.

2.8. CUSTOMER-OWNED METER EQUIPMENT RESTRICTIONS

Under no circumstances shall customers' equipment:

- 1) Be connected to, or in any way be served from, the secondary terminals of the voltage and/or current metering transformers.
- 2) Be installed within any metering enclosures including, but not limited to, metering transformer cabinets, transformer compartments, meter sockets or cold sequence disconnect.
- 3) Be connected to an unmetered bus or conductor.
- 4) Plug in devices such as surge suppression, generator transfer switch or any equipment designed to fit between the meter and the socket is not allowed.

- 5) Foreign attachments such as but not limited to CATV, phone loops, grounding clamps and load monitoring equipment, etc., are not permitted to be attached or connected to meter/metering equipment, service riser or service mast.
- 6) Customer-owned transformers shall not be installed ahead of any company metering, except as permitted by local tariffs.

2.9. DIVERSION OF ELECTRICITY

Under no circumstances shall devices or attachments be connected to the Company's facilities in such a manner as to permit the use of unmetered energy except in emergencies where specifically authorized by the Company. Refer to Section 4, <u>METERING</u>, <u>Existing Services</u>.

2.10. EASEMENTS FOR COMPANY'S FACILITIES

The customer shall provide, at the request of and at no cost to the Company, necessary easements and suitable land area or building space owned and controlled by the customer for installation, construction, reconstruction, maintenance, operation, control and use of the Company's overhead and/or underground facilities used or useful to render service to the customer.

2.11. CUSTOMER'S RESPONSIBILITY

The customer shall give authorized employees of the Company access at all reasonable times to the premises of the customer in order to obtain information concerning connected load, to measure or test service, to read meters, or for other purposes incidental to the supplying of electric service. Failure to comply may result in disconnection of services.

It is the responsibility of the customer to adequately protect the Company's equipment located on the customer's property against damage. The customer shall be responsible for any damages or loss resulting from improper protection or neglect.

Pad-mounted transformers, switchgear, and metering equipment shall be installed with adequate clearances for normal maintenance work as specified in Section 5 and the Illustrations Section.

Underground distribution facilities will not be installed until the property is to final grade (±6 inches), the property pins are installed, and the structure is staked or foundation is installed as applicable. Grade at pad-mounted equipment shall be to exact final grade. Whenever it is deemed necessary by the Company, the customer shall provide Company-approved conduit. This will be required in locations that are not readily accessible by the Company such as under driveways, roads, parking lots, sidewalks, patios, etc.

Customers shall connect their equipment so that the load at the point of delivery will be balanced as nearly as practicable. Where three-phase service (except 3-phase, 4-wire delta) is supplied, the customer will attempt to connect equipment so that the load in any one phase at the point of delivery will not exceed the load in any other phase by more than ten (10) percent. Refer to Section 6, <u>THREE-PHASE VOLTAGE UNBALANCE</u>.

2.12. CUSTOMER-OWNED FACILITIES

Distribution facilities, either overhead or underground, beyond the Company's point of delivery are to be installed, maintained, and operated by the customer under all the following conditions:

- 1) All energy is to be metered at one location.
- 2) Each installation is subject to the provisions of the Company's Rules and Regulations, the applicable Rate Schedule, and the approval of the Company.
- Under rates providing for delivery at secondary voltages, the Company will install and maintain only a single transformer installation for the customer, except as specified in Section 4, <u>SERVICES</u>.
- 4) The Company will <u>not install or permit the installation of</u> any of the following customerowned equipment on Company poles: meter sockets, metering equipment, distribution wires, posters, banners, placards, radio or television aerials, or other objects or devices.

Exception: Wires for municipal fire alarm systems, police signal systems, customer's underground service extensions to the overhead system, customer's dead-end equipment, or equipment covered by Joint Use Agreement.

Note: Meter sockets and other metering equipment shall not be installed on Company poles.

- 5) The customer's distribution system shall be in conformance with the *National Electrical Code*[®], the wiring regulations of the Public Authority, and the Company's Rules and Regulations.
- 6) The distribution facilities of the customer beyond the point of delivery shall be connected to the Company's distribution system at one central point through protective devices, approved by the Company, installed and maintained at the expense of the customer.
- 7) Customers shall maintain their distribution system in a safe operating condition so that it does not constitute a hazard to themselves or to other customers or persons. The Company assumes no responsibility for inspection of the customer's lines and facilities and shall not be liable for injury to persons or damage to property when occurring on or caused by the customer's lines or equipment.
- 8) Distribution facilities beyond the point of delivery shall be installed, owned, operated, and maintained by the customer. Such facilities shall be located on and traverse only land owned or controlled by the customer. A customer who is taking service under a commercial or industrial rate may cross dedicated public streets, alleys, or other public ways upon approval of the Company and the public body having jurisdiction, so long as such facilities are necessary for the purpose of serving customer's contiguous buildings or locations which are separated only by such streets, alleys and ways, and provided that such contiguous buildings or locations are used for an integral purpose. The customer's distribution facilities shall be installed in compliance with the *National Electrical Code*[®], the *National Electrical Safety Code*[®], the wiring regulations of the public body having jurisdiction, and the Company's Rules and Regulations.
- 9) Refer to Section 4 for additional requirements for customer-owned facilities.

2.13. <u>SAFETY</u>

Refer to federal regulations and individual state laws concerning safety requirements relating to high voltage power lines of public utilities, which produce, transmit, or deliver electricity. The following explanations should not be regarded as a substitute for reading the laws, but are meant to highlight some of the major points.

2.13.1. Overhead Safety

<u>Caution: Overhead wires and conductors are not insulated for protection from contact.</u> <u>Please exercise care when working near overhead facilities.</u>

Each year a number of accidents involving contact with high voltage overhead lines occur, often resulting in serious injury or death. In an effort to prevent these types of accidents, laws have been enacted to provide safer working conditions in areas around high voltage overhead lines.

These laws apply, with few exceptions, to any person or business entity contracting to do work or perform any activity, which may bring an individual or equipment within 10 feet of high voltage overhead lines in excess of 600 volts. If work is to be performed within 10 feet of high voltage lines, the public utility shall first be contacted to arrange for safety provisions. The Company is required to provide a cost estimate for making those provisions. If there is a dispute over the amount to be charged, the Company will proceed in a timely manner to provide the safety measures and the dispute will be settled at a later date. If work is begun after an agreement has been reached and before the safety provisions have been made, the person or entity performing the work shall be liable for damages resulting from contact with high voltage overhead lines. Violations of these laws may result in a fine and/or possible liability for damages resulting from contact with high voltage overhead lines.

2.13.2. Underground Safety

<u>Caution: Stakes, flags or painted lines mark the locations of underground utilities. Please</u> <u>dig very carefully within 18" on each side of the markings.</u>

Anyone planning to dig in or near a public road, street, alley, right-of-way, or utility easement shall notify the Company of your intent, no less than 48 hours (2 working days) before you dig. Call the telephone number listed below for your locale.

National, Call Before You Dig Line	811
✓Colorado, Utility Notification Center	800-922-1987
✓ Michigan, Miss Dig	800-482-7171
✓ Minnesota, Gopher State One Call (Outside Metro Area)	800-252-1166
✓ Minnesota Gopher State One Call (Metro Area)	651-454-0002
✓ New Mexico One Call	800-321-2537
✓North Dakota, North Dakota One Call	800-795-0555
✓ South Dakota, South Dakota One Call	800-781-7474
✓Texas, DIG TESS	800-344-8377
✓Wisconsin, Diggers Hotline	800-242-8511
Utility facilities may be buried clong the rear olds, and front property line	a in any of the regidentic

Utility facilities may be buried along the rear, side, and front property lines in any of the residential areas. Residential service lines may cross homeowner's front and back yards. Many facilities are also located within the street, alley, or highway rights-of-way.

Color Codes: (Verify color codes used within your locale)

- Red Electric Power Lines, Cables, Conduit and Lighting Cables
- Yellow Gas, Oil, Steam, Petroleum, or Gaseous Materials
- Orange Communication, Alarm or Signal Lines, Cables or Conduit, including Cable Television
- Blue Water, Irrigation and Slurry Lines
- Green Storm Drain Lines/Sewer
- Pink Survey Markings
- White Proposed Excavation

2.13.3. Change of Grade

The grade in any public right-of-way or easement shall not be changed without first contacting the Company to determine if electric facilities are contained within the right-of-way or easement. Permission may be granted to change the grade by the Company Area Engineering Department if the grade change will not affect the minimum clearance requirements. Company construction may be necessary if the grade change will necessitate moving equipment or facilities. The Company Area Engineering Department can provide an estimate for the cost to relocate facilities when necessary to provide adequate clearance.

2.13.4. Unlock, Open and/or De-energize any Electric Power Equipment Procedures

The Company established procedures to assure maximum safety to protect all individuals prior to unlocking, opening and/or de-energizing electric power equipment where access by unauthorized personnel is required. The following procedures apply to, but are not limited to, energized Company facilities such as vaults, transformers, manholes, switchgear and secondary pedestals:

- 1) The customer shall request and receive access authorization prior to the Company Representative unlocking, opening, and/or de-energizing any electric power equipment.
- 2) Normally, a transformer will not be permanently energized until the secondary service is complete. In cases where it is necessary to leave the transformer energized, such as installing additional secondary conductors, the Company Representative will unlock the transformer and stand by while work is performed and relock the transformer when the work is completed.
- 3) When a de-energized transformer is opened by the Company Representative for a contractor to pull cable, the contractor shall relock the transformer and notify the Company Representative before leaving the worksite.
- 4) Charges for work may apply when Company personnel are required to open and close transformers or other electric equipment and stand by while work is performed around energized equipment. The Company Representative will determine the amount to be charged.

2.13.5. Energization of Electric Service

The Company will not energize an electric service or set meters on new, rewired, altered, or repaired wiring installations unless all of the following conditions have been met:

- 1) The premises served have been properly identified by the customer.
- 2) Meter trace verifications have been performed by the Company's local Electric Meter Department.
- 3) An inspection release from the local Public Authority has been received by the Company.

Note 1: In locations where there is no local Public Authority, the wireman shall submit a signed and dated letter to the Company's Builders Call Line attesting that the electrical installation has been completed and installed according to the current National Electrical Code[®] and any other codes that apply before electric service is energized.

Note 2: In locations in Wisconsin where there is no local Public Authority, the Wisconsin / Michigan Electric Inspection Certificate, located in Section 2 of this manual, shall be submitted to the Company's Builders Call Line before electric service is energized.

Note 3: Services that have been shut off or disconnected for more than 365 days (1 year), must meet current installation requirements, in order for service to be reconnected.

- The Company Representative has verified that the service entrance shows no continuity, load, or voltage feedback on the load-side terminals of the electric meter socket or CT metering installation.
- 5) The Company Representative has verified that the customers' equipment has a mechanical means to disconnect and isolate equipment from the load-side terminals of the self-contained electric meter socket or current transformers (CTs). This requirement includes, but is not limited to, any load produced by transformers (dry-type or oil-filled) that are used for a separately derived system.

Note 1: Once a service is energized, it shall be the customer's responsibility to turn on load side breakers or close disconnecting switches.

6) The Company Representative has verified that the electric service meets all of the requirements in Section 4.

Note: The meter socket shall meet all requirements listed under <u>METER SOCKETS</u> in Section 4.

2.14. XCEL ENERGY LIMITED TELEPHONE DIRECTORY

Service Telephone Numbers:

- ✓ Builders Call Line for New or Existing Accounts
- ✓ Denver Metropolitan Area Closed Loop Desk
- ✓ Emergency/Lights Out
- ✓ Gas Emergency/Gas Odor
- ✓ Residential Customer Service
- ✓ TDD/TYY (Hearing Impaired Service)
- ✓ Business Solution Center
- ✓ Home Solution Center
- ✓ Electric Meter Technical Assistance

800-628-2121 303-425-3951 800-895-1999 800-895-2999 800-895-4999 800-895-4949 800-481-4700 800-824-1688 800-422-0782

Email Address

EMStandardsExceptionRequest@xcelenergy.com

SECTION 3

3. CHARACTER OF SERVICE AVAILABLE

Contact the Company for information regarding availability of any desired type of service in a given locale. Delays and unnecessary expense may be avoided by contacting the Company in advance of construction.

3.1. TYPES OF SERVICE

The service voltages listed below may not be available in each of the Company's service territories. The Company will assist in determining whether the service voltage requested is offered under the Company's Tariffs within the service territory. These service voltages are all derived from grounded transformer banks. Depending upon the service voltage, either the neutral or one phase conductor is grounded at the supply transformer and will be run from the transformer installation to the meter socket.

Customers requiring an ungrounded service for operation of a ground detection system, or for other operations permitted by the *National Electric Safety Code*[®], shall submit an exception request detailing the special circumstances necessitating the request.

Customers accepting three-phase service from an open-delta transformer bank shall sign a liability waiver form indicating the customer's acceptance of potential damage to customer's equipment due to voltage unbalance.

Voltage	State							
Vonago	со	МІ	MN	ND	NM	SD	ТХ	WI
120 V, 1Φ, 2W	X ¹	Х	X ²	X ²	Х	X ²	Х	Х
277 V, 1Φ, 2W		Х						Х
480 V, 1Φ, 2W			X ²	X ²	Х	X ²	Х	
120/240 V, 1Φ, 3W	Х	Х	Х	Х	Х	Х	Х	Х
120/208 V, 1Φ, 3W	Х		Х		Х		Х	
240/480 V, 1Φ, 3W			X ³	X ³		X ³		
240 V, 3Φ, 3W					Х		Х	
480 V, 3Φ, 3W					Х		Х	
120/208 V, 3Φ, 4W	Х	Х	Х	Х	Х	Х	Х	Х
120/240 V, 3Φ, 4W	Х		X ⁴	X ⁴	Х	X ⁴	Х	
277/480 V, 3Φ, 4W	Х	Х	Х	Х	Х	Х	Х	Х

3.1.1. Available Service Voltages by State

¹ By Exception Only

² Street Lighting Only

³ Highway Lighting Only

⁴ With Prior Approval (OH ONLY)

Contact the Company for information regarding the availability of Primary Distribution and Transmission voltages.

3.2. METER SOCKETS FOR TYPES OF SERVICE

- 1) Self-Contained Supplied by the customer (Refer to Section 4, METER SOCKETS):
 - a) 1Ø 2W, 1Ø 3W and 3Ø 3W Delta 5 terminal meter sockets
 - b) 3Ø 4W Wye and 3Ø 4W Delta 7 terminal meter sockets
- 2) Transformer Rated (CTs) Supplied by the Company:
 - a) 1Ø 2W, 1Ø 3W 8 terminal meter sockets (6 terminal meter sockets MI, MN, ND, SD, and WI only)
 - b) 3Ø 3W Delta 8 terminal meter sockets
 - c) 3Ø 4W Wye and 3Ø 4W Delta 13 terminal meter sockets

3.3. DISTRIBUTION (PRIMARY) SERVICE

Electric energy will be supplied at the voltage of Company's distribution line of adequate capacity for the load to be served. The Company will advise the applicant as to the primary voltage available and will specify the location of the primary metering installation.

Primary service is not available in Company's Network Service Area.

Secondary service voltage is not permitted for customers already supplied with primary service voltage.

3.4. TRANSMISSION SERVICE

Electric energy will be supplied at the voltage of the Company's existing transmission lines at locations specifically approved by the Company. Such service will be supplied only in locations accessible to the Company's transmission lines.

SECTION 4

4. SERVICE FACILITIES

The Company will provide service from either overhead or underground distribution facilities, depending upon availability and initial construction costs. Where there is a choice of overhead versus underground service, the Company will normally offer the form requiring the least initial construction cost, in which case the customer may elect to choose the alternate, but charges will apply.

The customer shall confer with the Company Representative before purchasing equipment, beginning construction of a proposed installation or altering existing service installations. The Company Representative will determine if the type of service and voltage desired by the customer is available, determine if additions to the Company's facilities will be required, and contact the Company's local Electric Meter Department to secure a definite meter location and point of delivery. The Company Representative will arrange for all necessary alterations and determine any applicable fees.

When the Company is required by order of a Public Authority to alter its distribution system, necessitating a change in the location of the point of delivery, the Company will designate a new point of delivery. The customer, at his expense, shall relocate the service entrance conductors and metering equipment to the new point of delivery. The relocated service shall comply with the installation standards contained within this manual.

4.1. SERVICES

A building or other structure will be supplied by only one service, in accordance with 2011 *National Electrical Code*[®] Article 230.2, or as may be amended.

The policy pertaining to the Company providing additional services for a building or group of buildings will vary depending upon the service territory. In most cases, additional charges for initial construction and perpetual maintenance costs will apply for the additional service(s). Contact the Company Area Engineering Department for specific information.

Only one service (point of delivery) will be provided to a building or other structure, except as specified below:

- 1) Special Conditions Additional services <u>may</u> be provided by the Company for:
 - a) Emergency lighting.
 - b) Fire pumps.
 - c) Legally required standby systems.
 - d) Optional standby systems.
 - e) Parallel power production systems.

- 2) Special Occupancies Additional services <u>may</u> be provided by the Company for:
 - a) Multiple-occupancy buildings where the Company determines that there is no available space for service equipment accessible to all occupants.
 - b) A single building or other structure where the Company determines that such building or structure is sufficiently large to make two or more services necessary.
- 3) Capacity Requirements Additional services <u>may</u> be provided where the Company determines that it cannot adequately provide service at a single point of delivery.
- 4) Different Characteristics Additional services <u>may</u> be provided by the Company for different voltages or phases, or for loads with different rate schedules (Except CO).

4.2. OVERHEAD SERVICE

4.2.1. Overhead System - Low Voltage (0-480 Volts)

General Requirements:

- 1) Service Connection Overhead service drop conductors will be installed and connected to service entrance conductors in accordance with the Company's Rules and Regulations.
- 2) Point of Attachment The Company will specify the location of the service-entrance conductors most suitable for connection to the Company's lines.
 - a) The customer shall furnish and install the physical means of attachment.
 - b) The point of attachment shall be located within 24" of the weather head and at a point nearest the Company's facilities to be used to provide service. Refer to the Illustrations Section, **Drawing SC-10**.
 - c) The point of attachment shall be located such that adequate clearance can be obtained for the service drop from trees, awnings, patio covers, foreign wires, adjacent buildings, swimming pools, etc. Service drops shall <u>not</u> pass over adjacent private property, except where permitted by easement. Specified heights and clearances may be maintained by use of an approved service mast through the roof.
 - d) Vertical Clearance from Ground Refer to 2007 *National Electric Safety Code*[®] Article 232 and Table 232-1, or as may be amended. Service-drop conductors, where not in excess of 600 volts nominal, shall have the following minimum clearances from final grade:
 - (1) 12.0' over spaces and ways subject to pedestrians.

Exception 1: Where the height of a building or other installation does not permit the 12.0' clearance, 10.5' clearance for insulated service drops limited to 300 volts to ground and 10.0' clearance for insulated service drops limited to 150 volts to ground are permitted.

(2) 16.0' over driveways.

Exception 2: Where the height of a residential building does not permit the 16.0' clearance, 12.5' clearance for insulated service drops limited to 300 volts to ground and 12.0' clearance for insulated service drops limited to 150 volts to ground are permitted.

- (3) 16.0' over other land traversed by vehicles.
- (4) Drip loops shall meet the same clearances as specified above for service drops.

Exception 3: Where the height of a residential building does not permit the specified clearance, 10.5' clearance for insulated drip loops limited to 300 volts to ground and 10.0' clearance for insulated drip loops limited to 150 volts to ground are permitted

- e) The point of attachment shall not be higher than twenty four (24) feet above final grade.
- Service Mast/Riser Supports Only the Company's power service-drop conductors shall be attached to a service mast. Phone loops, cable TV conductors, grounding clamps, etc. shall not be attached to the service mast or riser. Refer to 2011 National Electrical Code[®] Article 230-28 or as may be amended.
 - a) Service Mast The service mast is the conduit containing the service-entrance conductors where the point of attachment and the connection between the service drop and the service entrance conductors is located **above** the roofline. The conduit extends to a point, and the weather head is located, above the roof eave. The conduit passes through the eave of the building or extends past the roofline without passing through the eave. The means of attachment is attached to the service mast. Service masts shall be 2" minimum GRC metallic conduit. The point of attachment shall not exceed 48" above the roofline. If the weather head exceeds 48" above the roofline, then the mast shall be braced or guyed by the customer. Conduit couplings shall not be installed above the roofline. Refer to the Illustrations Section **Drawing SC-10** showing typical installation method.
 - b) Service Riser The service riser is the conduit containing the service-entrance conductors where the point of attachment and the connection between the service drop and the service-entrance conductors is located on a pole or **below** the roofline of the building being served. The conduit extends to a point, and the weather head is located, below the roof eave. The means of attachment is secured to the pole or building and is not attached to the service riser. Service Riser size, per *National Electrical Code*[®]. Refer to the Illustrations Section, **Drawing SC-10** showing typical installation method.
- 4) Ice and Snow Shields A meter ice and/or snow shield may be required on all new or rewired services in locations with heavy snowfall or ice loading and in locations above 6000 feet in elevation. All electric meters shall be located on the gable or non-drip side of a building or other structure, and there shall be no adjacent rooflines, which will drip directly on or towards a neighboring meter installation. Any installation deemed unsafe by the Company may be disconnected. Prior approval by the Local Electric Meter Department, is required to install service mast and/or meter on a drip side if it is not practical to install on gable end. Check with the Company's local Electric Meter Department to determine requirements for your locale. Refer to the Illustrations Section, Drawing SC-20 and SC-20A showing typical installation methods.

5) Service Drops - The allowable length of service drop conductors shall be governed by the slope of the ground, intervening trees and obstructions, and the size of the conductor required.

Conductor (Duplex , Triplex or Quadraplex)	Maximum Service Span* (Utility pole to House knob)
#6	110'
#4	110'
#2	90'
1/0	80'
4/0	70'
500	50'

*Service tension is limited to 800lbs under ½" 32° F ice loading conditions

- 6) Secondary Poles If the service span length is larger than allowed in the table above, secondary will need to be extended to a new company provided pole on the customer's property. From the new pole the service can be extended to the house. A suitable easement may be required before such installation is made.
- 7) Service Entrance Conductors Service entrance conductors shall have a current carrying capacity at least as great as that required by the *National Electrical Code*[®] and the Public Authority having jurisdiction. The Company strongly recommends that some provision be made for future load increase. A sufficient length of wire, but in no case less than twenty-four (24) inches on residential or thirty-six (36) inches on commercial services, shall extend from the service weather head for connection to the Company's service drop. Line and load conductors are not permitted in the same raceway or conduit. No conductors, other than service entrance conductors, shall be installed in the service entrance conduit. All line-side (non-metered) conductors shall be in a continuous length of conduit from the point of delivery to the meter socket or the cold sequence metering disconnect. Junction boxes, conduit fittings (e.g. LB's), or other devices are not allowed without specific approval from the Company's local Electric Meter Department.

4.2.2. Overhead System - Primary Voltage (Above 480 Volts)

Because of safety precautions, which must be exercised in the utilization of energy at voltages in excess of 480 volts, the Company shall be consulted in regard to service entrance, transformer location, and meter installation details for this class of service before construction is started.

Overhead service of 2400 volts or greater will <u>not</u> be attached directly to a building except where such building is used as a substation or transformer room. Refer to the Illustrations Section, **Drawing PM-10** for typical installation of primary voltage service.

4.3. UNDERGROUND SERVICE

4.3.1. Underground System - Low Voltage (0-480 Volts)

General Requirements:

- Service Connection Underground service laterals from underground distribution systems or overhead distribution systems shall be installed in accordance with the Company's Rules and Regulations.
- 2) Point of Entry The Company shall specify the location of the underground service lateral and metering equipment location most suitable for connection with the Company's facilities. The company will not run an underground service lateral through a wall below grade or above the first floor level.
- 3) Ice and Snow Shields A meter ice and/or snow shield may be required on all new or rewired services in locations with heavy snowfall or ice loading and in locations above 6000 feet in elevation. All electric meters shall be located on the gable or non-drip side of a building or other structure, and there shall be no adjacent rooflines, which will drip directly on or towards a neighboring meter installation. Any installation deemed unsafe by the Company may be disconnected. Prior approval by the Local Electric Meter Department, is required to install service mast and/or meter on a drip side if it is not practical to install on gable end. Check with the Company's local Electric Meter Department to determine requirements for your locale. Refer to the Illustrations Section, Drawing SC-20 and SC-20A showing typical installation methods.
- 4) Underground Service Laterals Laterals shall not be installed until property is to final grade (<u>+</u>6 inches), property pins are in place, and the cable route is free of obstructions.
 - a) Company owned service laterals shall not be installed at a depth of less than twenty-four (24) inches.

Note: WI, MI only the customer shall provide a minimum of 5 inch conduit or equivalent space per set of conductors. The standard service length is 25 feet or less. Conduit is to have a maximum of two 90 degrees sweeps. Consult with the company if a longer service is necessary. The customer may be responsible for additional charges for nonstandard service lengths. For conduit lengths over 50 feet, steel sweeps are required.

- b) Customer-owned commercial and industrial service laterals shall be installed in accordance to the 2011 *National Electrical Code*[®] or as amended.
- c) Electric and plastic gas services within the same trench shall be separated by twelve (12) radial inches. Steel gas services shall not be installed in the same trench with an electric service and require a minimum of twelve (12) radial inches of separation.
- d) Service conductors under hardscape shall be in conduit where the conduit extends two (2) feet beyond the hardscape edge.
- e) Conduit ells for service wire shall have a minimum radius of thirty-six (36) inches.
- f) In accordance with the NESC Section 351C2, buildings or other structures are not permitted to be located directly above or within 12 inches of underground conductors. In the event a building or structure is built over underground conductors, the customer may be responsible for costs associated with relocating the service conductors.

- 5) Ground Movement A slip sleeve or expansion joint shall be furnished and installed by the customer on all new and rewired underground residential meter installations and recommended for all commercial installations.
 - a) A slip sleeve shall be an 18" length of 2¹/₂" Schedule 40 or 3" Schedule 80 PVC conduit. The slip sleeve shall be buried to a depth of nine (9) inches so that nine (9) inches is exposed above final grade.
 - b) An expansion joint shall be a minimum 18" length Schedule 80 PVC installed at the bottom of the meter housing.

Note: Effective March 31, 2014 the customer will be responsible for providing the slip sleeve or expansion joint for underground service riser.

Refer to 2011 *National Electrical Code*[®] Article 300.5(J) (FPN), or as may be amended and to the Illustrations Section, **Drawings SC-30**, **SC-40**, **SC-50**, **SC-90** and **TR-10** for typical slip sleeve installations.

- 6) Service Entrance Conductors Service entrance conductors shall have a current carrying capacity at least as great as required by the *National Electrical Code*[®] and the Public Authority having jurisdiction. The Company strongly recommends that some provision be made for future load increase. Line and load conductors are not permitted in the same raceway or conduit. No conductors, other than service conductors, shall be installed in the service lateral conduit. Each service run shall be contained within its own conduit (A, B, C phases and neutral) on commercial services. Junction boxes, conduit bodies (e.g. LB's), or other devices are not allowed without specific approval from the Company's Local Meter Department. Drawings showing typical methods for installing service-entrance conductors are contained in the Illustrations Section.
- 7) Conductors in a Meter Socket On an underground service, the center knockout in the bottom of the socket, if provided, shall not be utilized. Line conductors shall enter through the knockout provided at the left side of the bottom horizontal surface of the meter socket. The line conductors shall be routed along the outermost edges of the meter socket allowing for ground settling, which could pull the line conductors down. Either the knockout on the right side of the bottom horizontal surface, the lower knockout on the right vertical surface, or the lower knockout on the back vertical surface of the meter socket may be used for load conductors. Load conductors shall <u>not</u> exit the left side of the meter socket. Refer to the Illustrations Section, **Drawings SC-140, SC-150, and SC-170.**

4.3.2. Underground System - Primary Voltage (Above 480 Volts)

Because of safety precautions, which must be exercised in the utilization of energy at voltages in excess of 480 volts, the Company shall be consulted in regard to service entrance, transformer location, and meter installation details for this class of service <u>in advance of construction and/or</u> <u>purchase of equipment.</u> Refer to the Illustrations Section, **Drawings PM-20, PM-30 and PM-40** for customer-owned primary switchgear and **Drawing CR-100** for primary meter cabinet clearance requirements.

Company Owned Service Conductors in Conduit

4.4. SERVICE LATERAL SIZES (for balanced load):

PAD-MOUNTED TRANSFORMERS							
KVA	Copper	Aluminum					
208 Grd Y/120 Volt							
75	1 - 4/0	1 - 500					
150	2 - 500	2 - 500					
300	3 - 500	2 - 750					
500	4 - 500	4 - 750					
750	6 - 500	5 - 750					
1000	8 - 500	7 - 750					
240/120 Volt ∆ (1)							
225	2 - 500	1 - 750					
300	2 - 500	2 - 500					
500	4 - 500	3 - 750					
750	6 - 500	5 - 750					
1000	8 - 500	6 - 750					
480 Grd Y/277 Volt							
75	1 - 1/0	1 - 1/0					
150	1 - 4/0	1 - 500					
300	1 - 500	2 - 500					
500	2 - 500	2 - 500					
750	3 - 500	3 - 750					
1000	4 - 500	4 - 750					
1500	6 - 500	5 - 750					
2000	7 - 500	6 - 750					
2500	8 - 500	7 - 750					
240/120 Volt 1 Φ							
167	2 - 500	2 - 500					

4.5. CONDUIT SIZING CHART:

The following is a list of pipe or duct size to be used for cable installations in conduit. This table is based on 40% maximum pipe fill.

Cable Size	Voltage	# Cond/Conduit	Pipe Size (I.D.)
1/0-2-1/0	600 V	1 Set	2" PVC or PE or 2" flex
4/0-2/0-4/0	600 V	1 Set	3" PVC or PE or 3" flex
350-4/0-350	600 V	1 Set	4" PVC or PE
350 AL/CU	600 V	1-5	5"
350 AL/CU	600 V	6-8	Two 5"
750 AL/CU	600 V	1-4	5"
750 AL/CU	600 V	5-8	Two 5"

NOTE: Conduit or Conduit fittings made from a ferrous material may not be used when separating three-phase runs into separate conduits.

4.6. TRANSFORMER INSTALLATIONS - NETWORK VAULTS

For non-network areas, transformer vaults will not be permitted.

The determination of facility type and routing will be made by the Company to be consistent with the characteristics of the territory in which service is to be rendered and the nature of the Company's existing facilities in the area.

Prior approval is required for all network vaults and the following rules shall apply:

- 1) Where extensive building remodeling is being done and it is necessary to provide a vault for transformers and related equipment, all necessary vault construction, including relocating facilities, shall be accomplished by the building owner at no cost to the Company.
- 2) All transformer vaults shall be constructed in accordance with the latest revision of the National Electrical Code[®], any other applicable codes and the Company's specifications. The customer, upon request by the Company, shall authorize in writing that the Company may declare and operate the vault and equipment therein as a Company Substation.
- 3) In addition to the requirements of the *National Electrical Code*[®], the following general requirements shall be observed:
 - a) Access for Company personnel and equipment is required. Such access shall be available to Company personnel at all times. The customer shall provide a hasp or other suitable means to accommodate the Company's lock.
 - b) If access to the vault does not permit the use of Company equipment for removal, relocation, and installation of vault facilities, the customer shall provide the means to remove, relocate, and install the Company's facilities.
 - c) The vault shall be suitably illuminated and a convenience outlet shall be provided at the expense of the customer. The light control switch and convenience outlet shall be located inside the vault and shall be connected to the unmetered bus.
 - d) The customer's equipment, fuses, etc. shall not be installed in the vault.
 - e) The customer shall provide a Company approved separate ventilation system to the outside air. The vault's ventilation ducts <u>shall not</u>, under any circumstances, be tied into the building ventilation system.
 - f) Vaults shall be provided with a retaining or holding tank system to collect any oil spillage. Any water entering the vault must be drained away from the vault separate from any oil. Provisions shall be made to pump any oil collected in the sump from the vault.
 - g) Because of the variety of special problems arising during the construction of building vaults, only the most general specifications covering their design and arrangements are presented herein. The Company shall be consulted well in advance of any proposed project.
 - h) The Company will not energize any building vault transformer for temporary or permanent service until all vault specifications are met, a final checklist of vault specifications is approved by the assigned Company Area Engineer, and the vault has been turned over to the Company for occupancy.

4.7. TRANSFORMER INSTALLATIONS - PAD-MOUNTED

The Company will provide an outdoor pad-mounted transformer for service to the customer's facilities such as shopping centers, office buildings, schools, large apartment buildings, etc. under the following conditions:

- 1) The customer's facilities shall be located in an area not presently served or expected to be served from the Company's underground network system. The Company reserves the right to define areas to be served by secondary network systems.
- 2) The Company will own, operate and maintain the primary underground installation between the adjacent distribution facilities and the transformer, including the primary cable, ducts, transformer and protective equipment.
- 3) The Company will provide an adequate base at finished grade for the installation of the Company's pad and pad-mounted transformer. In areas near buildings where earth has been disturbed, the customer shall provide firm soil conditions (at least 2000 pounds/square foot compaction) under pad area to prevent settling of the pad. In cases where the adequacy of the base may be doubtful, the Company may require a "Certificate of Adequacy" from a qualified testing laboratory.
- 4) The Company will make and maintain all connections at the transformer terminals. No customer-owned switches, fuses, etc. may be located within a fenced area designed to contain a transformer installation without written approval of the assigned Company Area Engineer.
- 5) The property shall be to final grade (±6 inches) except at the equipment location, which shall be to exact final grade. The property must be level and clear for ten (10) feet to allow for operation and maintenance of the pad mounted equipment. Property pins shall be in place with the structure staked or the foundation in, prior to installation of the pad-mounted equipment and splice boxes.
- 6) The Company shall be consulted well in advance of any proposed project.
- 7) If, in the judgment of the assigned Company Area Engineer, the selected location for the installation of the pad-mounted equipment is not adequately protected from traffic, or when directed by the local Public Authority, the customer shall furnish and install either a fence guardrail or guard posts to protect the pad-mounted equipment installation. At the customer's request, the Company <u>may</u> elect to furnish and install the guardrail or guard posts, and the customer shall accept such cost as non-standard design on a non-refundable basis, not subject to Construction Allowance. The installation shall conform within practical limits to the Illustrations Section, **Drawing CR-90**.

Further details relating specifically to transformers can be found in Section 5. Refer to the Illustrations Section, **Drawings CC-10, CC-30, CC-40, CC-50, CR-20, CR-30, CR-40, CR-50, CR-60 and CR-9**0 for typical pad-mounted transformer installation and clearance requirements.

4.8. POINT OF DELIVERY

The point of delivery is the point where the Company's electric facilities are first connected to the electric facilities of the customer. The point of delivery for the various classifications of service is shown throughout the Illustrations Section.

Effective Date April 15, 2015

It is the policy of the Company to own, operate, and maintain the electric distribution facilities up to the point of delivery. This policy is applicable to service rendered from either overhead or underground facilities. All such facilities will be installed in accordance with the Company's Line Extension Policy and Rules and Regulations as filed with the Commission.

4.9. CUSTOMER-OWNED SERVICE CONDUCTORS (Not Applicable in WI/MI)

The number and size of customer-owned conductors that may be terminated to Company facilities is limited by the type of installation as follows:

- 1) Overhead-to-Overhead:
 - a) Service entrance risers on a building are limited to a maximum number of six (6), with a single set of conductors in each riser.
 - b) The conductor size shall not exceed 750 kcmil.
- 2) Overhead-to-Underground:
 - a) A maximum of three U-guard risers per pole (including Company-owned, foreign utility owned and/or customer-owned) shall be attached to a Company pole.
 - b) Thirty-two (32') feet of customer owned conductor shall be coiled at the base of Company pole, where applicable. If customer installs conduit from structure to base of pole, customer may install elbow at pole but under no circumstances install any customer-owned conduit on Company-owned pole.
 - c) Customer-owned conduit at the base of the Company's pole shall not exceed six (6) inches above final grade.
 - d) The U-guard risers shall be grouped together and shall not occupy more than 40% of the pole circumference.
 - e) Only a single set of conductors shall be installed in each U-guard riser.
 - f) The conductor size shall not exceed 750 kcmil.
- 3) Underground:
 - a) Three-Phase Pad-mounted Transformer The maximum number of secondaries or service runs per phase that are to be served from a three-phase transformer is eight (8). The maximum conductor size shall not exceed 500 kcmil copper or 750 kcmil aluminum.
 - A secondary connection cabinet is required when the number of the Customer's secondary conductors exceeds eight 8-runs per phase or the size of the conductors is greater than 500 kcmil copper or 750 kcmil aluminum.
 - ii) When not required, a secondary connection cabinet may also be installed at the customer's discretion.
 - iii) All secondary connection cabinets with or without metering provisions shall be provided by the Customer and placed adjacent to the transformer. Refer to the Illustrations Section **Drawings CC-10, CC-40, and CC-50.**

iv) Effective March 1, 2016: All secondary connection cabinets with or without metering provisions shall have a 3-point latch with provisions for a Company padlock and door(s) shall be hinged on either the left or right side.

- b) Single-Phase Pad-mounted Transformer The maximum number of secondaries or services per phase that are to be served from a single-phase transformer is based on cable size. A maximum cable size of 500 kcmil is permitted. For cables 500 kcmil or 350 kcmil a maximum of 4 runs are allowed. For residential applications, a maximum of 4 runs of 350 kcmil plus 2 runs of 4/0 are allowed (total of six (6) runs).
- c) Single-Phase Pedestal The maximum number of cables in a standard single-phase pedestal, with six-position URD moles, is 15. This includes one secondary feed from the transformer, 4 services, and the ground. The ground wire needs to be installed in its own port on the Neutral URD mole. The maximum conductor size shall not exceed 350kcmil aluminum. If a street light feed is required, or if any additional services need to be run from the pedestal, an 8 position URD mole shall be used.

4.10. METERING

4.10.1. New Services

The Company will not permit a temporary unmetered service (closed loop/flat tap/jumpered) on new electrical services. Service may be supplied from a temporary meter panel prior to an inspection release on new services. Refer to Section 4, <u>TEMPORARY SERVICE</u> and the Illustrations Section, **Drawings TM-10, TM-20 and TM-30**.

Before permission will be granted to energize a new service, the Company shall have an application for electric service and an inspection release shall be provided to the Company by the local Public Authority.

Note 1: In locations where there is no local Public Authority or customers exempt from inspection, the wireman shall submit a signed and dated letter to the Company's Builders Call Line attesting that the electrical installation has been completed and installed according to the current National Electrical Code[®] and any other codes that apply before electric service is energized.

Note 2: In locations in WI/MI where there is no local Public Authority, the Electrical Inspections Certificate form in the Section 2 shall be completed and presented to the Company before electric service is energized.

4.10.2. Existing Services

Before a meter will be installed on an existing service, which has been rewired, altered, or repaired, an inspection release shall be received by the Company from the local Public Authority.

Note: In locations where there is no local Public Authority, the wireman shall submit a signed and dated letter to the Company's Builders Call Line attesting that the electrical installation has been completed and installed according to the current National Electrical Code[®] and any other codes that apply before electric service is energized.

Closed Loop Temporary Unmetered Services are not allowed in MI, MN, ND, SD, TX, NM and WI.

Closed Loop Temporary Unmetered Services for CO Only. The following rules shall apply:

- For existing services, a temporary unmetered service (closed loop/flat tap/jumpered) may or may not be allowed in the service territory or locale where electric service is needed. Before closing a loop, the customer shall obtain a wiring permit from the local Public Authority and permission from the Company, and all wiring shall comply with the *National Electrical Code*[®] and the rules of the local Public Authority.
- 2) Electric energy used during the period of the closed loop will be estimated and billed at the appropriate rate. The customer of record will be responsible for the energy used.
- 3) On any wiring installation where a meter has been disconnected, the meter shall not be reconnected by anyone except a Company Representative. Closing a manual bypass mechanism or installing jumpers in the meter socket is not permitted and will be considered a closed loop, which requires prior permission.
- 4) If any wiring being served on a closed loop is not installed in accordance with the Company's Rules and Regulations, the Company may open the closed loop.

Note: Customers that have been disconnected by non-Company personnel may incur a reconnect fee.

5) The Company may grant permission for a temporary unmetered service (closed loop/flat tap/jumpered) on an existing service for up to a maximum of seven (7) calendar days. Special permission by the Company's local Electric Meter Department is required to extend a closed loop beyond seven days. Permission to close a loop may be obtained in the form of an authorization number by calling the Company Office nearest you. If a temporary unmetered service is not allowed in the service territory or locale where electric service is needed, or if the length of time that temporary service is required exceeds seven (7) days, the customer may contact the Company's Builders Call Line to coordinate temporary meter service. Refer to Section 2, XCEL ENERGY LIMITED TELEPHONE DIRECTORY.

4.10.3. Meter Installation And Ownership

All service to a customer will be supplied by a single service (point of delivery) and only one meter will be installed at an address or single unit of a multi-unit building. Only in the event that more than one service is allowed by the Company as detailed in <u>SERVICES</u> in this Section, will the Company install more than one meter.

Only authorized Company employees or qualified individuals authorized by the Company are permitted to connect, disconnect, move or remove meters. All meters, service wires, and other electrical facilities installed by the Company upon the customer's premises for delivering or measuring electrical energy to the customer shall continue to be the property of the Company. All metering equipment owned by the Company and not installed shall be returned to the Company. These facilities may be repaired, inspected, tested, replaced, or removed by the Company.

In <u>TX/NM only</u>, an oil well pumping service may be provided from a customer-owned overhead transformer bank installed on a customer-owned primary distribution system with prior approval from the Company's local Electric Meter Department. For all new installations, the meter shall be installed on the customer-owned transformer pole.

4.10.4. Classification Of Metering

Refer to Section 1 for the definition of Classification of Metering.

The Company classifies its metering installations as:

- 1) Residential Rate:
 - a) Self-Contained (Hot Sequence required).
 - b) Instrument Transformer (Hot Sequence required).
- 2) Commercial and Industrial Rates:
 - a) Self-Contained (See Cold Sequence Metering Section for Jurisdictional Requirements).
 - b) Instrument Transformer (Hot Sequence required).
 - c) Temporary Construction (See Cold Sequence Metering Section for Jurisdictional Requirements).

The type of metering used will be determined by the Company based upon: the service voltage, the load supplied, the available fault current, and the applicable Rate Schedule.

Residential service lateral may be extended to a structure containing not more than six residential units provided all meters are grouped at one location and all units are separately metered on residential rates. If house power service (Commercial) is required, then the service lateral shall be installed by the customer, except for WI and MI.

All services shall be metered on the secondary side of the Company's transformer unless the applicable Rate Schedule specifies that the service be metered on the primary side of the transformer. The Company may install its meter on either side of the transformer and losses occurring between the point of delivery and the meter will be computed and added to, or subtracted from, the reading of the meter. Company Area Engineering Department and Rate Department approvals are required for Primary Rate installations and will only be considered under extenuating circumstances.

4.10.5. Self-Contained Metering

Single-phase and three-phase services with a total connected load of 200 amps or less shall be metered by self-contained meters.

Single-phase and three-phase services with a total connected load of 200-320 amps may be metered by either 320 amp self-contained or instrument transformer (CT) metering.

Single-phase and three-phase services where the total connected load is in excess of, or anticipated to be in excess of, 320 amps shall use instrument transformer (CT) metering.

The total amp rating of the main disconnect(s) shall not exceed 250 amps for a 200 amp continuous duty rated meter socket or 400 amps for a 320 amp continuous duty rated meter socket.

All self-contained single position and/or modular (multi-position) meter sockets that are of either singlephase or three-phase design shall be furnished, owned, installed, and maintained by the customer. All self-contained meter sockets shall be Nationally Recognized Testing Laboratory (NRTL) listed and labeled and will be inspected by the local Public Authority for compliance to the *National Electric Code*[®] and any other applicable codes. The construction of the meter sockets shall also conform to the Company's standards as described in <u>METER SOCKETS</u> in this Section.

K-base type meter socket installations are not allowed within the Company's service areas.

Effective Date April 15, 2015

Note: The service entrance conductor intended to be connected to the high-leg of a 3-phase, 4-wire delta-connected system shall be durably and permanently marked at both ends of the conductor by an outer finish that is orange in color in accordance with 2011 National Electrical Code[®] Article 110.15, or as may be amended, and shall be installed in the far right hand position of the meter mounting block. Refer to the Illustrations Section, **Drawings SC-120 and SC-140**.

4.10.6. Instrument Transformer Metering, Secondary Voltage

Hot sequence is the required installation method for instrument transformer (CT) metering. A cold sequence disconnecting device is <u>not</u> allowed ahead of a CT cabinet unless required by local Public Authority having jurisdiction.

The maximum metered load shall not be greater than 4000 amps.

The CTs and meter-socket will be supplied, owned, and maintained by the Company and shall be installed by the customer. The instrument transformer compartment in a CT cabinet, service connection cabinet, or switchgear CT compartment, and the necessary conduit and fittings shall be supplied, owned, installed, and maintained by the customer. The customer³ shall terminate the line-side and load-side conductors in the CT cabinet, or switchgear CT compartment. The Company will terminate the line-side conductors and the customer shall terminate the load-side conductors in a secondary connection cabinet. The secondary (metering) conductors will be supplied, owned, installed, and maintained by the Company. Customer-owned equipment, other than service conductors, shall not be installed in the space dedicated to instrument transformers.

All current transformers (CTs) shall be installed in a CT cabinet, secondary connection cabinet, or switchgear CT compartment. Refer to <u>METERING</u>, <u>CT Cabinets</u>, <u>secondary connection cabinets</u> (with <u>or without Optional Customer Disconnect Switch and Metering Provisions</u>) and <u>Switchgear CT</u> <u>Compartments</u> in this Section.

The following CT installations are not allowed:

- 1) Rack mounted on mast, pole or side of building using donut or window type CTs.
- 2) Grecian urn or over-the-bushing type CTs mounted in the Company's distribution transformer.

The CTs shall be installed in such a manner that the secondary (metering) terminals are readily accessible from the door of the CT compartment. The CTs shall be mounted such that the H1 "white dot" marking for polarity is on the line side. When bar-type CTs are installed, the bolts used to make the connections shall be the largest standard diameter that will fit through the holes or slots provided for this purpose.

Conductors in CT cabinets and service connection cabinets shall be installed in accordance with the requirements of 2011 *National Electrical Code*[®] Article 312.6, or as may be amended.

³ The Company will terminate the line conductors in the WI and MI service territories.

Metering conduit installed below grade (underground) from the meter-socket to the CT cabinet (or compartment) shall be minimum 1" Schedule 80 PVC. Metering conduit installed above grade (above ground) from the meter-socket to the CT cabinet (or compartment) shall be minimum 1" GRC, IMC, or EMT. Metering conduit shall be a continuous run between the meter socket and the CT cabinet. The conduit run shall not exceed 25 feet in length. Installations requiring conduit runs greater than 25 feet (up to 100 feet maximum) may be allowed with prior approval from the Company's local Electric Meter Department. The metering conduit for installations of 25-100 feet shall be 1 ¼" GRC, IMC, or EMT. If the conduit run exceeds 25 feet in length, the total degrees of bends shall not exceed 180, the equivalent of two 90 degree bends. Junction boxes, conduit bodies (e.g. LB's), or other devices are not allowed without prior approval from the Company's local Electric Meter Department.

The meter socket shall be bonded with a separate bonding conductor in accordance with 2011 *National Electrical Code*[®] Article 250, or as may be amended. Check with Company's local Electric Meter Department for bonding requirements.

4.10.7. CT Cabinets

In addition to the requirements in <u>METERING</u>, <u>Instrument Transformer Metering</u>, <u>Secondary Voltage</u> in this Section, the following requirements shall also be met:

- 1) The CT cabinet (enclosure) shall meet a minimum of NEMA 3R standards.
- 2) The maximum connected load shall not be greater than 4000 amps per metered service.
- 3) The CT cabinet shall be Nationally Recognized Testing Laboratory (NRTL) listed and labeled as a <u>CT enclosure (UL and/or Third-party certification).</u>
- 4) CT cabinets rated from 400 to 800 amps shall have mounting provisions for bar-type CTs. Refer to the Illustrations Section **Drawing TR-40**.
- 5) CT cabinets rated from 801 to 4000 amps shall have a removable bus section with a 12" minimum length, 5" maximum width, and an insulated CT support which will accommodate window-type CTs. The removable bus section shall have an enclosed screw type compression terminal to accommodate a minimum #12 AWG metering potential conductor on the line-side section of the bus. Refer to the Illustrations Section Drawing TR-40.
- 6) The CT cabinet shall be furnished with factory installed landing pads and lugs for phase and neutral conductors.
- 7) The neutral bus shall have a neutral lug which will accommodate one #12 AWG solid through two #10 AWG stranded wire(s) for the metering neutral conductors.
- 8) All instrument transformer compartments shall have barriers between adjacent areas.
- 9) The door shall be hinged either on the left or right side and be equipped with a hasp for a Company padlock with a 5/16" diameter shackle. Effective March 1, 2016, Latching methods shall utilize captive fasteners. Studs with wing nuts are not allowed.
- 10) The installation height of the CTs shall be between 2'-0" minimum and 6'-0" maximum measured from the center of the CTs to final grade. The minimum clearance from the bottom of a wall-mounted CT cabinet to final grade shall be 1'-0".

- 11) The service entrance conductor connected to the high-leg of a 3-phase, 4-wire delta system shall be durably and permanently marked at both ends of the conductor by an outer finish that is orange in color in accordance with 2011 *National Electrical Code*[®] Article 110.15, or as may be amended, and shall be installed in the right-hand phase position for vertical bus or the bottom phase position for horizontal bus in the CT cabinet.
- 12) In <u>TX and NM only</u>. On some types of 400 and 800 amp bar-type CT cabinets, the neutral bus bar can be physically relocated to the center phase position for use in a 3-phase, 3-wire cornergrounded system. The customer shall furnish and install the bus work on the grounded (center) phase.
- 13) In <u>WI and MI only</u>, for overhead services, the line-side conductors shall enter and terminate in the top half of the CT cabinet, and the load-side conductors shall exit and terminate in the bottom half. Likewise, for underground services, the line-side conductors shall enter and terminate in the bottom half of the CT cabinet, and the load-side conductors shall exit and terminate in the top half. Neither the line-side nor the load-side conductors shall cross the horizontal centerline of the CT cabinet.
- 14) For <u>WI and MI only</u>, refer to the table below for CT cabinet minimum dimensions.

Ampacity	Minimum Number of Conductor Terminals to Provide	Vertical Bending Space (1\oplus & 3\oplus)	Depth (3¢)	Depth (1ø)	Width (3¢)	Width (1¢)
400	1	18"	10"	10"	30"	24"
600	2	18"	10"	10"	30"	24"
800	2	24"	12"	10"	32"	24"
1000	3	24"	12"		32"	
1200	4	27"	12"		32"	

DIMENSIONS FOR WALL-MOUNTED CT ENCLOSURES AND SWITCHGEAR (WI AND MI ONLY)

Refer to the Illustrations Section, Drawings TR-20 and TR-40.

4.10.8. Secondary Connection Cabinets with metering provisions.

Single point services to multiple buildings may be metered with a pad-mounted secondary connection cabinet with or without customer disconnect switch. The use of a secondary connection cabinet with a customer disconnect switch allows the customer the ability to de-energize his own service for equipment maintenance without calling the Company to schedule an outage. The secondary connection cabinet shall be located adjacent to the distribution transformer. Refer to the Illustrations Section, **Drawings CC-20, CC-30, CC-40 and CC-50**.

Note: Refer to <u>SERVICES</u> and also <u>METERING</u>, <u>Meter Installation and Ownership</u> in this Section for clarification on the allowable number of service and metering points.

In addition to the requirements in <u>METERING</u>, <u>Instrument Transformer Metering</u>, <u>Secondary Voltage</u> in this Section, the following requirements shall also be met:

- 1) All buildings shall be served from the same transformer.
- 2) The maximum connected load shall not be greater than 4000 amps per metered service.

- 3) Secondary connection cabinets from 400 to 800 amp rating shall have mounting provisions for bar-type CTs. Refer to the Illustrations Section **Drawing TR-40**.
- 4) Secondary connection cabinets from 801 to 4000 amps shall have a removable bus section with a 12" minimum length, 5" maximum width, and an insulated CT support which will accommodate window-type CTs. The removable bus section shall have an enclosed screw type compression terminal to accommodate a minimum #12 AWG metering potential conductor on the line-side section of the bus. Refer to the Illustrations Section Drawing TR-40.
- 5) The neutral bus shall have a neutral lug which will accommodate one #12 AWG solid through two #10 AWG stranded wires for the metering neutral conductors.
- 6) The door(s) shall be hinged either on the left or right side and be equipped with a 3-point latch with provisions for a Company padlock with a 5/16" diameter shackle.
- 7) The installation height of the CTs shall be between 2'-0" minimum and 6'-0" maximum measured from the center of the CTs to the bottom of the cabinet.
- 8) The phase arrangement on 3-phase installations shall be A, B, C front-to-back, top-to-bottom, left-to-right when viewed from the front of the equipment.
- 9) In TX and NM only. On some types of 400 and 800 amp bar-type CT compartments, the neutral bus bar can be physically relocated to the center phase position for use in a 3-phase, 3-wire corner-grounded system. The customer shall furnish and install the bus work on the grounded (center) phase.

The customer shall install the pad and pad-mounted secondary connection cabinet in accordance with the drawings listed in CC "Connection Cabinet" of the Illustrations Section.

4.10.9. Switchgear CT Compartments

In addition to the requirements in <u>METERING</u>, <u>Instrument Transformer Metering</u>, <u>Secondary Voltage</u> in this Section, the following requirements shall also be met:

- 1) Switchgear CT Compartments from 400 to 800 amp rating shall have mounting provisions for bar-type CTs. Refer to the Illustrations Section **Drawing TR-40**.
- 2) Switchgear CT Compartments from 801 to 4000 amps shall have a removable bus section with a 12" minimum length, 5" maximum width, and an insulated CT support which will accommodate window-type CT. The removable bus section shall have an enclosed screw type compression terminal to accommodate a minimum #12 AWG metering potential conductor on the line-side section of the bus. Refer to the Illustrations Section **Drawing TR-40**.
- 3) The maximum connected load shall not be greater than 4000 amps per metered service.
- 4) A metering neutral lug, which will accommodate one #12 AWG solid through two #10 AWG stranded wires for the metering neutral conductors, shall be available near the front of the CT compartment so that it can be safely accessed even if the switchgear is energized.
- 5) All instrument transformer compartments shall have barriers between adjacent areas.
- 6) The door shall be hinged either on the left or right side and be equipped with a hasp for a Company padlock with a 5/16" diameter shackle. **Effective March 1, 2016**, latching methods shall utilize captive fasteners. Studs with wing nuts are **not** allowed.

- 7) The installation height of the CTs shall be between 2'-0" minimum and 6'-0" maximum measured from the center of the CTs to the bottom of the switchgear.
- 8) Current Transformer Compartment shall have a minimum clearance of 12" from the bottom of enclosure door to final grade.
- 9) The phase arrangement on a 3-phase installation shall be A, B, C front-to-back, top-to-bottom, left-to-right when viewed from the front of the switchgear, except for a 3-phase, 4-wire delta system in accordance with 2011 *National Electrical Code*[®] Article 408.3(E) Exception, or as may be amended. The high-leg of a 3-phase, 4-wire delta system shall be installed in the right-hand phase position for vertical bus or the bottom phase position for horizontal bus in the switchgear CT compartment.
- 10) <u>In TX and NM only</u>. On some types of 400 and 800 amp bar-type CT compartment, the neutral bus bar can be physically relocated to the center phase position for use in a 3-phase, 3-wire corner-grounded system. The customer shall furnish and install the bus work on the grounded (center) phase.
- 11) For <u>WI and MI only</u>, refer to the table below for switchgear CT compartment minimum dimensions.

Ampacity	Minimum Number of Conductor Terminals to Provide	Vertical Bending Space (1\oplus & 3\oplus)	Depth With Neutral Bus In Plane	Depth With Neutral Bus Offset	Width With Neutral Bus In Plane	Width With Neutral Bus Offset
1600	5	36"	14"	18"	36"	30"
2000	6	36"	14"	18"	36"	30"
2500	7	42"	14"	18"	36"	30"
3000	8	42"	14"	18"	36"	30"
4000	8	42"	14"	18"	36"	30"

DIMENSIONS FOR SWITCHGEAR CT COMPARTMENTS (WI AND MI ONLY)

Refer to the Illustrations Section, Drawings TR-30 and TR-40.

4.11. TEMPORARY SERVICE

Temporary service may be made available prior to the installation of the permanent meter. Temporary service shall be restricted to as short a time as possible, such as the time necessary for the construction of a building. Temporary service will be provided by the Company in accordance with its established Rate Schedules, Electric Service Connection Policy, and Line Extension Policy.

4.11.1. Overhead Temporary Service

The overhead service drop support shall be supplied by the customer in accordance with the requirements shown in the Illustrations Section, **Drawing TM-10** and the additional requirements of this Section. The support shall be within 70 feet of a pole supporting the Company's secondary lines with conductor no larger than 4/0. The support shall be located in such a manner as to clear all utility obstructions. The overhead drop shall overhang only the property owned and controlled by the customer and shall clear all structures and obstacles in accordance with the Illustrations Section,

Effective Date April 15, 2015

Drawings CR-70, CR-70A, and CR-130 and the applicable requirements for <u>OVERHEAD SERVICE</u> in Section 4. The support shall be installed in such a manner that the installed drop is at a vertical angle of not less than 45 degrees and not closer than 10 feet horizontally to the Company's secondary or primary conductors. Temporary meter panels shall not be installed on a Company pole. The ground rod(s) and grounding electrode conductor shall be furnished and installed by the customer and shall comply with 2011 *National Electrical Code*[®] Article 250, or as may be amended.

4.11.2. Underground Temporary Service

The underground service lateral and meter support shall be supplied and installed by the customer in accordance with the requirements shown in the Illustrations Section, **Drawing TM-30** and the additional requirements of this Section. The meter support shall be installed outside the utility easement and not less than 5 feet from the service pedestal or pad-mounted transformer. The grounding electrode conductor shall be furnished and installed by the customer and shall comply with 2011 *National Electrical Code*[®] Article 250, or as may be amended. The ground rod(s) shall be furnished and installed outside of all utility easements.

4.11.3. Alternate Underground Temporary Service

Where permitted by the local Public Authority, the underground service lateral, and meter support shall be supplied and installed by the customer in accordance with the requirements shown in the Illustrations Section, **Drawing TM-20** and the additional requirements of this Section. The meter support shall be installed at a distance not less than 6 feet from the service pedestal or pad-mounted transformer and shall <u>clear all utility easements and underground obstructions</u>. The temporary service lateral conductors shall be an approved type for direct burial installation and installed by the customer in accordance with the *National Electrical Code*[®]. The grounding electrode conductor shall be furnished and installed by the customer and shall comply with 2011 *National Electrical Code*[®] Article 250, or as may be amended. The ground rod(s) shall be furnished and installed by the customer and shall be installed outside of all utility easements.

4.11.4. Requirements for Temporary Service

Temporary service shall normally be served from the distribution transformer or service pedestal.

The service address shall be prominently displayed on the temporary service installation. Entry into and connections within all pad-mounted or underground facilities will be made by the Company.

The meter socket shall be furnished and installed by the customer. Temporary service installations shall be braced as shown in the respective Drawings in the Illustrations Section to withstand normal service drop tension and normal use of the facility.

Temporary meter service panels shall not be attached to vehicles or trailers. Refer to the Illustrations Section, **Drawings TM-10, TM-20 and TM-30** for acceptable temporary meter panel designs. In the event that a temporary service installation fails or collapses, it will be disconnected by the Company until repaired by the customer.

4.12. PRIMARY METER INSTALLATIONS

Company-owned primary metering installations shall be located on the customer's property within a distance of 5 feet to 25 feet from the access point. Primary metering installations require coordination between the customer and the Company regarding technical details and location. Service at distribution primary voltage requires special engineering considerations; therefore, it is necessary to determine availability of this type of service. The Company Representative shall be consulted well in advance of the time the service will be required so that all design and construction work of both parties may be properly coordinated. The Company's Electric Meter Engineering Department shall also be contacted in advance of design, construction and/or purchase of equipment. Electric Meter Engineering will provide a set of specifications upon customer request. This will reduce the risk of project delays or expensive changes during construction.

Primary voltage installations use both current and voltage instrument transformers regardless of the load current.

4.12.1. Overhead

The primary meter installation will be installed on a Company-owned pole.

4.12.2. Underground

The ownership of the primary metering enclosure depends upon the service territory.

The primary meter installation may be in a Company-owned primary metering cabinet, a customerowned primary metering cabinet or customer-owned primary rated switchgear.

Pre-approval of equipment drawings by Electric Meter Engineering is required for the use of customer-owned primary metering. Equipment drawings detailing all customer-owned primary metering shall be submitted to Electric Meter Engineering for written approval in advance of design construction and/or purchase of equipment. Refer to the Illustration Section Drawings PM-10, PM-20, PM-30 and PM-40.

4.13. METER SOCKETS

4.13.1. Self-Contained 200 Amp and 320 Amp Meter Sockets

Purchasing, installing, connecting, and maintaining self-contained meter sockets shall be the responsibility of the customer.

All meter sockets shall be Nationally Recognized Testing Laboratory (NRTL) listed and labeled, used in accordance with their labeling, installed per the 2011 *National Electrical Code*[®], or as may be amended, and meet any code requirements that may be enforced by the local Public Authority.

All single and multiple position meter sockets installed on the Company's system shall meet the Company's standards for these devices as listed on the following pages. Company Electric Meter Personnel are instructed not to install a meter at a location where the meter socket does not comply with <u>all criteria listed below</u>. Meter sockets will be considered un-approved unless they adhere to this criteria.

- 1) Individual meter sockets shall be constructed from steel. Sockets constructed from aluminum or non-metallic materials are not allowed.
- 2) Individual meter sockets, excluding side-wired type which are bussed on the line side of the meter, used in underground installations shall have the following minimum dimensions:
 - a) 200 amp 19" height x 13" width.
 - b) 320 amp 26 ¹/₂" height x 13" width.
- 3) Temporary cover plates for meter sockets shall be constructed from a non-metallic material.
- 4) Single-phase and three-phase meter sockets shall be rated for either 200 or 320 amp continuous duty and shall be equipped with an approved lever-actuated locking-jaw bypass constructed such that the bypass lever cannot be in the bypass position with the socket cover installed. The bypass handle shall be located on the right side of the meter block when facing the meter block. The only approved bypasses are the Talon (Landis & Gyr) HQ, Square D, Milbank HD (Heavy Duty), Eaton MSL (with the "XCH" suffix), and Cooper B-Line.

Note: Effictive April 15, 2015: Blue Handled Eaton MSL (Meter Socket Lever Bypass) single-phase and three-phase meter sockets using a "XCH" suffix are approved for use.

Note: Effective October 1, 2014 all temporary single-phase commercial services (e.g. construction temporary), shall have a locking jaw lever bypass.

This space is intentially left blank

This space is intentionally left blank.

- 5) Sockets shall be equipped with an insulating, track-resistant polycarbonate safety shield.
- 6) Single-phase and three-phase, three-wire sockets shall have a fifth terminal connected to the neutral within the socket with minimum #16 AWG wire. The fifth terminal shall be installed in the 9 o'clock, rather than the 6 o'clock, position if the meter block design allows. The Company will not furnish or install the fifth terminal.
- 7) Three-phase, four-wire sockets shall have the seventh terminal connected to the neutral within the socket with minimum #16 AWG wire.
- 8) Sockets shall have ringless style covers. No screws, studs or wing nuts are allowed to secure meter covers.
- 9) Sealing means shall provide for a plastic padlock seal with a 0.047" diameter shackle and a key type padlock with a $\frac{9}{32}$ " shackle.
- 10) 320A meter sockets shall have an anti-inversion clip installed in the top right terminal.

Additional Requirements for Self-Contained Multiple Metering Panels:

- 1) Multiple metering panels shall be constructed from steel or aluminum. Panels constructed from non-metallic materials are not allowed.
- 2) Each meter socket shall have an individual ringless style cover with sealing provisions. No screws, studs or wing nuts are allowed to secure meter covers.
- 3) The panel shall have permanent barriers to isolate the customer's disconnect switch and wiring from the metering areas.
- 4) Each line-side compartment shall have provisions for a Company seal, whether or not the compartment is designed to house a meter.
- 5) No multiple metering panels shall have a door that completely encloses the utility metering.

Additional Requirements for Combination Metering Devices:

- 1) Combination metering devices, such as meter/main and meter/panel, shall be constructed from steel or aluminum. Devices constructed from non-metallic materials are not allowed.
- Combination metering devices, excluding side-wired type which are bussed on the line side of the meter, used in underground installations shall have the following minimum dimensions in the metering section:
 - a) 200 amp 9 ½" height x 13" width (height measured from top of enclosure to center of meter block).

Effective Date April 15, 2015

- b) 320 amp 13 ¹/₄" height x 13" width (height measured from top of enclosure to center of meter block).
- 3) Combination metering devices shall have permanent barriers to isolate the customer's disconnect switch and wiring area from the metering area.
- 4) Combination metering devices shall have separate covers on the customer's disconnect switch and wiring area and on the metering area.

Additional Requirements for Metering Pedestals:

- 1) Metering pedestals shall be constructed from steel or aluminum. Pedestals constructed from non-metallic materials are not allowed.
- 2) Pedestals shall be furnished, installed, and maintained by the customer.
- 3) Pedestals shall meet Company and applicable code requirements.
- 4) Pedestals shall be adequately supported to maintain the vertical alignment of the meter in a level and plumb position throughout the life of the installation.
- 5) Metering pedestals with factory installed disconnecting means, shall have permanent barriers to isolate the customer's disconnect switch and wiring area from the metering area.
- 6) Metering pedestals shall have separate covers on the customer's disconnect switch, wiring area and on the metering area.
- 7) The utility metering compartment door shall be hinged either on the left or right side of metering pedestal. Top hinged doors require prior approval from the local Electric Meter Department. A locking mechanism shall be provided to maintain the door in an open position.
- 8) Customer owned equipment other than service conductors, shall not be installed in the space dedicated to the utility metering compartment.
- 9) Sockets shall have ringless style covers. No screws, studs or wing nuts are allowed to secure the meter socket covers.
- 10) Pedestals that have the meter socket located inside a metering compartment enclosure, shall have an 8"x8" lexan viewing window installed.
- 11) Pedestals shall meet additional requirements shown in the Illustrations Section, **Drawings SC-60 and SC-70**.

4.13.2. Instrument Transformer Meter Sockets

The Company will furnish instrument transformer meter sockets. The Company shall be contacted first to determine the rate, load and service voltage. The customer should contact the Company's local Electric Meter Department to obtain metering equipment and to coordinate meter installation.

4.14. METER LOCATION AND INSTALLATION

4.14.1. Meter Location

The customer shall provide and maintain, without cost to the Company, an easily accessible metering location. The Company will locate an acceptable point of delivery and meter location. No wiring dependent upon a meter location shall be started until a definite meter location has been established. The Company will not be responsible for the relocation of the service attachment, service entrance, or metering equipment resulting from an improper location chosen by the customer, which does not meet the requirements of the Company.

Residential self-contained and transformer-rated meters (including CT enclosures) shall be installed outdoors. **The Company will determine meter locations in all instances**. Residential meters originally installed outdoors that, due to alterations or additions to the residence, become enclosed within the building structure (e.g. enclosed patio or garage), where access through a doorway is required, shall be relocated to an outdoor location designated by the Company's local Electric Meter Department.

The relocated service entrance installation shall conform to current Company standards.

Commercial or Industrial self-contained and transformer-rated meter installations (including CT enclosures) shall be installed outdoors.

Multiple Residential/Commercial metering should be installed outdoors.

Requests for multiple indoor metering may be allowed if it is not practical to install the meters outdoors, WITH PRIOR WRITTEN APPROVAL BY SUBMITTING AN EXCEPTION FORM AS DESCRIBED IN THE FOREWORD OF THIS DOCUMENT

If approved, indoor meter installations shall meet the following requirements:

- 1) The customer shall provide Company personnel access to the building and meter room(s) at all times for reading, testing and other maintenance and/or safety purposes.
- 2) Meters shall be grouped together in a common room or other suitable space with direct access from outside the building (or common area).
- 3) The customer must provide a suitable keyless entry for Company access. Customer shall provide the Company with the keyless-entry code (or key code) prior to energizing the service.
- 4) Customer may be required to provide phone lines for meter reading purposes if the building is not readily accessible at all times.
- 5) The meter room(s) shall be dedicated to utility metering only. Meter room(s) are not permitted to be used as customer's storage area.

Mobile homes, construction trailers, and those buildings not intended as dwelling units, such as, but not limited to, contractor's onsite offices, sales offices, mobile studios, mobile stores, or construction job dormitories intended for sleeping purposes only, shall have the meter socket located adjacent to and in line of sight of the structure it supplies. The meter socket shall <u>not</u> be mounted on or attached to the structure. Refer to 2011 *National Electrical Code*[®] Article 550.32(A), or as may be amended.

Manufactured homes may have the meter socket attached to the structure provided the structure meets the definition of a Manufactured Home as defined in 2011 *National Electrical Code*[®] Article 550.2, or as may be amended, and meets the requirements of 2011 *National Electrical Code*[®] Article 550.32(B), or as may be amended. The manufactured home shall be installed on and secured to a permanent foundation and shall provide the necessary structural support for the meter socket attachment.

Effective Date April 15, 2015

Meters originally installed in accessible locations satisfactory to the Company, which become inaccessible by virtue of alterations or new construction, shall be reinstalled at a point designated by the Company at the expense of the property owner.

Meters shall be installed:

- 1) In a location that will be easily accessible to Company personnel at all reasonable hours for reading and maintenance.
- 2) In a location where they will be safe from damage.

Meters shall <u>not</u> be installed:

- 1) On fences, mobile homes or construction trailers.
- 2) Where the meter will, in the Company's opinion, interfere with traffic on sidewalks, driveways, hallways or passageways.
- 3) Where the meter will, in the Company's opinion, obstruct the opening of doors or windows.
- 4) In a location that may, in the Company's opinion, be considered hazardous.
- 5) Where meter reading or servicing may, in the Company's opinion, become impracticable.

4.14.2. Meter Installation

Installation of line-side (ahead of the meter) facilities shall be in conformance with the Illustrations Section drawings.

Installation of the meter socket is the responsibility of the customer. Meter sockets and associated equipment shall be mounted securely and plumb. Expansion bolts, plugs, or anchors shall be used where attachment is made to masonry, concrete, or plaster walls.

The meter socket, service mast, service riser, or any conduit containing conductors on the line side of meters shall not be covered or concealed except when necessary to pass through roof eaves or through floor structures within a building.

The customer shall provide suitable protective equipment approved by the Company if a meter location puts the meter at risk of damage from any means, including falling ice or snow from roof overhangs.

All line-side unmetered conductors shall be in a continuous length of conduit from the point of delivery to the meter socket, cold sequence disconnect, or CT cabinet. No conductors other than line-side conductors shall be permitted in line-side conduits, troughs, or lug landings. Junction boxes, conduit bodies (e.g. LB's), or other devices are not allowed without specific approval from the local Electric Meter Department.

In <u>TX and NM only</u>, a lightning arrestor will be furnished, installed, and maintained by the Company on all 480 volt self-contained services, both 3-wire and 4-wire if required. Refer to the Illustrations Section **Drawing SC-80**.

4.14.3. Meter Socket Identification

The unit number shall be plainly marked on all commercial services and all multiple residential services by a <u>permanent</u> durable means at the meter socket **and** corresponding main service breaker, tenant panel board, doorway or entrance to the apartment, office, store or other premise. <u>The method of identifying the corresponding unit on the meter socket is listed below:</u>

4.14.4. Meter Socket Identification Requirements For Colorado

The meter socket shall be marked with a stamped brass, aluminum, or stainless steel tag securely attached to the meter socket. The stamped tag shall be attached to the exterior, non-removable portion of the meter socket or at the individual meter main disconnect. Any other means of identification is not acceptable.

4.14.5. Meter Socket Identification Requirements For (MI, MN, ND, NM, SD, TX, and WI)

The meter socket shall be marked with a stamped plastic, brass, aluminum, stainless steel tag, or a weather resistant plastic/vinyl sticker securely attached to the meter socket. The stamped tag or permanent plastic/vinyl sticker shall be attached to the exterior, non-removable portion of the meter socket and at the individual meter main disconnect. Any other means of identification is not acceptable.

Note: Meters will not be installed until all units are permanently marked.

4.15. METER MOUNTING HEIGHTS

The mounting height of meters, measured from the center of the meter to final grade or platform outdoors, or to the floor when installed indoors, are as follows:

- 1) Single meter sockets:
 - a) Self-contained or transformer-rated -----4' minimum to 6' maximum
 - b) Meter pedestals ------4' minimum to 6' maximum
- 2) Multiple meter sockets, vertically aligned:
 - a) Indoor ------2' minimum to 6'-6" maximum
 - b) Outdoor ------3' minimum to 6'-6" maximum

The height of multiple meter sockets, either horizontally or vertically aligned, shall be evenly distributed from the center point of the meter stack between the upper and lower height limitations.

If a platform is used to achieve the required mounting heights for a meter installation, it shall be permanent and accessible by a stairway. The minimum horizontal dimensions of the platform shall meet the *National Electrical Code*[®] requirements for working space as specified under <u>METER</u> <u>CLEARANCES</u> in this Section and the Illustrations Section, **Drawing CR-120**.

Mounting heights are also shown throughout the drawings in the Illustrations Section.

4.16. METER CLEARANCES

The minimum depth of working space in front of metering equipment shall be 3', 3'-6", or 4' in accordance with 2011 *National Electrical Code*[®] Article 110.26(A)(1) and Table 110.26(A)(1), or as may be amended. The minimum width of the working space in front of metering equipment shall be the width of the metering equipment or 2'-6", whichever is greater, in accordance with 2011 *National Electrical Code*[®] Article 110.26(A)(2), or as may be amended. No customer-owned equipment may be installed directly in front of metering equipment which includes cold sequence disconnects, CT cabinets, secondary connection cabinets, switchgear CT compartments, and meter sockets.

Refer to the Illustrations Section, Drawing CR-120 for clearance (working space) requirements.

4.16.1. Clearances from Gas Meter Sets

Minimum Clearances from Gas Meter Sets and Sources of Ignition												
Minimum clearance between gas meter sets and sources of ignition.	There shall be a 3' radial minimum clearance between the discharge/release point of the relief device line or regulator vent or connected terminal outlet piping of all gas meter sets and sources of ignition. Any discharge/release point of the relief device line or regulator vent or connected terminal outlet piping must be located outside where the gas can escape freely into the atmosphere and away from any opening into the building.											

Minimum Workii	ng Clearances from Gas Meter Sets
Ū	No electrical equipment shall be installed directly above a gas meter or in an area 12" on either side of a gas meter set.
Working clearance between gas meter sets and other obstructions.	In all cases, sufficient working space (3' preferred) in front of and on either side of the gas meter and associated piping shall allow access for inspection, reading, replacement, or necessary maintenance.

Minimum Clearances from Gas Meter Sets and Common Building Openings or Mechanically Induced Air Intakes												
Common building openings (doors, garage doors, windows, crawl space, attic and dryer vents, etc.)	There should be a 3' radial preferred minimum clearance between the discharge/release point of the relief device line or regulator vent or connected terminal outlet piping of all gas meter sets and common building openings.											
Mechanically induced air intakes	There shall be a 6' radial minimum clearance between the discharge/release point of the regulator vent or relief line vent or connected terminal outlet piping of all gas meter sets and mechanically induced air intakes. The 6- foot clearance is measured from the vent or source of release (discharge port), not from the physical location of the meter set assembly.											

Refer to Illustrations Section, drawings CR-10 and CR-20 for clearance requirements.

4.17. COLD SEQUENCE METERING

Cold Sequence Requirements for MN, MI, ND, SD, and WI

Cold sequence metering <u>is not allowed</u> on commercial and industrial self-contained 480 volt meter installations, for both single-phase and three-phase applications unless required by Local Public Authority having jurisdiction.

Cold Sequence Requirements for TX and NM

Cold Sequence metering <u>is not allowed</u> in the TX and NM Service Territory. "Hot Sequence Metering" will be the required installation method for all metering applications. Hot Sequence Metering is defined as "the electric meter is connected directly to the service conductors without the use of a fault-current limiting disconnect or meter safety-switch device between the electric meter and the supply source. 4.17.1. <u>Cold Sequence Requirements for CO</u>

All new, rewired, or altered <u>commercial and industrial self-contained</u> meter installations (all installations other than residential) for services up to 320 amp, single-phase and three-phase, require the installation of a fusible load-make/load-break safety or pullout switch with fault current-limiting fuses ahead of each individual meter. Commercial and industrial installations may be subject to available fault currents up to 100,000 symmetrical RMS amps. Current-limiting fuses shall be selected to limit faults to 10,000 symmetrical RMS amps at the meter.

Exception 1: A fault current-limiting circuit breaker may be utilized in lieu of a fusible load-break safety or pullout switch if pre-approved by the Company's Electric Meter Engineering Department. The request shall be submitted in writing through the written exception process and include a fault-current analysis report by a registered professional engineer. All calculations shall be based upon the worst-case transformer percent resistance, percent reactance, and percent impedance values shown in Section 5, Tables I through V.

Exception 2: Multiple commercial tenant meter sockets are permitted to have a single fusible current-limiting main disconnect ahead of the common bus to limit fault current to 10,000 amps. Each individual meter may be connected either cold sequence or hot sequence with the disconnecting means (switch or circuit breaker) located adjacent to the meter socket. A fault current-limiting circuit breaker may be utilized for the main disconnect if Company approved in accordance with Exception 1 above.

Exception 3: <u>Single-phase</u> commercial installations up to 320 amps are permitted to be hot sequenced provided all three of the following conditions are met:

- (1) Only one meter is served by the overhead service drop or underground service lateral.
- (2) The available fault current is below 10,000 amps. The Company may require a faultcurrent analysis report be provided to verify if an installation meets this requirement.
- (3) The service voltage is 240 volts or less.

Note: Three-phase meters do not qualify for this exception except as specified in <u>HOT</u> <u>SEQUENCE METERING</u>, <u>Residential</u> in this Section.

A cold sequence disconnect shall be furnished, owned, installed, and maintained by the customer.

The cold sequence disconnect shall be installed on the same wall directly ahead of and within 24" of the meter.

Effective Date April 15, 2015

The cold sequence disconnect shall contain provisions for a Company wire seal for the cover and a Company padlock in the operating handle lock-off position. Wire seals will be used by the Company to secure the enclosure from unauthorized entry and will allow the customer emergency access to reset breakers or to replace fuses. A Company padlock will only be used to lock disconnects in the off position <u>for services that are shut off</u>.

The cold sequence disconnect shall not be operated by the customer except for emergency conditions. For seasonal loads or service discontinuance, the cold sequence disconnect shall not be operated in an off position in lieu of a service disconnection by the Company. Customers requiring a service to be discontinued shall contact the Builders Call Line.

Note: All Company-owned meters shall stay energized up to the line side terminals of the meter socket, in order to obtain information concerning connected load, to measure or test service, to read meters, or for other purposes incidental to the supplying of electric service.

The amp rating of the cold sequence disconnect shall not exceed the amp rating of the meter socket and shall be installed in accordance with 2011 NEC[®] Article 230, or as may be amended.

Tables VII through IX in Section 5 can be used to determine if the available fault current at a single-phase electric meter socket is less than 10,000 amperes based on a specific transformer size and service conductor size and length.

4.18. HOT SEQUENCE METERING

4.18.1. Residential

Residential self-contained meter installations, both single-phase and three-phase, shall be hot sequence metering.

In Colorado only, if the fault current does exceed 10,000 amps at the electric meter, instrument transformer (CT) type metering shall be utilized.

Exception 1: A fault current-limiting circuit breaker shall be utilized in lieu of a fusible load-break safety or pullout switch if pre-approved by the Company's Electric Meter Engineering Department. The request shall be submitted in writing through the written exception process and include a fault current analysis report by a registered professional engineer. All calculations shall be based upon the worst-case transformer percent resistance, percent reactance, and percent impedance values shown in Section 5, Tables I through V.

Note: Exceptions will not be granted for the use of any type of fault current-limiting fuses ahead of the meter for single family residential applications.

Exception 2: Multiple residential tenant meter sockets are permitted to have a single fusible current-limiting main disconnect ahead of the common bus to limit fault current to 10,000 amps. Single-phase or three-phase commercial house power meters (e.g. common lighting, emergency lighting, or laundry facilities) may be protected by the current-limiting main disconnect that serves the residential meter stack. Common lighting, emergency lighting, or laundry facility meters not fed from a protected meter stack shall be cold sequenced. A fault current-limiting circuit breaker may be utilized for the main disconnect if Company-approved in accordance with Exception 1 above.

4.18.2. Commercial and Industrial

Refer to COLD SEQUENCE METERING in this section for jurisdictional requirements for commercial and industrial self-contained metering.

Hot Sequence is the required installation method for commercial and industrial instrument transformer type (CT) metering.

Note: Cold sequence disconnects are not allowed ahead of the CT cabinet, unless required by *local Public Authority having jurisdiction.*

SECTION 5

5. TRANSFORMERS

Necessary transformers will be installed and maintained by the Company in accordance with its established Rate Schedules, Electric Service Connection Policy, and Line Extension Policy.

The Company will not furnish transformers unless they are of standard size and voltage as established by the Company for the locality where the service is rendered. The customer shall notify the Company in advance of any change in the customer's load requirements that may affect the installed transformer capacity.

If the customer's power requirement, within six months after the installation of transformers, proves to be less than shown in the application for service, the Company may make a reduction in the installed transformer capacity and the customer will be required to pay the Company the cost of making the change.

If the customer's power requirement, within six months after the installation of transformers, proves to be more than the installed transformer capacity, the Company may make an increase in the installed transformer capacity and the customer will be required to pay to the Company the cost of making the change.

5.1. GROUNDING

All service systems that operate below 1000 volts contain a grounded neutral or a grounded phase conductor used as a circuit conductor in the system. The grounded neutral or grounded phase conductor is grounded at the supply transformer and will be run from the transformer bank to the meter socket and to each service disconnection means in accordance with 2011 *National Electrical Code*[®] Article 250.24(B), or as may be amended.

Customers requiring an ungrounded service for operation of a ground detection system, or for other operations permitted by the *National Electric Safety Code*[®], shall submit an exception request detailing the special circumstances necessitating the request. In addition, the customer shall state in the exception request that he is aware of and accepts the increased risk to personal safety associated with an ungrounded service. When supplying an ungrounded service results in an additional cost to the Company, the additional cost may be passed on to the customer.

5.2. SPECIAL RULES

When a customer furnishes transformers or other equipment, in accordance with the applicable Company Rate Schedule, Electric Service Connection Policy, and Line Extension Policy, the Company accepts no responsibility for maintaining or replacing the customer's transformers or other equipment if damaged or destroyed.

Company Rate Schedules for primary metering installations require that the customer provide and own all equipment beyond the point of delivery. In unusual cases, the Company may rent transformers, if available, to the customer in accordance with the Company's Rules and Regulations.

The customer shall provide a minimum of ten (10) feet level clearance on the door side(s) of padmounted transformers for hot-stick operation and ten (10) feet level clearance on the door side(s) of pad-mounted primary metering cabinets for instrument transformer maintenance. Transformers shall not be located under any overhang (roof, balcony, stairs, etc.). Clearance requirements are shown in the Illustrations Section, **Drawings CR-30, CR-40, CR-50, CR-60, CR-90 and CR-100**.

5.3. FAULT CURRENT

It is the intent of the Company to address the customer's need for information concerning fault current and transformer protective device requirements pertaining to new construction, rewire, or additional load. Refer to 2011 *National Electrical Code*[®] Article 110.9 Interrupting Rating and Article 110.16 Flash Protection, or as may be amended.

Tables IA through V in this Section show the available RMS symmetrical fault currents that may be expected at the secondary terminals of distribution transformers. Each fault current value listed in the tables is based on the lowest percent impedance transformer that might be set initially or as a replacement. No primary source or secondary line impedance has been included since it is generally relatively small, may change, and cannot be accurately forecasted.

Note: Because an overloaded transformer is typically replaced by the next larger size transformer, and an under-loaded transformer may be replaced by the next smaller size transformer, the customer is encouraged to use this range of transformers to perform their studies and select equipment such as current limiting fuses, breakers and switchgear bus bar bracing.

Table VI through VIII in this Section can be used to determine if the available fault current at a singlephase electric meter socket is less than 10,000 amperes based on specific transformer size and service conductor size and length, which may allow a single-phase commercial installation to be hot sequenced. Refer to Section 4, <u>COLD SEQUENCE METERING</u>, Exception 3 for the exact requirements.

Due to the variability of the transformer and electric distribution system characteristics these tables are to be used as a general guideline and shall not be used as a design tool to replace engineering that may be required by the Code Authorities having jurisdiction. Customers or contractors requiring specific fault current calculations should consult a registered professional engineer of their choice.

Two types of faults are possible on a single-phase transformer having a 120/240V secondary: 1) across terminals having 120V between them, and 2) across terminals having 240V between them. While the 120V fault is higher at the transformer terminals, it attenuates more rapidly as the effect of cable impedance is added. Because of this affect, the 240V fault is often higher at the meter or CT enclosure. The following tables have been developed to aid in determining the available fault current levels at the electric meter. In addition, the tables can be used to determine the number of feet of a given size conductor between the transformer and the terminals of the meter needed to limit the available fault current to 10,000 amps.

Note 1: All residential installations served from a single-phase pad-mount transformer shall use the calculations based on the installation of a 50kVA minimum transformer.

Note 2: All temporary construction meter installations may use the actual transformer size.

5.4. ARC FLASH

It is the intent of the Company to address a customer's need for information concerning arc flash data requires as follows.

For Secondary Voltage Services the Company will provide, upon request from the customer:

- 1. Transformer size, primary voltage, secondary voltage, and typical percent impedance
- 2. Transformer primary fuse information size and type.
- 3. Maximum available secondary symmetrical three-phase fault current, from Tables 1A through V in this Section.

For Primary Voltage Services (excluding network services)⁴ the Company will provide, upon request from the customer:

- 1. Calculated symmetrical bolted three-phase fault current, bolted single-line ground fault current and X/R ratio at the service point.
- 2. The upstream protective device information nearest the service point. This information will include the device model, rating and applicable settings.

Fault current calculations are based upon the distribution system configuration at the time of the calculations. The Company does not provide minimum fault current information or associated protective device clearing times.

It is understood that this data is to be used for arc flash calculations. Parties using this data must understand that it may change due to various circumstances. The Company will not notify the customer when such changes occur.

Tables IA through V in this Section are only intended to provide the basic information necessary for secondary service customers to make their own internal system fault current and arc flash calculations. Primary service customers will still need to consult with a Company Area Engineer, to obtain fault current and protective device information for their service locations.

<u>It is highly recommended when customers are performing maintenance work on or near</u> <u>exposed equipment or circuit parts that their electrical system be de-energized whenever</u> <u>possible.</u>

⁴ For network service information, please contact the area engineer.

TABLE IA

	SINGLE-PHASE OVERHEAD TRANSFORMERS																			
	SINGLE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER																			
	Transformer Protective Device																			
	NSP PSCo SPS																			
TR	TR	TR	TR	Fault Current	TR	TR	TR	Fault Current	4 kV	15 kV	25 kV	·	35 kV	4 kV	15 kV	25 kV	4 kV	15 kV	25 kV	35 kV
kVA	%R	%Х	%Z	120 V Secondary	%R	%Х	%Z	240 V Secondary				Link	Current Limiter							
10	1.5	1.2	1.9	4,300	1	1	1.4	2,900	10T	3T	2T	2K	12 Amp	10K	1.4*	0.7*	5.5X	2X	1.25X	0.75X
25	1.5	1.2	1.9	10,900	1	1	1.4	7,400	15T	6T	3T	3K	12 Amp	25K	10K	2.1*	20QA	5.5X	1.5X	1.25X
50	1.5	1.2	1.9	21,700	1	1	1.4	14,800	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	4X	2X
75	1.5	1.2	1.9	32,600	1	1	1.4	22,200	50T	12T	8T	8K	12 Amp	65K	25K	15K	50QA	20QA	7X	5.5X
100	1.5	1.2	1.9	43,400	1	1	1.4	29,600	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	7X	4X
150	1.5	1.2	1.9	65,100	1	1	1.4	44,400						140K	40K	25K	125QA	40QA	15QA	5.5X
167																				

* Chance Slo-Fast speed fuses

TABLE IB

	SINGLE-PHASE PAD MOUNTED TRANSFORMERS												
SING	SINGLE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER. ALL FAULT CURRENTS ARE BASED ON 1%R AND 1%X FOR THE TRANSFORMER IMPEDANCE.												
TR	TR TR TR TR Fault Current TR TR TR Fault Current TR TR TR Fault Current Transformer Protective Device Image: Comparison of the transformer Protective Device TR TR TR TR TR TR TR TR TR <												
kVA	%R	%X	%Z	240 V Secondary	4 kV	15 kV	25 kV	35 kV					
25	1	1	1.4	7,400	25	8	3	3					
50	1	1	1.4	14,800	50	15	8	8					
100	1	1	1.4	29,600	65	25	15	8					
150	150 1 1 1.4 44,400 100 50 25 15												
167	167 1 1 1.4 49,400 100 50 25 15												

TABLE II

	THREE-PHASE PAD MOUNTED TRANSFORMERS												
TH	THREE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER												
					Transformer Protective Device (Bay-O-Net Fuses for NSP, PSCo, and SPS)								
TR	TR TR TR Fault Current Fault Current 4 kV 15 kV 25 kV 35 kV												
kVA	%R	%Х	%Z	120/208 V Secondary	277/480 V Secondary								
75	1	1.25	1.6	13,000	5,600	25	8	3	3				
150	1	1.25	1.6	26,000	11,200	50	15	8	8				
300	1	1.25	1.6	52,000	22,500	65	25	15	8				
500	1	1.5	1.8	77,100	33,400	140	50	25	15				
750	1	5.22	5.32	39,100	16,900	140	65	50	25				
1000	0.86	5.25	5.32	52,100	22,600		65	50	25				
1500	0.86	5.25	5.32	78,200	33,900		140	65	50				
2000	0.86	5.25	5.32		45,200		125	100	65				
2500													

TABLE III

3-PHASE OVERHEAD WYE CONNECETED TRANSFORMER BANKS

THREE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER. ALL FAULT CURRENTS ARE BASED ON 1%R AND 1%X FOR THE TRANSFORMER IMPEDANCE.

						Transformer Protective Device						
	u l		h					l.	NSP			
TR	TR	TR	TR	Fault Current	Fault Current	4 kV	15 kV	25 kV		351	кV	
kVA	%R	%Х	%Z	120/208 V Secondary	277/480 V Secondary				Link	Curr	ent Limiter	
75	1	1	1.4	14,800	6,400	15T	6T	3T	3K	1	12 Amp	
150	1	1	1.4	29,700	12,800	30T	10T	6T	6K	1	12 Amp	
300	1	1	1.4	59,400	25,700	65T	15T	10T	10K	1	12 Amp	
500	1	1	1.4	99,100	42,900	100T	25T	15T	20K	1	12 Amp	
							Т	ransformer	Protectiv	e Device		
									PSCo			
TR	TR	TR	TR	Fault Current	Fault Current	4	kV	15	kV		25 kV	
kVA	%R	%X	%Z	120/208 V Secondary	277/480 V Secondary							
75	1	1	1.4	14,800	6,400	2	5K	1	0K		2.1*	
150	1	1	1.4	29,700	12,800	4	0K	1	5K		10K	
300	1	1	1.4	59,400	25,700	10	00K		5K		15K	
500	1	1	1.4	99,100	42,900	14	0K 6		65K		25K	
							Т	ransformer	Protectiv	e Device		
	T								SPS			
TR	TR	TR	TR	Fault Current	Fault Current	4 k	V	15 kV	25	5 kV	35 kV	
kVA	%R	. %2	K %Z	120/208 V Secondary	277/480 V Secondary							
75	1	1	1.4	14,800	6,400	200	QA	5.5X	1	.5X	1.25X	
150	1	1	1.4	29,700	12,800	400	QA	15QA	2	4X 2X		
300	1	1	1.4	59,400	25,700	75QA 2		25QA	,	7X	4X	
500	1	1	1.4	99,100	42,900	125	QA	40QA	15	δQA	7X	

* Chance Slo-fast speed fuses

TABLE IV

THREE-PHASE OVERHEAD OPEN DELTA SECONDARY TRANFORMER BANKS

THREE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER. DELTA SECONDARY TRANSFORMER BANK EQUIVALENT IMPEDANCE VALUES: MODEL AS NEEDED USING THE SINGLE-PHASE OVERHEAD TRANSFORMER IMPEDANCE VALUES SHOWN IN TABLE IA.

				Transformer Protective Device NSP PSCo											
						NSP				PSCo					
TR	kVA	Fault Current	Fault Current	4 kV	15 kV	25 kV	35	kV	4 kV	15 kV	25 kV	4 kV	15 kV	25 kV	35 kV
Power	Lighting	120/240 V Secondary	240/480 V Secondary				Link	Current Limiter							
10	10	6,144	3,072	10T	3T	2T	2K	12 Amp	10K	1.4*	0.7*	5.5X	2X	1.25X	.75X
10	25	9,935	4,968	15T	6T	3T	3K	12 Amp	25K	10K	2.1*	20QA	5.5X	2.5X	1.5X
10	50	16,944	8,472	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	5.5X	4X
10	75	24,166	12,083	50T	12T	8T	8K	12 Amp	65K	25K	15K	50QA	20QA	7X	5.5X
10	100	31,455	15,728	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X
10	167	51,098	25,549	100T	25T	15T	20K	12 Amp	140K	65K	25K	125QA	40QA	20QA	15QA
25	25	15,362	7,681	15T	6T	3T	3K	12 Amp	25K	10K	2.1*	20QA	5.5X	2.5X	1.5X
25	50	21,514	10,757	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	5.5X	4X
25	75	28,253	14,127	50T	12T	8T	8K	12 Amp	65K	25K	15K	50QA	20QA	7X	5.5X
25	100	35,244	17,622	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X
25	167	54,468	27,234	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA
50	50	30,724	15,362	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	5.5X	4X
50	75	36,653	18,327	50T	12T	8T	8K	12 Amp	65K	25K	15K	50QA	20QA	7X	5.5X
50	100	43,028	21,514	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X
50	167	61,220	30,610	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA
75	75	46,086	23,043	50T	12T	8T	8K	12 Amp	65K	25K	15K	50QA	20QA	7X	5.5X
75	100	51,923	25,962	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X
75	167	69,024	34,512	65T	15T	10T	10K	12 Amp	100K	25K	15K	125QA	40QA	20QA	15QA
100	100	61,448	30,724	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X
100	167	77,563	38,782	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA
167	167	102,618	51,309	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA

* Chance Slo-fast speed fuses

TABLE V

THREE-PHASE OVERHEAD CLOSED DELTA SECONDARY TRANSFORMER BANKS

THREE-PHASE FAULT CURRENT IN RMS AMPS SYMMETRICAL EXPECTED AT THE SECONDARY TERMINALS OF THE TRANSFORMER. DELTA SECONDARY TRANSFORMER BANK EQUIVALENT IMPEDANCE VALUES: MODEL AS NEEDED USING THE SINGLE-PHASE OVERHEAD TRANSFOMER IMPEDANCE VALUES SHOWN IN TABLE IA.

								Т	ransformer	Protect	tive De	evice					
							NSP	.			PSCo			SPS			
TR kVA Power Lighti		A Lighting	Fault Current	Fault Current 240/480 V Secondary	4 kV			5 kV Current Limiter	<u>4 kV</u>	15 kV	25 kV	4 kV	15 kV	25 kV	35 kV		
10	10	10	6,782	3,391	10T	3T	2T	Link 2K	12 Amp	10K	1.4*	0.7*	5.5X	2X	1.25X	.75X	
10	10	25	12,757	6,379	101 15T	6T	3T	3K	12 Amp	25K	1.4 10K	2.1*	20QA			1.5X	
10	10	50	25,515	12,758	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA			4X	
10	10	100	51,031	25,516	65T	15T	10T	10K	12 Amp	100K		15K	75QA			7X	
10	10	167	85,221	42,611	100T	25T	15T	20K	12 Amp	140K	65K	25K	125QA	40QA	20QA	15QA	
25	25	25	16,956	8,478	15T	6T	3T	3K	12 Amp	25K	10K	2.1*	20QA	5.5X	2.5X	1.5X	
25	25	50	25,515	12,758	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	5.5X	4X	
25	25	100	51,031	25,516	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X	
25	25	167	85,221	42,611	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA	
50	50	50	33,913	16,957	30T	10T	6T	6K	12 Amp	40K	15K	10K	40QA	15QA	5.5X	4X	
50	50	100	51,031	25,516	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X	
50	50	167	85,221	42,611	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA	
100	100	100	67,826	33,913	65T	15T	10T	10K	12 Amp	100K	25K	15K	75QA	25QA	15QA	7X	
100	100	167	85,221	42,611	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA	
167	167	167	113,270	56,635	100T	25T	15T	20K	25 Amp	140K	65K	25K	125QA	40QA	20QA	15QA	

* Chance Slo-fast speed fuses

TABLE VI

Minimum length (feet) of low voltage conductor (secondary plus service drop) needed to limit the available 120 or 240 volt fault current from a <u>single-phase transformer secondary</u> to less than 10,000 amps.

Underground Conductor

TRANSFORMER	120/240 VOLT SINGLE-PHASE ALUMINUM CONDUCTOR SIZE											
SIZE (KVA)	#4 #1 1/0 2/0 4/0 350											
25	5'	5'	5'	5'	5'	10'						
50	15'	20'	25'	35'	45'	65'						
100	20'	40'	50'	60'	90'	135'						

Overhead Conductor

TRANSFORMER	120/240 VOLT SINGLE-PHASE ALUMINUM CONDUCTOR SIZE						
SIZE (KVA)	#4	#2	1/0	2/0	4/0	350	500
25	5'	5'	5'	5'	10'	10'	15'
50	15'	20'	30'	35'	50'	70'	90'
75	20'	30'	45'	55'	80'	120'	150'
100	25'	35'	50'	65'	95'	140'	185'

TABLE VII

Minimum length (feet) of low voltage conductor (secondary plus service drop) needed to limit the available 120 or 240 volt fault current from one unit of a <u>three-phase delta transformer secondary</u> to less than 10,000 amps.

Overhead Conductor

The transformer size is the largest single-phase unit of the three-phase bank.

TRANSFORMER	120/240 VOLT SINGLE-PHASE ALUMINUM CONDUCTOR SIZE						
SIZE (KVA)	#4	#2	1/0	2/0	4/0	350	500
25	5'	10'	15'	15'	25'	25'	30'
50	20'	30'	45'	55'	80'	120'	155'
100	25'	40'	60'	75'	110'	165'	215'

TABLE VIII

Minimum length (feet) of low voltage conductor (secondary plus service drop) needed to limit the available single-phase 120\208 volt fault current from one or two units of a <u>three-phase wye transformer secondary</u> to less than 10,000 amps.

Underground Conductor

The transformer size is the three-phase rating.

TRANSFORMER	120/208 VOLT SINGLE-PHASE ALUMINUM CONDUCTOR SIZE					
SIZE (KVA)	#4	#1	1/0	2/0	4/0	350
150	20'	35'	40'	50'	70'	110'
300	20'	40'	50'	60'	95'	140'

Overhead Conductor

The transformer size is the largest single-phase unit of an overhead three-phase bank.

TRANSFORMER	120/208 VOLT SINGLE-PHASE ALUMINUM CONDUCTOR SIZE				
SIZE (KVA)	#4	#2	1/0	2/0	4/0
25	10'	15'	20'	20'	30'
50	20'	30'	45'	50'	80'
100	25'	35'	55'	65'	100'

SECTION 6

6. UTILIZATION EQUIPMENT

All electric wiring, ducts, cables and apparatus, including protective equipment, necessary for utilization of electric service on the customer's side of the point of delivery, shall be furnished, installed, and maintained by the customer. Such equipment should be selected to provide efficient use of energy and good voltage regulation. The customer shall not use any equipment or device that will adversely affect the Company's service to the customer or to other customers. The customer's equipment shall be suitable for the service supplied and shall be installed and maintained in good and safe condition by the customer in accordance with the rules and requirements of the *National Electrical Code*[®], the local Public Authority, and the Company.

6.1. THREE-PHASE VOLTAGE UNBALANCE

Percent Voltage Unbalance = 100 X <u>Maximum Voltage Deviation</u> from Average Voltage Average Voltage

Example: With voltages of 220, 216 and 209, the average is 215, the maximum deviation from the average is 6 and the *Percentage Unbalance* = $100 X \frac{6}{215} = 2.79\%$

Note: These calculations must use phase-to-phase voltages as shown in the example. Phase-to-neutral voltages may give inaccurate results.

The Company's goal is to limit the maximum steady-state voltage unbalance to 3 percent, in accordance with ANSI C84.1. Voltage unbalance will be measured at the customer's service entrance with all loads disconnected.

The customer's load may affect voltage measurements because of 3-phase load and power factor unbalance. Because it is not always practical to require the customer to disconnect all load, the Company may take measurements by measuring individual phase loads and power factors and calculating their effect on measurements taken without disconnecting the load.

When a customer's three-phase service voltage is found to have an unbalance greater than 3 percent, the Company will act to reduce the unbalance and bring it within these limits within a reasonable length of time.

6.2. HARMONICS

There is a growing proportion of harmonic producing non-linear loads on distribution systems. Excessive harmonic distortion on the distribution system can have adverse effects on both utility and customer equipment. To limit the harmonic currents and resulting harmonic voltages created by non-linear loads, the guidelines included in IEEE Std 519-1992 "IEEE Recommended Practices and Requirements for Harmonic Control in Electrical Power Systems" shall be followed. The following table gives the allowable limits of electric current distortion at the point of delivery.

Maximum Harmonic Current Distortion in Percent of IL						
Individual Harmonic Order (Odd Harmonics)						
I _{sc} /IL	h <11	11≤h <17	17≤h <23	23≤h <35	35≤h	TDD
<20	4.0	2.0	1.5	0.6	0.3	5.0
20<50	7.0	3.5	2.5	1.0	0.5	8.0
50<100	10.0	4.5	4.0	1.5	0.7	12.0
100<1000	12.0	5.5	5.0	2.0	1.0	15.0
>1000	15.0	7.0	6.0	2.5	1.4	20.0

Current Distortion Limits for General Distribution Systems (120 through 69,000 V)

- "I_{SC}" is the short circuit current (aka fault current) available from the Company at the Point of Delivery.
- "IL" is the maximum demand load current of the customer (fundamental frequency component).
 IL may be calculated as the average monthly maximum demand interval current for the preceding twelve months.
- "h" is the order of the harmonic.
- Even harmonics are limited to 25% of the odd harmonic limits listed in the table.
- The current distortion limits apply to the demand interval in use, either 15 or 30 minutes.
- Current distortions that result in a direct current offset (e.g. half-wave converters) are not allowed.
- For short periods such as during start-up or unusual conditions, the limits may be exceeded by 50%.
- All power generation equipment shall comply with the $I_{SC}/I_L{<}20$ distortion limits regardless of the actual I_{SC}/I_L

• "TDD" is the total harmonic distortion in percent where:
$$TDD = \frac{(I_2^2 + I_3^2 + I_4^2 + \dots I_h^2)^{1/2}}{I_L} * 100$$

• Individual harmonic current distortion is: % $I_h = \frac{I_h}{I_L} * 100$

THD, whether voltage or current, is always an instantaneous quantity given as a percent of the fundamental (60 Hz) voltage or current. The total harmonic distortion (THD) rating of equipment is the harmonic current distortion when the equipment is operating at rated load. When a power quality meter used in a PQ study indicates a current THD, it is stating the harmonic current as a percent of the fundamental current at a given instant in time.

TDD is the average distortion over a demand interval. To determine the average maximum demand interval value, the average of the maximum demand interval for each of the preceding twelve months is determined and then averaged (I_L). The harmonic current limit is in percent of this average fundamental load current over a demand interval. The current limit does not apply to THD. The objective of the limits provided in the above table is to ensure the composite effect, on the supply system, of all harmonic current contributions, are held to a level such that the resulting supply voltage harmonic distortion is under the desired threshold.

For example: If the 12 month average of the monthly maximum demands currents for a customer

equals 150 ampere (IL) and the available fault (ISC) is 5000A, then the ratio is 33, the total demand distortion (TDD) limit is 8%, and the harmonic current limit is 12A ($0.08 \times 150A = 12A$). The harmonic current content of the customer's load should normally be under the 12A level. On rare occasions, the harmonic current can briefly be up to 18A ($12A \times 1.5 = 18A$) and still comply with the 8% current distortion limit used in this example.

6.3. POWER FACTOR ADJUSTMENT

Requirements for power factor adjustment vary depending on the Company's established Rates, Rules and Regulations. Contact the Company for specific information.

Low power factor has an adverse effect, not only on the Company's electric system, but also on the customer's electric system. Improvement in the latter alone often warrants the customer's installation of high power-factor equipment.

6.4. <u>MOTORS</u>

Appliances and apparatus should be equipped with motors which will provide the customer with satisfactory operation of the appliance and at the same time avoid interference with service to other customers. Motors may cause voltage disturbances resulting in flickering lights, television interference, and other objectionable conditions.

6.4.1. Motor Identification

All motors connected to the Company's lines shall bear a manufacturer's nameplate indicating horsepower, continuous or intermittent duty, speed, voltage and current ratings. When a motor is rewound to produce a change in the original design, a new nameplate shall be attached indicating the new characteristics.

6.4.2. Voltage

All new motor installations shall be designed to operate on the type of service provided by the Company. The Company's Area Engineering Department will advise the customer as to the type of service available at the location where the motor is to be used. Inquiry should be made before purchasing or installing the motor.

6.4.3. Allowable Starting Current


The starting current characteristics of an electric motor are of primary importance to the voltage disturbance the motor will create on the Company's system. The starting kVA/hp for large motors generally does not exceed 6 times the full load kVA/hp. The resulting voltage drop to the system may be acceptable under certain conditions. Starting current can be limited by the motor design or by use of auxiliary control equipment which reduces the voltage drop at the motor terminals during the starting interval. The auxiliary control equipment shall comply with the limitations provided under HARMONICS in this Section. Automatically controlled motors shall be adjusted to not exceed the starting limitations provided by the Company. Reduced voltage starting equipment that chops the voltage waveform may not meet these requirements (i.e. SCRs, thyristors, etc.). The voltage flicker that is produced by starting automatically controlled motors shall meet the limitations specified under MOTORS, Voltage Flicker in this Section.

Depending on the service size, the starting current of residential central air conditioners can cause objectionable voltage flicker. The magnitude of the voltage flicker increases with the size of the air conditioner. Contact the Company Area Engineering Department when assistance is required to determine actual field conditions and limitations.

6.4.4. Voltage Flicker

The Company uses IEEE Standard 141-1976 as a guideline for the level of allowable flicker. Customers are not allowed to start any load on the Company's system that produces unacceptable levels of flicker which affect other customers. Customers are responsible for correcting unacceptable flicker problems in a timely manner when notified by the Company.

The Company offers assistance to customers in regard to flicker problems. Fees may apply for these services.



Frequency Between Dips

6.4.5. Horsepower Rating

Motors rated 5 horsepower or smaller shall be single-phase unless an established three-phase service exists. Single-phase motors larger than 5 horsepower will <u>not</u> be permitted on services supplied on a residential rate schedule without permission of the Company. Single-phase motors larger than 5 horsepower may be permitted on services supplied on a non-residential rate schedule with Company approval. Larger motors may require starting compensation to limit voltage variation on the system - consult the Company if there is any doubt. The Company will not be held responsible for, nor continue service to, motors with unacceptable starting characteristics.

6.4.6. Grounding

The frame of all motors and starters shall be grounded in accordance with the *National Electrical Code*[®].

6.4.7. Protection of Customer Owned Equipment

Whenever the inherent design of a motor or the characteristics of the load which it serves are such that either automatic reclosing of the electric circuit after a power interruption or sustained low voltage would damage either the motor or the driven equipment, the customer should provide adequate protection to prevent such damage. Starting compensators, auto starters, or equivalent apparatus included in each motor installation should be equipped with under-voltage protection to return the starting apparatus to the "off" position upon failure of the supply circuit.

Three-phase motors which would cause damage to the driven equipment due to a reversal of motor rotation should be equipped with reverse-phase relays to disconnect the motor from the line if it should receive single-phase or reverse-phase power. In addition, mechanical devices should be installed to prevent damage due to travel of the driven mechanism in the wrong direction. The Company assumes no liability for damage resulting from single-phase or reverse-phase operation of three-phase equipment.

Three over-current protective devices should be provided for three-phase motors.

6.5. NON-LINEAR LOADS

It is necessary that welders, x-ray machines, variable-speed motors, and any other large non-linear loads, permanent or temporary, be installed and operated in such a manner that they will not impair service to other customers.

The limited use of single-phase transformer type welders is permitted when adequate transformer and distribution capacity is available, provided the maximum welder input cannot at any time exceed 60 amperes at 240 volts or 30 amperes at 120 volts. The customer shall consult the Company prior to the purchase or installation of welders exceeding these limits. Service for motor-generator and synchronous converter type welders will be governed by the rules and regulations for motors.

6.6. WATER PIPE THAWING

Because of the danger of damage to its equipment and impairment of its service, the Company does not permit direct line connection to water pipes for thawing purposes. Customers or contractors desiring service for water pipe thawing apparatus should consult the Company.

6.7. SPECIAL APPARATUS

The customer shall consult with the Company before any special apparatus or any apparatus requiring extremely close voltage regulation is connected. It is necessary that electrical equipment be installed and operated in a manner that will not impair service to other customers. The use of welding machines, x-ray machines, elevators, or other equipment having fluctuating or intermittent load characteristics, or having an abnormal effect on voltage, may require furnishing service through isolated transformers and separate service drops or excess capacity facilities in order to protect the quality of service to the customer or to other customers. The Company reserves the right to charge the customer the full cost of facilities necessary to provide any special service required by such equipment and to prevent any impairment in service to other customers.

6.8. LOAD BALANCE

No single-phase loads in excess of 50 kVA on a 4.16 kV system or 100 kVA on higher voltage systems will be served except by special arrangement with the Company. Lower limits may apply in certain service areas. The customer's wiring on three-wire, single-phase installations shall be so arranged that the connected load from one phase to neutral shall not exceed 60 percent of the customer's total connected load. The use of single-phase loads on three-phase services shall not unbalance the current per phase more than ten percent. The percentage unbalance is calculated by taking the maximum deviation from average amperage and dividing it by the average amperage as shown in the following example:

A phase current 38 amps B phase current 38 amps C phase current 44 amps				
Average current = <u>38</u>	<u>8 + 38 + 44</u> = 40 amps 3			
Maximum Deviation	44 – 40 = 4 amps			
Percent unbalance	<u>maximum deviation</u> x 100 average current			
Percent unbalance	$\underline{4} \times 100 = 10\%$			

The Company normally will not install three-phase where single-phase is adequate. Exceptions can be made where it is mutually advantageous to both Company and the Customer. Normally, motors up to and including 10 horsepower rated at NEMA Codes A through G can be served single-phase. It is strongly recommended that no residential customers be served from any single-phase transformer which serves a single-phase motor of 5hp or greater. Three-phase motors connected using add-a-phase are considered as single-phase motors.

SECTION 7

7. SPECIAL TYPES OF SERVICE

7.1. NON-STANDARD CONSTRUCTION

Non-standard construction is contingent upon prior approval by the Company. Standard electric service is provided from a single source of supply under the terms, conditions, and Rules and Regulations of the Company's Tariff on file and in effect with the Commission. Any change from standard service, which is within the limits prescribed by the Commission, will be at the customer's expense. This includes all engineering, installation, maintenance, and material costs required to provide and maintain this non-standard construction.

Where additional transformer installations are requested solely to limit the size and length of customerowned services, the additional costs of such installations may be charged to the customer as "Non-Standard Construction".

7.2. DATA PULSES

Meter pulses generated for customer use as data to their load management system

Data pulses are generated by an electric meter at a rate which is proportional to the load. Customers may purchase data pulses which, when accumulated over a demand interval and multiplied by a pulse value, will represent the customer's demand. The customer's calculated demand and corresponding demand interval will not duplicate the Company's billing demand and demand interval but will be useful in controlling the customer's demand limits.

Customer accessible data pulse wiring will be provided within a junction box located next to the existing meter. A data pulse will consist of a change in state of a Form "C" contact with the "K" lead serving as the common terminal. The meter pulse contacts are rated 100 milliamps at 120 volts AC or DC.

The pulse initiator and the associated pulse value are an integral part of the demand meter. The selection of equipment for a particular installation will determine the pulse value. The pulse value will be provided at the time of the pulse installation, but may change due to necessary changes in metering equipment. The kWh pulse value given to the customer will be for a 3-wire Form C connection. If the customer's load controller uses a 2-wire Form A connection, the kWh pulse value must be multiplied by a factor of 2. The following formula can be used to determine the kWh value per pulse.

$$kWh \ Pulse \ Value = \frac{Kh \times CT \ Ratio \times PT \ Ratio}{Pulses \ / \ R \ evolution \ x \ 1000}$$

The Company reserves the right to interrupt pulses at any time in order to test or change the meter and to change the pulse value whenever it becomes necessary to upgrade the metering equipment. Every effort will be made to notify the customer when it becomes necessary to interrupt pulses for equipment maintenance. The customer will be notified of any change to the pulse values.

Illustrations Section, **Drawing IR-40** shows possible metering configurations supplying customer data pulses.

SECTION 8

8. DISTRIBUTED GENERATION

The Company will allow customers to connect on-site generating equipment to the Company's system. Generating equipment can include, but is not limited to, fossil fuel generators, wind turbines, hydroelectric turbines, and photovoltaic (solar) inverters. All generating equipment shall be "non-islanding" per IEEE 1547 unless specifically agreed upon with the Company.

8.1. INTERCONNECTION REQUIREMENTS

The customer shall inform the Company of plans to install and connect generating equipment to the Company's system. It is in the best interest of both the Company and the customer to obtain Company interconnection acceptance and approvals before the customer completes final designs or purchases any equipment. Customer-owned generating equipment shall be installed without causing adverse effects to the Company's or customer's equipment and without introducing potentially dangerous situations to the Company's personnel or the public.

Generation that can operate either momentarily or continuously in parallel with Company facilities shall incorporate protective devices (relays, circuit breakers, etc.) and metering equipment as specified by the Company's Interconnection Guidelines. The customer's installation shall meet state Commission rules for distributed generation, all applicable national, state, and local construction and safety codes, and applicable Federal Energy Regulatory Commission (FERC), regional reliability council, and Open Access Transmission Tariff (OATT) rules.

A copy of the Interconnection Guidelines may be obtained from the Company's website under the Energy Partners Section or the Company Area Engineer that is assigned to the geographic area that includes the proposed generation interconnection site. The specific Interconnection Guideline which is applicable depends on the type, size, and operating mode of the generation that is proposed. Normally, generation facilities totaling over 10 MW are connected to the area electric transmission system. The local transmission provider should be contacted for a copy of the interconnection requirements for larger facilities. Usually, contact is made with their System Planning group.

The Company will not assume any responsibility for the protection of the customer's facility or any portion of the customer's electrical equipment. The customer is fully responsible for protecting his equipment from damage caused by faults or other disturbances on the Company's system.

The Company will review the customer's design for interconnection acceptance only. The Company will not approve the reliability or adequacy of the customer's design.

8.2. LABELING/PLACARD REQUIREMENTS

All required labels or placards shall be <u>weatherproof, durable, and permanently</u> (screws or rivets) attached to the meter socket, or other equipment as necessary. Check with the local Area Engineering Department for additional requirements such as, sizing, color scheme, and verbiage.

8.2.1. Generators Operating as a Backup Source

For generating equipment that is designed to operate as a backup source consult the state rules or Company Area Engineering Department.

8.2.2. Generators Operating as a Parallel Source

For generating equipment designed to operate in parallel with the utility grid the following labels are required in addition to any labels required by the state or Authority Having Jurisdiction:

- 1) "Generation System Connected" or similar located on or directly adjacent to the revenue meter socket.
- 2) "Utility AC Disconnect" located on the utility accessible AC disconnect when an AC disconnect is required to be installed.
- 3) If the AC disconnect is not within close proximity to the Company's revenue meter, the Customer shall post at the revenue meter a clearly labeled map showing the location of the revenue meter, the AC disconnect, production meter (if applicable), and generation facility.

8.3. METERING REQUIREMENTS

Certain types of generating equipment may qualify for net metering. Check the tariffs on file with the local utility or regulatory commission for net metered rates.

8.3.1. Net Metering

Net meters are bi-directional meters that measure both directions of power flow and are typically used on distributed generation that utilizes renewable energy sources. Metering both directions of power flow allows customers to generate in parallel with the Company and sell back excess generation.

8.3.2. Production Meters

Production meters, if required, are Company meters that measure the gross generation of a distribution connected generator. When production meters are utilized, there are additional requirements to ensure the safety our personnel and the public.

- 1) A single point of manual AC disconnect shall be installed between the generation source and the production meter, adjacent to the production meter, except in NM.
- 2) The customer supplied production meter socket or CT compartment shall meet all of the requirements in Section 4.

- 3) The production meter shall be located within ten (10) feet of the existing billing meter. If this cannot be accomplished, additional labeling at each meter directing personnel to the other meter location is required. Approval from the local Electric Meter Shop may also be required.
- 4) Self-contained production meter sockets shall have the generation source wired to the line side terminals of the self-contained meter socket. When instrument transformers are utilized for the production metering, the H1 polarity marking shall be facing the customer generation source.
- 5) The production meter socket shall be labeled in accordance with the requirements in Section 4 under <u>Meter Identification</u>.

A customer-owned production meter may be installed at the Customer's expense. This meter will not be supplied or maintained by the Company. If the customer-owned production meter is in series with the Company required production meter, there shall be a manual means of disconnect between the two production meters.

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 76 of 180

Selecting the Correct Self-Contained Meter Socket

Self-contained meter sockets for services less than 600 volts and up to 320 amps.

SINGLE-PHASE SERVICE	PROPER METER SOCKET
120/240 Volts 3-wire	5 - terminal
120/208 Volts 3-wire	5 - terminal
240/480 Volts 3-wire	5 - terminal

THREE-PHASE SERVICE	PROPER METER SOCKET
120/208 Volts 4-wire	7 - terminal
120/240 Volts 4-wire	7 - terminal
277/480 Volts 4-wire	7 - terminal
240 Volts or 480 Volts 3-wire (Corner grounded)	5 - terminal

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 77 of 180

TABLE OF RESPONSIBILITY


Drawing SC-10							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Service Connection	Company	Company					
Service Entrance Conduit and Conductor	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ice And Snow Shield If Required	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

SELF-CONTAINED METER INSTALLATION FROM AN OVERHEAD SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Residential or Commercial (Hot Sequence Installation Shown)

Point of attachment shall not exceed 24' above grade. Foreign attachments to meter housing mast or riser are not permitted. The neutral wire from the 5th terminal on single-phase and the 7th terminal on 3-phase, 4-wire shall be connected to neutral within meter socket.



- 1. Ground rod furnished and installed by customer per NEC®.
- 2. Clearances shall conform to current edition of NESC®.
- 3. The use of a mast may be required above 6000 feet elevation.
- Check with the Company's local Electric Meter Department to determine if service mast and/or ice and snow shield are required. Refer to Drawings SC-20 and SC-20A for details.
- Masts shall be braced if the weatherhead exceeds 48". The company may require bracing for the weatherhead at 48" or under.
- 6. See Section-4 for cold and hot sequence metering requirements.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-08	JD		I-1.3	PAGE I-1.3

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 79 of 180

TABLE OF RESPONSIBILITY

Drawing SC -20 & 20A							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Underground Service Lateral (Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ice And Snow Shield If Required	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Underground Service Residential (6 meters or fewer)


- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Page I – 1.4

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-20 ttachment B.2., Pages 80 of 180


METER ICE AND SNOW SHIELD (Hot Sequence Installation Shown)




- 1. Shield must be capable of protecting meter.
- 2. Meter socket must have minimum 12" clearance from shield in all directions.
- 3. Check with company's local Electric Meter Department to determine if ice and snow shield is required.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy [®]	Mar-13	Dec-07	JD		I-1.5	PAGE I-1.5

METER ICE AND SNOW SHIELD (Hot Sequence Installation Shown)



- 1. Required meter protection will consist of walls and gable roof which are structurally part of the building.
- 2. Walls will be 6' high and 6' apart.
- 3. Gable roof will extend a minimum of 6" beyond drip line (preferably 12").
- 4. Meters will not be set until meter protection is in place and approved by XcelEnergy.



- 1. Required meter protection will consist of walls and gable roof which are structurally part of the building.
- 2. Walls will be 5' high and 4' apart.
- 3. Gable roof will extend a minimum of 6" beyond drip line (preferably 12").
- 4. Meters will not be set until meter protection is in place and approved by XcelEnergy.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Dec-07	New	DR		I-1.5A	PAGE I-1.5A

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 82 of 180

TABLE OF RESPONSIBILITY

Drawing SC-30							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Service Lateral (Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Slip Sleeve/Expansion Joint	Customer*	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Underground Service Residential (6 meters or fewer)


- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

*Customer will be responsible effective March 31, 2014.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-30⁽²⁾ttachment B.2., Pages 83 of 180

DIRECT BURIAL FROM AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Residential or Commercial (Hot Sequence Installation Shown)




NOTES:

1. See Section 4 for cold and hot sequence metering requirements.

2. Check with the Company's local Electric Meter Department to determine if ice and snow shield are required. Refer to Drawing SC-20 and SC-20A for details.

3. Point of delivery at Company facilities on commercial service in Wisconsin and Michigan.



Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 84 of 180

TABLE OF RESPONSIBILITY

Drawing SC-40							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Service Lateral (Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Slip Sleeve/Expansion Joint	Customer*	Customer					
Service Entrance Conduit	Customer	Customer					
Service Entrance Conduit Under Hard Surface	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					


Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

*Customer will be responsible effective March 31, 2014.



NOTES:

1. See Section 4 for cold and hot sequence metering requirements.

2. Check with the Company's local Electric Meter Department to determine if ice and snow shield are required. Refer to Drawing SC-20 and SC-20A for details.

3. Point of delivery at Company facilities on commercial service in Wisconsin and Michigan.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-11	JD		I-1.9	PAGE I-1.9

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 86 of 180

TABLE OF RESPONSIBILITY

	Drawing SC-50							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Service Lateral (Residential)	Company	Company						
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer						
Slip Sleeve/Expansion Joint	Customer*	Customer						
Service Entrance Conduit	Customer	Customer						
Meter Socket	Customer	Customer						
Meter Socket Mounting Structure	Customer	Customer						
Billing Meter	Company	Company						
Load Side Conduit And Conductor	Customer	Customer						
Ground Rod(s)	Customer	Customer						

Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.


*Customer will be responsible effective March 31, 2014.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-50 ttachment B.2., Pages 87 of 180

PERMANENT SERVICE INSTALLATION FROM AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Residential or Commercial (Hot Sequence Installation Shown)

Installation shall be outside of the utility easement and shall be more than 6' from the service pedestal, pull box or pad-mounted transformer.

PREFERRED INSTALLATION ALTERNATIVE SINGLE POST INSTALLATION



2. Point of delivery at Company facilities on commercial service in Wisconsin and Michigan.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-11	JD		I-1.11	PAGE I-1.11

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 88 of 180

TABLE OF RESPONSIBILITY

Drawing SC-60								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Service Lateral (Residential)	Company	Company						
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer						
Service Entrance Conduit Under Hard Surface	Customer	Customer						
Meter Pedestal	Customer	Customer						
Meter Pedestal Extension Unit (Required)	Customer	Customer						
Billing Meter	Company	Company						
Load Side Conduit And Conductor	Customer	Customer						
Ground Rod(s)	Customer	Customer						

Point of Delivery:


Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-60⁴ttachment B.2., Pages 89 of 180

METER PEDESTAL ATTACHED TO BUILDING FROM AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Residential or Commercial (Hot Sequence Installation Shown)



- 1. Adequate space shall be provided for removal of meter pedestal cover when underground conductors are located beneath concrete.
- If concrete is to be installed, conduit shall be furnished and installed by customer. Conduit shall extend 2' beyond concrete and 4" above final grade.3.
- 3. 15" manufacturer's extension required to be installed on all pedestals.
- 4. Point of delivery at Company facilities on commercial service in Wisconsin and Michigan.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-11	Dec-07	JD		I-1.13	PAGE I-1.13

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 90 of 180

TABLE OF RESPONSIBILITY

Drawing SC-70, 70A & 70B								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Service Lateral (Residential)	Company	Company						
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer						
Service Entrance Conduit Under Hard Surface	Customer	Customer						
Meter Pedestal	Customer	Customer						
Meter Pedestal Mounting Base or Direct Burial Kit	Customer	Customer						
Concrete Pad If Required	Customer	Customer						
Billing Meter	Company	Company						
Load Side Conduit And Conductor	Customer	Customer						
Ground Rod(s)	Customer	Customer						

Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.


DIRECT BURIAL OR FREE STANDING PEDESTAL FROM AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Mobile Home, Area Lighting, Sprinkler System etc. Residential or Commercial

Pedestals are not permitted to be installed in or on a mobile home.

Installation shall be outside the utility easement and shall be more than 6' from the service pedestal, pull box or pad-mounted transformer.


DIRECT BURIAL

FREE STANDING



- 1. The free standing pedestal with a manufacturer's footing base shall be mounted on a 3' x 3' x 3" concrete pad with 95% ground compaction to prevent settling of pad.
- 2. The direct burial pedestal shall have manufacturer's extension and stabilizer installed.
- 3. The meter pedestal shall be installed to maintain vertical alignment throughout the life of the installation.
- 4. The electric meter shall face away from the mobile home and preferably face the driveway or road.
- 5. See Section 4 for cold and hot sequence metering requirements.
- 6. Point of delivery at Company facilities on commercial service (except in Wisconsin and Michigan).

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-11	Dec-07	JD		I-1.15	PAGE I-1.15



NOTES:

- 1. Place power supply box a minimum of 10' from pole for working room.
- If communications ground on pole bond to Xcel Energy ground. 2.
- U-Guard for power and telecommunication cable must be on same side of pole. 3.
- Telecommunications power supply box to be grounded with separate ground rod. 4.
- Power supplies shall not be mounted on poles. They shall be pad-mounted as 5. shown above.
- 6. Meters may not be installed on company poles.

Replaces

Jan-11

Drawn by

JD


NESC 384.C - Bonding should be provided between all above ground metallic power 7. and communications apparatus (pedestals, terminals, apparatus cases, transformer cases, etc.) that are separated by a distance of 1.8 m (6 ft) or less. For the purpose of this rule, pole grounds are not considered an aboveground metallic power apparatus and therefore not required to be bonded to the communication apparatus.

Vool Coorden au	Issued
Acel Energy*	Mar-13

Approved	File	STANDARD FOR ELECTRIC INSTALLATI	ON AND USE
	I-1.15A	PAGE	I-1.15A

Docket No. E999/CI-15-755 Information Request MPUC-005 Bachment B.2., Pages 93 of 180

INSTALLATION OF COMMUNICATIONS PAD-MOUNTED POWER SUPPLY



Notes:

1. NESC 384.C

Bonding should be provided between all above ground metallic power and communications apparatus (pedestals, terminals, apparatus cases, transformer cases, etc.) that are separated by a distance of 1.8 m (6 ft) or less. For the purpose of this rule, pole grounds are not considered an aboveground metallic power apparatus and therefore not required to be bonded to the communication apparatus.



VaclEnarrow	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy [*]	Mar-13	Jan-11	JD		I-1.15B	PAGE I-1.15B

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 94 of 180

TABLE OF RESPONSIBILITY

Drawing SC-80								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Pole	Customer	Customer						
Overhead Service Drop	Company	Company						
Service Entrance Conduit and Conductor	Customer	Customer						
Meter Socket(s)	Customer	Customer						
Meter Socket Mounting Structure	Customer	Customer						
Optional Wireway	Customer	Customer						
Billing Meter(s)	Company	Company						
Load Side Conduit(s) And Conductor(s)	Customer	Customer						
Ground Rod(s)	Customer	Customer						
Lightning Arrester	Company	Company						

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.



- Lightning arrester furnished and installed by Company when required in CO, TX, and NM.
- See Section 4 for cold and hot sequence metering requirements.
- 4. Ground rod(s) and conductor furnished and installed by customer per NEC®.



VeelEnewere	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Acel Energy	Mar-13	Jan-11	JD		I-1.17	PAGE I-1.17

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 96 of 180

TABLE OF RESPONSIBILITY

Drawing SC-90								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Service Lateral (Residential)	Company	Company						
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer						
Slip Sleeve/Expansion Joint	Customer*	Customer						
Service Entrance Conduit	Customer	Customer						
Meter Socket(s)	Customer	Customer						
Meter Socket Mounting Structure	Customer	Customer						
Optional Wireway	Customer	Customer						
Billing Meter(s)	Company	Company						
Load Side Conduit(s) And Conductor(s)	Customer	Customer						
Ground Rod(s)	Customer	Customer						


Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

*Customer will be responsible effective March 31, 2014.



- 1. Ground rod(s) furnished and installed by the customer per NEC®.
- 2. See Section 4 for meter socket identification requirements.
- 3. See Section 4 for cold and hot sequence metering requirements.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-11	JD		I-1.19	PAGE I-1.19

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 98 of 180

TABLE OF RESPONSIBILITY

Drawing SC-100							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Underground Service Lateral (6 or fewer Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Multiple Meter Center	Customer	Customer					
Main Disconnect If Required	Customer	Customer					
Billing Meters	Company	Company					
Load Side Conduit(s) And Conductor(s)	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.


Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Page I – 1.20

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-10 Cachment B.2., Pages 99 of 180

MULTIPLE METERING FROM AN OVERHEAD/UNDERGROUND SECONDARY SUPPLY (PREFERRED METHOD TO DRAWING SC-110) Services up to 320 amp 1Ø-3Ø Residential or Commercial

The neutral wire from the 5th terminal on single-phase and the 7th terminal on 3-phase, 4-wire shall be connected to neutral within meter socket.



- 1. See Section 4 for meter socket identification requirements.
- 2. See Section 4 for meter socket requirements.
- 3. See Section 4 for multiple meter panel requirements.
- 4. See Section 4 for cold and hot sequence metering requirements.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Dec-07	JD		I-1.21	PAGE I-1.21

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015

Attachment B.2., Pages 100 of 180

Drawing SC-110							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Underground Service Lateral (6 or fewer Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket(s)	Customer	Customer					
Optional Wireway	Customer	Customer					
Billing Meter(s)	Company	Company					
Load Side Conduit(s) And Conductor(s)	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Underground Service Residential (6 meters or fewer)


- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering. •

Underground Service Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING SC-1 Actionment B.2., Pages 101 of 180

FABRICATED MULTIPLE METERING FROM AN OVERHEAD/UNDERGROUND SECONDARY SUPPLY (ALTERNATIVE METHOD TO DRAWING SC-100) Services up to 320 amp 1Ø-3Ø Residential or Commercial

Lever operated bypass required on all meter sockets.



- 1. Meter sockets and service equipment are furnished by customer.
- 2. See Section 4 for meter socket identification requirements.
- 3. See Section 4 for cold and hot sequence metering requirements.



VaclEnarrours	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy ^{**}	Mar-13	Oct-07	JD		I-1.23	PAGE I-1.23

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 102 of 180


TABLE OF RESPONSIBILITY

Drawing SC-120								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Overhead Service Drop	Company	Company						
Service Entrance Conduit And Conductor	Customer	Customer						
Meter Socket	Customer	Customer						
Billing Meter	Company	Company						
Load Side Conduit And Conductor	Customer	Customer						
Ground Rod(s)	Customer	Customer						

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

WIRING CONFIGURATION FOR OVERHEAD INSTALLATION 120/208 Volt Wye, 120/240 Volt Delta, or 277/480 Volt Wye 3-Phase 4-Wire



- 1. See Section 4 for cold and hot sequence metering requirements.
- 2. Meter housing shall be grounded per NEC®.



2	VaalEnakouks	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
	Xcel Energy *	Jan-11	Dec-07	JD		I-1.25	PAGE I-1.25

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 104 of 180


TABLE OF RESPONSIBILITY

Drawing SC-130							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Service Entrance And Conductor	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

WIRING CONFIGURATION FOR OVERHEAD INSTALLATION 120/208 Volt or 120/240 Volt 1-Phase 3-Wire, 240 Volt Delta 3-Phase 3-Wire, or 480 Volt Delta 3-Phase 3-Wire



1. See Section 4 for cold and hot sequence metering requirements.

2. Meter housing shall be grounded per NEC®.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Dec-07	JD		I-1.27	PAGE I-1.27

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 106 of 180

TABLE OF RESPONSIBILITY

Drawing SC-140							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Service Lateral (6 or fewer Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.


Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

WIRING CONFIGURATION FOR UNDERGROUND INSTALLATION 120/208 Volt Wye, 120/240 Volt Delta, or 277/480 Volt Wye 3-Phase 4-Wire

Lever operated bypass required


7th terminal required and shall be connected to the neutral within the meter socket.

High-Leg, Wild Leg, Power Leg Marking The service entrance conductor intended to be connected to the high-leg of a 3-phase, 4-wire delta-connected system shall be durably and permanently marked at both ends of the conductor by an outer finish that is orange in color and shall be installed in the far right hand position of the meter mounting block.



120/240 Delta





- 1. See Section 4 for cold and hot sequence metering requirements
- 2. Meter housing shall be grounded per NEC®.



Vac	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy [*]	Jan-11	Oct-07	JD		I-1.29	PAGE I-1.29

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 108 of 180

TABLE OF RESPONSIBILITY

Drawing SC-150							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Service Lateral (6 or fewer Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.


Load conductors shall

exit right side, bottom,

WIRING CONFIGURATION FOR UNDERGROUND INSTALLATION 120/208 Volt or 120/240 Volt 1-Phase 3-Wire, 240 Volt Delta 3-Phase 3-Wire, or 480 Volt Delta 3-Phase 3-Wire

Lever operated bypass required.

5th terminal required and shall be connected to the neutral on 1-phase, 3-wire or the gounded phase on 3-phase, 3-wire within the meter socket.



NOTES:

1. See Section 4 for cold and hot sequence metering requirements.

2. Meter housing to be grounded per NEC®.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy	Mar-13	Dec-07	JD		I-1.31	PAGE I-1.31

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 110 of 180


TABLE OF RESPONSIBILITY

Drawing SC-160							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Service Entrance And Conductor	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

WIRING CONFIGURATION FOR OVERHEAD INSTALLATION 120 V 1-Phase, 2-Wire



- 1. See Section 4 for cold and hot sequence metering requirements.
- 2. Meter housing shall be grounded per NEC®.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-11	JD		I-1.33	PAGE I-1.33

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 112 of 180

TABLE OF RESPONSIBILITY

Drawing SC-170							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Service Lateral (6 or fewer Residential)	Company	Company					
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer					
Service Entrance Conduit	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Underground Service Residential (6 meters or fewer)

- At line side terminals of meter socket; or
- Line side of disconnect if main disconnect is used ahead of metering.

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

120 Volt 1-Phase, 2-Wire

Neutral

6 insulated minimum

wire for jumper wire.

be connected to the neutral on 1-phase, 2-wire within the meter socket. (\mathbf{F}) 120/240 Single-phase 0 C LINE 0 \ominus T θ LOAD 0

Line Conductors

Load conductors shall exit right side, bottom, or rear of meter socket when lever type bypass meter socket is utilized. The line side conductors shall be routed along the outermost edges of the meter socket allowing for conductor settling.

Load

Load conductors may

exit any position.

NOTES:

Lever operated bypass required.

5th terminal required and shall

- 1. See Section 4 for cold and hot sequence metering requirements
- 2. Meter housing shall be grounded per NEC®.



Line conductors shall enter

through bottom knockout. Side entry not allowed. Center knockout shall not

be used.

Load Conductors

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 114 of 180

TABLE OF RESPONSIBILITY

	Drawing TR -10	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Meter Mounting Structure, Pole	Customer	Customer
Overhead Service Drop	Company	Company
Underground Service Lateral Commercial (except WI and MI)	Customer	Customer
Underground Service Residential	Company	Company
Service Entrance Conduit	Customer	Customer
Current Transformer Cabinet	Customer	Customer
Metering Circuit Conduit	Customer	Customer
Metering Circuit Conductors	Company	Company
Current Transformers	Company	Customer
Meter Socket	Company	Customer
Billing Meter	Company	Company
Load Side Conduit And Conductor	Customer	Customer
Ground Rod(s)	Customer	Customer

Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.


Underground Service Residential - At line side terminals of CT Cabinet

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer (except Wisconsin and Michigan).

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING TR-1 Chachment B.2., Pages 115 of 180

CURRENT TRANSFORMER INSTALLATION FROM AN OVERHEAD/UNDERGROUND SECONDARY SUPPLY Services Over 400 amp 1Ø-3Ø Residential or Commercial

Installation shall be outside of the utility easement and shall be more than 6' from the service pedestal, pull box or pad-mounted transformer.



NOTE:

1. See Section 4 for current transformer metering requirements.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
9 7 Mar-13	Jan-13	JD		I-2.2	PAGE I-2.2

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 116 of 180

TABLE OF RESPONSIBILITY

Drawing TR -20 & 20A							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Underground Service Lateral Commercial (except WI and MI)	Customer	Customer					
Underground Service Residential	Company	Company					
Service Entrance Conduit	Customer	Customer					
Current Transformer Enclosure	Customer	Customer					
Metering Circuit Conduit	Customer	Customer					
Metering Circuit Conductors	Company	Company					
Current Transformers	Company	Customer					
Meter Socket	Company	Customer					
Billing Meter	Company	Company					
Load Side Conduit And Conductor	Customer	Customer					
Ground Rod(s)	Customer	Customer					


Point of Delivery:

Overhead Service Residential/Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Underground Service Residential - At line side terminals of CT Cabinet

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer (except Wisconsin and Michigan).


CURRENT TRANSFORMER ENCLOSURES Services from 400-800 amps



- 1. Service conductors are not allowed to cross in front of CTs.
- 2. See Section 4 for instrument transformer type, installation details, and requirements.
- 3. For underground services, the load-side conductors shall terminate and exit in the top half of the CT cabinet for WI and MI.
- 4. For overhead services, the load-side conductors shall terminate and exit in the bottom half of the CT cabinet for WI and MI.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-11	Dec-07	JD		I-2.4	PAGE I-2.4

CURRENT TRANSFORMER ENCLOSURES Services from 801-4000 amps



- 1. Service conductors are not allowed to cross in front of CTs.
- 2. See Section 4 for instrument transformer type, installation details, and requirements.
- 3. For underground services, the load-side conductors shall terminate and exit in the top half of the CT cabinet for WI and MI.
- 4. For overhead services, the load-side conductors shall terminate and exit in the bottom half of the CT cabinet for WI and MI.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-11	New	JD		I-2.4A	PAGE I-2.4A

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015

Attachment B.2., Pages 119 of 180 **TABLE OF RESPONSIBILITY**

	Drawing TR -30	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Overhead Service Drop	Company	Company
Underground Service Lateral Commercial (except WI and MI)	Customer	Customer
Underground Service Residential	Company	Company
Service Entrance Conduit	Customer	Customer
Switchgear With Metering Compartment	Customer	Customer
Metering Circuit Conduit	Customer	Customer
Metering Circuit Conductors	Company	Company
Current Transformers	Company	Customer
Meter Socket	Company	Customer
Billing Meter	Company	Company
Load Side Conduit And Conductor	Customer	Customer
Ground Rod(s)	Customer	Customer

Point of Delivery:


Overhead Service Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Underground Service Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Page I -2.5

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING TR-30^{tachment B.2., Pages 120 of 180}

TYPICAL ARRANGEMENTS FOR C.T. COMPARTMENTS WITHIN CUSTOMER OWNED GEAR



SEE DRAWING TR-40 FOR CURRENT TRANSFORMER MOUNTING REQUIREMENTS

- 1. All cabinets shall be UL approved.
- 2. CT compartment shall be locked separately by company.
- 3. Nonmetallic conduit shall extend into CT compartment.
- 4. Line side bus bar hole pattern shall have NEMA 2-hole spacing and be centered on bar in WI and MI only.
- 5. Holes to accommodate 1/2 inch bolts.
- 6. See section 4 for Current Transformer Cabinet requirements

	VaclEnarrow	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
C	Acel Energy"	Mar-13	Jan-11	JD		I-2.6	PAGE I-2.6

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015

Attachment B.2., Pages 121 of 180 **TABLE OF RESPONSIBILITY**

	Drawing TR -40	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Overhead Service Drop	Company	Company
Underground Service Lateral Commercial (except WI and MI)	Customer	Customer
Underground Service Residential	Company	Company
Service Entrance Conduit	Customer	Customer
Switchgear With Metering Compartment	Customer	Customer
Metering Circuit Conduit	Customer	Customer
Metering Circuit Conductors	Company	Company
Current Transformers	Company	Customer
Meter Socket	Company	Customer
Billing Meter	Company	Company
Load Side Conduit And Conductor	Customer	Customer
Ground Rod(s)	Customer	Customer


Point of Delivery:

Overhead Service Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Underground Service Commercial - Point where the Company's facilities are first connected to the electric facilities of the customer.

Page I – 2.7

CURRENT TRANSFORMER MOUNTING REQUIREMENTS FOR CABINETS AND SWITCHGEAR



- 1. White dot on CT is polarity mark and faces line-side.
- 2. See Section-4 for current transformer cabinet requirements.
- 3. Line side bus bar hole pattern shall have NEMA 2-hole spacing and be centered on bar in WI and MI only.



VaclEnarous	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Mar-13	Jan-11	JD		I-2.8	PAGE I-2.8

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 123 of 180

TABLE OF RESPONSIBILITY


Drawing PM -10							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Primary Line Side	Company	Company					
Line-Side Deadends, Cutouts, and Arrestors	Company	Company					
Metering Pole and Line-Side Down Guy if Required	Company	Company					
Instrument Transformers	Company	Company					
Instrument Transformer Rack	Company	Company					
Meter Socket	Company	Company					
Metering Circuit Conduit and Conductors	Company	Company					
Billing Meter	Company	Company					
Load-Side Deadends and Conductors	Customer	Customer					
Load Connections to Company Facilities	Company	Company					
Ground Rod(s), Conductor, or Grid	Company	Company					

Point of Delivery:

Overhead Service Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING PM-1^{Aftpachment B.2., Pages 124 of 180}

COMPANY OWNED OVERHEAD PRIMARY METER INSTALLATION



- 1. Customer facilities not allowed on Company primary meter pole.
- 2. Customer shall provide a pole near primary meter pole for customer switches, fuses, and overhead or underground distribution.
- 3. The length of the slack span shall normally be 40 feet maximum, but in some instances may be limited to 25 feet. Contact the Company local Area Engineer for specifications.
- 4. Overhead to underground service customers are to be served from a separate customer owned terminal pole. Underground does not attach to this pole.



VaalEnakouv	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy [∞]	Mar-13	Jan-11	JD		I-3.2	PAGE I-3.2

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 125 of 180

TABLE OF RESPONSIBILITY


	Drawing PM -20							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Primary line Side & Termination	Company	Company						
Line Side Conduit & Conductors	Company	Company						
Protective Equipment and Enclosures	Customer	Customer						
Switchgear with Metering Bay	Customer	Customer						
Instrument Transformers	Company	Customer						
Meter Socket	Company	Customer						
Metering Circuit Conduit	Customer	Customer						
Metering Circuit Conductors	Company	Company						
Billing Meter	Company	Company						
Load Side Conduit and Conductor	Customer	Customer						

Point of Delivery:

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

For responsibilities of primary line side conduit and conductors in each service area, please contact Company for information.

CUSTOMER-OWNED PRIMARY SWITCHGEAR



Load conductors may not pass through metering bay or service entrance bay.

PRIOR TO PURCHASE OF SWITCH GEAR, WORKING DRAWINGS OF THE METERING BAY SHALL BE APPROVED BY METER ENGINEERING DEPARTMENT

APPROVAL OF ALL SWITCHGEAR DRAWINGS, BY LOCAL AREA ENGINEERING DEPARTMENT IS REQUIRED PRIOR TO PURCHASE

CONTACT METER ENGINEERING DEPARTMENT, FOR INSTRUMENT TRANSFORMER MOUNTING AND INSTALLATION REQUIREMENTS.

- 1. Company will furnish and install incoming service conductors, including terminations.
- 2. Company will furnish and install meters and secondary conductors for meters.
- 3. Company will furnish and customer shall install metering current and potential transformers.
- 4. Company will furnish and customer shall install meter socket.
- 5. Customer will furnish and install all switchgear, protection equipment, and enclosures.
- 6. See Section 4, Primary Meter Installations, for installation details and requirements.
- 7. Provide safety barriers between energized equipment and personnel or ground.
- 8. Meter location to be determined by Electric Meter Department.



VeelEnormu	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Jan-08	Mar-04	DR		I-3.4	PAGE I-3.4

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 127 of 180

TABLE OF RESPONSIBILITY


Drawing PM -30							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Underground Primary Line Side & Termination	Company	Company					
Line Side Conduit & Conductors	Company	Company					
Protective Equipment and Enclosures	Customer	Customer					
Switchgear with Metering Bay	Customer	Customer					
Instrument Transformers	Company	Customer					
Meter Socket	Company	Customer					
Metering Circuit Conduit	Customer	Customer					
Metering Circuit Conductors	Company	Company					
Billing Meter	Company	Company					
Load Side Conduit and Conductor	Customer	Customer					

Point of Delivery:

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

For responsibilities of line side conduit and conductors in each service area, please contact company for information.

CUSTOMER-OWNED PRIMARY SWITCHGEAR SOURCE SELECTIVE SYSTEM WITH SPLIT BUS



Load conductors may not pass through metering bay or service entrance bay.

PRIOR TO PURCHASE OF SWITCH GEAR, WORKING DRAWINGS OF THE METERING BAY SHALL BE APPROVED BY METER ENGINEERING DEPARTMENT

APPROVAL OF ALL SWITCHGEAR DRAWINGS, BY LOCAL AREA ENGINEERING DEPARTMENT IS REQUIRED PRIOR TO PURCHASE

CONTACT METER ENGINEERING DEPARTMENT, FOR INSTRUMENT TRANSFORMER MOUNTING AND INSTALLATION REQUIREMENTS.

- 1. Company will furnish and install incoming service conductors, including terminations.
- 2. Company will furnish and install meters and secondary conductors for meters.
- 3. Company will furnish and customer shall install metering current and potential transformers.
- 4. Company will furnish and customer shall install meter socket.
- 5. Customer will furnish and install all switchgear, protection equipment, and enclosures.
- 6. See Section 4, Primary Meter Installations, for installation details and requirements.
- 7. Provide safety barriers between energized equipment and personnel or ground.
- 8. Meter location to be determined by Electric Meter Department.



VaclEnavour	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Acel Energy*	Dec-07	Mar-04	DR		I-3.6	PAGE I-3.6

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 129 of 180


TABLE OF RESPONSIBILITY

	Drawing PM-40	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Primary Metering Cabinet	Company	Company
Pad, Concrete Pre-cast with Pit	Company	Company
Line Side Conduit & Conductor	Company	Company
Line Side Terminations	Company	Company
Instrument Transformers	Company	Company
Meter Socket	Company	Company
Metering Circuit Conductors	Company	Company
Billing Meter	Company	Company
Load Side Conduit and Conductor	Customer	Customer
Load Side Terminations	Company	Company

Point of Delivery:

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.





- 1. 15 kV, 25 kV and 35kV configurations may vary.
- 2. See Section 4, primary voltage (above 480 volts) for installation details and requirements.
- 3. In TX, NM, and CO only.
- 4. Customer owned conductors must match company owned conductor sizes.
- 5. In areas where there will be above ground metal equipment within 6 ft of switchgear, the NESC requires the equipment to be grounded and the grounds bonded. Install 8 ft of #4 Cu bonding wire 3 ft to the side, 6 in back from the front of the pad and buried 12 in deep. Connect the coil to the ground rod lug, not the switchgear.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Dec-07	JD		I-3.8	PAGE I-3.8

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 131 of 180

TABLE OF RESPONSIBILITY

Drawing TM -10							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL					
Permits and Inspections	Customer	N/A					
Overhead Service Drop	Company	Company					
Meter Socket Mounting Structure	Customer	Customer					
Service Entrance Conduit and Conductors	Customer	Customer					
Meter Socket	Customer	Customer					
Billing Meter	Company	Company					
Load Side Conduit and Conductors	Customer	Customer					
Ground Rod(s)	Customer	Customer					

Point of Delivery:

Overhead Service Commercial - Point where the *Company's* facilities are first connected to the electric facilities of the customer.



- 4. Make sure area is clear of underground obstructions before installing support or ground rod.
- 5. Service drop shall not be at an angle of less than 45° from vertical.
- 6. If utility designated pole is used, the 16' maximum can be increased to 24' maximum.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-11	JD		I-4.2	PAGE I-4.2

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 133 of 180

TABLE OF RESPONSIBILITY

	Drawing TM -20							
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL						
Permits and Inspections	Customer	N/A						
Underground Service Lateral	Customer	Customer						
Meter Socket Mounting Structure	Customer	Customer						
Service Entrance Conduit	Customer	Customer						
Meter Socket	Customer	Customer						
Billing Meter	Company	Company						
Load Side Conduit and Conductor	Customer	Customer						
Ground Rod(s)	Customer	Customer						


Point of Delivery:

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING TM-24 Contended B.2., Pages 134 of 180 TEMPORARY SERVICE INSTALLATION FROM

AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø Commercial Service

The installation shall be outside utility easement and shall be not less than 6' from the service pedestal, pull box or pad-mount transformer and no closer than 10' from the Company-owned pole.



Service address shall be prominently displayed on the temporary service installation.

ſ	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
	Jan-11	Dec-07	JD		I-4.4	PAGE I-4.4

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 135 of 180

TABLE OF RESPONSIBILITY

Drawing TM -30						
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL				
Permits and Inspections	Customer	N/A				
Service Lateral	Customer	Customer				
Meter Socket Mounting Structure	Customer	Customer				
Service Entrance Conduit	Customer	Customer				
Meter Socket	Customer	Customer				
Billing Meter	Company	Company				
Load Side Conductor	Customer	Customer				
Ground Rod(s)	Customer	Customer				

Point of Delivery:

Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING TM-3 Grachment B.2., Pages 136 of 180 TEMPORARY SERVICE INSTALLATION FROM AN UNDERGROUND SECONDARY SUPPLY Services up to 320 amp 1Ø-3Ø **Commercial Service** The installation shall be outside utility easement and shall not be less than 5' from service pedestal or pad-mounted transformer. 1/4"x6"x12" steel ^{6'} maximum 3/32"x1.25"x1.25" steel Check jurisdictional cold 4' ^{minimum} sequence requirements Optional point -1/4"x6"x12" steel of delivery ·3/32"x1"x1" steel Wooden vertical support to be ^{,(2}" Ma[†], constructed of 4"x4" post. W. MINIMUM 3- #6 minimum insulated 300 » Final Grade mum conductors, furnished and installed in 1" Min.-1 1/2" Max. See Section 4 for Meter Socket Requirements. 6' Maximum 4' Maximum liquid tight flexible conduit by 36" length of conductor customer. Maximum length 12' shall be supplied so that 4' minimum termination can be made within the pedestal or pad Point of mounted transformer. delivery The wires may be cut by the Company for proper S' Minimu installation. 12" Maximum The customer shallsupply a liquid tight Minimun box connector. Stake down S. Minimum each corner Final Grade for stability.-Ground rod(s) is furnished and installed by the customer per NEC®

Service address shall be prominently displayed on the temporary service installation.

- 1. Entry into service pedestal or pad mounted transformer shall be made by Company.
- 2. Temporary shall not be connected to overhead supply.



VaclEnarrow	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Mar-13	Jan-11	JD		I-4.6	PAGE I-4.6

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 137 of 180

TABLE OF RESPONSIBILITY

	Drawing IR -20	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Overhead Service Drop	Company	Company
Underground Service Lateral (Residential)	Company	Company
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer
Normally closed relay within meter	Company	Company
Service Entrance Conduit	Customer	Customer
Meter Socket(s)	Customer	Customer
Control wire from meter to junction box	Company	Company
NEMA 3R Junction Box	Customer	Customer
Contactor or Relay	Customer	Customer
Conduit and Conductor for Load Control Device	Customer	Customer
Supply Voltage for Load Control Device	Customer	Customer
Billing Meter	Company	Company
Load Side Conduit and Conductor	Customer	Customer

Page I – 5.1

TIME OF DAY, LIMITED OR OPTIONAL OFF PEAK METERING MI, MN, ND, SD, WI, ONLY



to operate their equipment during "on peak" it can be accomplished by simply de-energizing the control circuit.

- 1. Company will provide normally closed relay within meter.
- 2. Company will provide control wire from meter to junction box.
- 3. Customer will provide and install meter socket(s).
- 4. Customer will provide and install NEMA 3R Junction Box within 24" of meter socket
- 5. Customer will provide and install conduit and wiring for load control circuit.
- 6. Customer will provide and install normally closed relay or contactor.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-11	Dec-07	JD		I-5.2	PAGE I-5.2

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 139 of 180

TABLE OF RESPONSIBILITY

Drawing IR -30						
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL				
Permits and Inspections	Customer	N/A				
Overhead Service Drop	Company	Company				
Underground Service Lateral (Residential)	Company	Company				
Underground Service Lateral (Commercial) (except WI and MI)	Customer	Customer				
Service Entrance Conduit	Customer	Customer				
Meter Socket(s)	Customer	Customer				
NEMA 3R Junction Box	Customer	Customer				
Radio-controlled switch with normally closed relay	Company	Customer				
Conduit And Conductor for Load Control Device	Customer	Customer				
Supply Voltage for Load Control Device	Customer	Customer				
Billing Meter	Company	Company				
Load Side Conduit and Conductor	Customer	Customer				

DUAL FUEL SERVICE METERING MN, ND, SD, ONLY

Contact Company's local Electric Meter Department for additional information.



- 4. Customer will provide and install meter socket(s).
- 5. Customer will provide and install NEMA 3R Junction Box within 24" meter socket.
- 6. Customer will provide and install a radio-controlled switch.
- 7. Customer will provide and install conduit and wiring for load control circuit.
- 9. Customer will provide and install a normally closed relay or contactor.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC IN
Xcel Energy*	Jan-11	Dec-07	JD		I-5.4	PAGE

Docket No. E999/CI-15-755 Information Request MPUC-005

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 141 of 180

TABLE OF RESPONSIBILITY

Drawing IR -40						
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL				
Self Contained Meter Socket	Customer	Customer				
Transformer Rated Meter Socket	Company	Customer				
Billing Meter	Company	Company				
Conduit from Meter Socket to Pulse Device	Company	Company				
Data Pulse Device	Company	Company				
Junction Box	Company	Company				
Data Recorder if Required	Company	Company				
Wires from Pulse Device to Customers Equipment	Customer	Customer				
Conduit from Pulse Device to Customers Equipment	Customer	Customer				

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING IR-40²ttachment B.2., Pages 142 of 180

DATA PULSE DEVICE FOR CUSTOMER LOAD MANAGEMENT SYSTEM



Customer contacts are fused at 1/2 amp, and not more than 120 volts AC or DC shall be applied to any set of contacts.

- 1. The customer accessible terminal strip may be contained in the device box with Y, K, Z channel indication lights.
- 2. The customer accessible data pulse may be installed in an external box without terminal strip and indication lights.
- 3. The type of device and box to be supplied to the customer shall be decided solely by the Company.
- 4. One data pulse box device is required for each set of customer pulses.



Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 143 of 180

TABLE OF RESPONSIBILITY

Drawings CC-10 & 10A						
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL				
Permits and Inspections	Customer	N/A				
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company				
Cable Tray	Customer	Customer				
SCC Concrete Pad	Customer	Customer				
Secondary Connection Cabinet (SCC)	Customer	Customer				
SCC Line-Side Termination Lugs	Company	Company				
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer				
SCC Load-Side Conduit/Sweeps and Conductor	Customer	Customer				

Point of Delivery:


Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.



- 1. Company will furnish and install pad-mounted transformer.
- 2. Company will furnish and install conductors from transformer to secondary connection cabinet including termination lugs at secondary connection cabinet.
- 3. Customer shall furnish, install and maintain continuous and/or separate pad for transformer and secondary connection cabinet per drawing pages CC-40 through CC-60E.
- 4. Customer shall furnish, install and maintain secondary connection cabinet and bus bar hole pattern shall have NEMA spacing (1-3/4" on center) and be centered on bar. SCC bus bar holes to accommodate 1/2" bolts
- 5. Customer to furnish ground rod for bonding to enclosure and at right side of neutral bus bar installed per NEC ®.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy	Jan-13	Dec-07	JD		I-6.20	PAGE I-6.20

SECONDARY CONNECTION CABINET (SCC) PRE-CAST CABLE TRAY SPECIFICATION



Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Oct-07	Mar-04	DR		I-6.21	PAGE I-6.21

Docket No. E999/CI-15-755

Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 146 of 180


TABLE OF RESPONSIBILITY

	Drawing CC -20		
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL	
Permits and Inspections	Customer	N/A	
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company	
SCC Line-Side Termination Lugs	Company	Company	
Cable Tray	Customer	Customer	
SCC Concrete Pad	Customer	Customer	
SCC with Metering Provisions	Customer	Customer	
Metering Circuit Conduit	Customer	Customer	
Metering Circuit Conductors	Company	Company	
Current Transformers	Company	Customer	
Meter Socket	Company	Customer	
Billing Meter	Company	Company	
SCC Load-Side Conduit/Sweeps and Conductor	Customer	Customer	
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer	

Underground Service Commercial – Point where the Company's facilities are first connected to the electric facilities of the customer.

Page I - 6.30

CUSTOMER OWNED PAD-MOUNTED METERING SECONDARY CONNECTION CABINET



- 1. Bus bar phase arrangement shall be A, B, C from front to back, Top to Bottom, Left to Right, NEC® 408.3 (e).
- 2. "B" phase shall be that phase having the higher voltage to ground on 3-phase, 4-wire, delta-connected systems.
- 3. The high-leg shall be marked with an outer finish that is orange in color. NEC® 110.15
- 4. Company will furnish and install pad-mounted transformer.
- 5. Company will furnish and install conductors from transformer to secondary connection cabinet including termination lugs at secondary connection cabinet.
- 6. Customer shall furnish, install and maintain continuous and/or separate pad for transformer and secondary connection cabinet.
- 7. Customer shall furnish, install and maintain secondary connection cabinet and bus bar hole pattern shall have NEMA spacing (1-3/4" on center) and be centered on bar. SCC bus bar holes to accommodate 1/2" bolts.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Mar-13	Jan-13	JD		I-6.40	PAGE I-6.40

Docket No. E999/CI-15-755

Effective Date April 15, 2015


Information Request MPUC-005 Attachment B.2., Pages 148 of 180

TABLE OF RESPONSIBILTY

	Drawing CC -30	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company
SCC Line-Side Termination Lugs	Company	Company
Cable Tray	Customer	Customer
SCC Concrete Pad	Customer	Customer
Connection Cabinet with Metering Provisions	Customer	Customer
Metering Circuit Conduit	Customer	Customer
Metering Circuit Conductors	Company	Company
Current Transformers	Company	Customer
Meter Socket	Company	Customer
Billing Meter	Company	Company
SCC Load-Side Conduit /Sweeps and Conductor	Customer	Customer
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer

Point Of Delivery: Underground Service Commercial – Point where the *Company's* facilities are first connected to the electric facilities of the customer.

CUSTOMER OWNED PAD-MOUNTED METERING SECONDARY CONNECTION CABINET (SCC) WITH CUSTOMER DISCONNECT SWITCH



- 1. Four foot clearance shall be maintained on door sides and three foot clearance on non-door sides of SCC.
- 2. Customer shall furnish and install ground rod(s) for SCC.
- 3. Company will furnish and install pad-mounted transformer.
- 4. Company will furnish and install conductors from transformer to secondary connection cabinet including termination lugs at secondary connection cabinet.
- 5. Customer shall furnish, install and maintain continuous and/or separate pad for transformer and secondary connection cabinet per drawing pages CC-40 through CC-60E.
- 6. Customer shall furnish, install and maintain secondary connection cabinet and bus bar hole pattern shall have NEMA spacing (1-3/4" on center) and be centered on bar. SCC bus bar holes to accommodate 1/2" bolts.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Mar-13	Jan-13	JD		I-6.60	PAGE I-6.60

Effective Date April 15, 2015

Docket No. E999/CI-15-755 Information Request MPUC-005 Attachment B.2., Pages 150 of 180


TABLE OF RESPONSIBILITY

	Drawing CC –40 & 40A								
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL							
Permits and Inspections	Customer	N/A							
Secondary Connection Cabinet (SCC) Concrete Pad	Customer	Customer							
Pre-Cast Transformer & SCC Concrete Pad	Customer	Customer							
Cable Tray	Customer	Customer							
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company							
SCC Load Side Conduit/Sweeps and Conductor	Customer	Customer							
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer							

SECONDARY CONNECTION CABINET-TRANSFORMER PRE-CAST PAD

15/25 kV for 75-500 kVA & 15/25 kV for 750-2500 kVA


In-Line Orientation-Preferred



Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-10	Oct-07	JD		I-6.80	PAGE I-6.80

SECONDARY CONNECTION CABINET-TRANSFORMER PRE-CAST PAD 15/25 kV for 75-500 kVA & 15/25 kV for 750-2500 kVA

90° Orientation



Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-10	Oct-07	JD		I-6.81	PAGE I-6.81

Effective Date April 15, 2015

Docket No. E999/CI-15-755 Information Request MPUC-005 Attachment B.2., Pages 153 of 180

TABLE OF RESPONSIBILITY


Dra	awing CC – 50, 50A, B, C, D & F	2
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL
Permits and Inspections	Customer	N/A
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company
SCC Line-Side Termination Lugs	Company	Company
Cable Tray	Customer	Customer
Transformer Pour-In-Place Concrete Pad	Customer	Customer
Secondary Connection Cabinet (SCC) Concrete Pad	Customer	Customer
Connection Cabinet	Customer	Customer
SCC Load Side Conduit/Sweeps and Conductor	Customer	Customer
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CC-5 Cachment B.2., Pages 154 of 180

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

15 & 25 kV for 75-500 kVa

In-Line Orientation-Preferred




	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Oct-07	Mar-04	DR		I-6.91	PAGE I-6.91

Docket No. E999/CI-15-755 Information Request MPUC-005 Chment B.2., Pages 155 of 180

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

15 & 25 kV for 75-500 kVa

90° Orientation




	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy	Oct-07	Mar-04	DR		I-6.92	PAGE I-6.92

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

15 /25 kV for 750-2500 kVa & 35 kV for 1500-2500 kVA

In-Line Orientation-Preferred




	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Oct-07	Mar-04	DR		I-6.93	PAGE I-6.93

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

15 /25 kV for 750-2500 kVa & 35 kV for 1500-2500 kVA

90° Orientation




	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy	JY Nov-07	Mar-04	DR		I-6.94	PAGE I-6.94

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CC-50 Tachment B.2., Pages 158 of 180

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

35 kV for 75-1000 kVA

In-Line Orientation-Preferred




	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Nov-07	Mar-04	DR		I-6.95	PAGE I-6.95

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CC-50 Enchment B.2., Pages 159 of 180

SECONDARY CONNECTION CABINET AND TRANSFORMER POURED-IN-PLACE PAD

35 kV for 75-1000 kVA

90° Orientation



	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Acel Energy	Nov-07	Mar-04	DR		I-6.96	PAGE I-6.96

Docket No. E999/CI-15-755


Effective Date April 15, 2015

Information Request MPUC-005 Attachment B.2., Pages 160 of 180

TABLE OF RESPONSIBILITY


Dra	wing CC – 60, 60A, B, C, D & F	E	
ITEM MATERIAL OR WORK DESCRIPTION	PARTY TO FURNISH, OWN AND MAINTAIN	PARTY TO INSTALL	
Permits and Inspections	Customer	N/A	
Conductors from Transformer to Secondary Connection Cabinet (SCC)	Company	Company	
SCC Line-Side Termination Lugs	Company	Company	
Transformer Pour-In-Place Concrete Pad	Customer	Customer	
SCC Load Side Conduit/Sweeps and Conductor	Customer	Customer	
SCC Ground Rod and Conductor to neutral bus and case ground	Customer	Customer	

TRANSFORMER PAD DIMENSIONS FOR POURED-IN-PLACE



	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Dec-07	Mar-04	DR		I-6.101	PAGE I-6.101

THREE PHASE TRANSFORMER CONCRETE PAD 15 AND 25 kV (75-500 kVA) POURED IN PLACE




	REINFORCING STEEL SCHEDULE									
٢	2	3	4	\$	6	Approx. Weight				
(5) #4 X 6'-0"	(6) #4 X 0'-6"	(3) #4 X 6'-0"	(7) #4 X 2'-10"	(6) #4 X 5'-2"	(4) #4 X 3'-0"	2300 lbs.				

- 1. Concrete shall have a minimum compressive strength of 3000 psi at 28 days. All concrete shall be air entrained (4% to 6% by volume) with a maximum W/C ratio of 0.45.
- 2. Reinforcing steel shall be furnished in accordance with ASTM A615 Grade 60. Place per schedule within the limits shown. All reinforcing steel shall be uniformly tied to reinforcing steel to prevent displacement during concrete placement.
- 3. Top surface finish shall be level. Wood float top; do not leave any depressions.
- 4. Soil compaction under pad (for both pour-in-place and separate standard pads) to be at 95% Standard Proctor.
- 5. Maximum 2 elbows (conduits), for primary feed and source circuits, will be 4", Schedule 40 PVC 90°, 36" radius.
- 6. Primary PVC elbow stub-outs must be a minimum of 12" out from pad edge whether from a front or side trench approach feeding the transformer.
- 7. Pad must be located within 10 feet of driving surface for truck access for placement of transformer.
- 8. Maximum of 2 conduits, 4" if required.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-13	Nov-07	JD		I-6.102	PAGE I-6.102

THREE PHASE TRANSFORMER CONCRETE PAD 15 AND 25 kV (750-2500 kVA) POURED IN PLACE




NOTES:

1. Concrete shall have a minimum compressive strength of 3000 psi at 28 days. All concrete shall be air entraine (4% to 6% by volume) with a maximum W/C ratio of 0.45.

- 2. Reinforcing steel shall be furnished in accordance with ASTM A615 Grade 60. Place per schedule within the limits shown. All reinforcing steel shall be uniformly tied to reinforcing steel to prevent displacement during concrete placement.
- 3. Top surface finish shall be level. Wood float top; do not leave any depressions.
- 4. Soil compaction under pad (for both pour-in-place and separate standard pads) to be at 95% Standard Proctor.
- 5. Maximum 2 elbows (conduits), for primary feed and source circuits, will be 4", Schedule 40 PVC 90°, 36" radius.
- 6. Primary PVC elbow stub-outs must be a minimum of 12" out from pad edge whether from a front or side trench approach feeding the transformer.
- 7. Pad must be located within 10 feet of driving surface for truck access for placement of transformer.
- 8. Maximum of 2 conduits, 4" if required.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-13	Nov-07	JD		I-6.103	PAGE I-6.103

THREE PHASE TRANSFORMER CONCRETE PAD 35 kV (75-1000 kVA) POURED IN PLACE




	REINFORCING STEEL SCHEDULE									
1	1) 2 3 1 5 6 Approx. Weight									
(6) #4 X 7'-10"	(6) #4 X 0'-9"	(3) #4 X 7'-10"	(9) #4 X 3'-5"	(8) #4 X 5'-9"	(4) #4 X 3'-0"	4400 lbs.				

- 1. Concrete shall have a minimum compressive strength of 3000 psi at 28 days. All concrete shall be air entrained (4% to 6% by volume) with a maximum W/C ratio of 0.45.
- 2. Reinforcing steel shall be furnished in accordance with ASTM A615 Grade 60. Place per schedule within the limits shown. All reinforcing steel shall be uniformly tied to reinforcing steel to prevent displacement during concrete placement.
- 3. Top surface finish shall be level. Wood float top; do not leave any depressions.
- 4. Soil compaction under pad (for both pour-in-place and separate standard pads) to be at 95% Standard Proctor.
- 5. Maximum 2 elbows (conduits), for primary feed and source circuits, will be 4", Schedule 40 PVC 90°, 36" radius.
- 6. Primary PVC elbow stub-outs must be a minimum of 12" out from pad edge whether from a front or side trench approach feeding the transformer.
- 7. Pad must be located within 10 feet of driving surface for truck access for placement of transformer.
- 8. Maximum of 2 conduits, 4" if required.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-13	Nov-07	JD		I-6.104	PAGE I-6.104

THREE PHASE TRANSFORMER CONCRETE PAD 35 kV (1500-2500 kVA) POURED IN PLACE




NOTES:

1. Concrete shall have a minimum compressive strength of 3000 psi at 28 days. All concrete shall be air entrained (4% to 6% by volume) with a maximum W/C ratio of 0.45.

- 2. Reinforcing steel shall be furnished in accordance with ASTM A615 Grade 60. Place per schedule within the limits shown. All reinforcing steel shall be uniformly tied to reinforcing steel to prevent displacement during concrete placement.
- 3. Top surface finish shall be level. Wood float top; do not leave any depressions.
- 4. Soil compaction under pad (for both pour-in-place and separate standard pads) to be at 95% Standard Proctor.
- 5. Maximum 2 elbows (conduits), for primary feed and source circuits, will be 4", Schedule 40 PVC 90°, 36" radius.
- 6. Primary PVC elbow stub-outs must be a minimum of 12" out from pad edge whether from a front or side trench approach feeding the transformer.
- 7. Pad must be located within 10 feet of driving surface for truck access for placement of transformer.
- 8. Maximum of 2 conduits, 4" if required.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-13	Nov-07	JD		I-6.105	PAGE I-6.105


THREE PHASE TRANSFORMER CONCRETE PAD 35 kV (3750-5000 kVA STEPDOWN) POURED IN PLACE



- 1. Concrete shall have a minimum compressive strength of 3000 psi at 28 days. All concrete shall be air entrained (4% to 6% by volume) with a maximum W/C ratio of 0.45.
- 2. Reinforcing steel shall be furnished in accordance with ASTM A615 Grade 60. Place per schedule within the limits shown. All reinforcing steel shall be uniformly tied to reinforcing steel to prevent displacement during concrete placement.
- 3. Top surface finish shall be level. Wood float top; do not leave any depressions.
- 4. Soil compaction under pad (for both pour-in-place and separate standard pads) to be at 95% Standard Proctor.
- 5. Maximum 2 elbows (conduits), for primary feed and source circuits, will be 4", Schedule 40 PVC 90°, 36" radius.
- 6. Primary PVC elbow stub-outs must be a minimum of 12" out from pad edge whether from a front or side trench approach feeding the transformer.
- 7. Pad must be located within 10 feet of driving surface for truck access for placement of transformer.
- 8. Maximum of 2 conduits, 4" if required.

Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Jan-13	Nov-07	JD		I-6.106	PAGE I-6.106

CLEARANCE REQUIREMENTS FROM GAS METER




- 1. 3' minimum working clearance from non-electrical obstructions is preferred around gas meter set.
- 2. Disregard clearances when measuring around corners of structure.
- 3. See drawings SC-20 and SC-20A for ice and snow shield requirements.
- 4. Electric and plastic gas services within the same trench shall be separated by twelve (12) radial inches. Steel gas services shall not be installed in the same trench with an electric service and require a minimum of twelve (12) radial inches of separation.



VallEnarrow	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Mar-13	Jan-13	JD		I-7.1	PAGE I-7.1

CLEARANCE REQUIREMENTS FOR PROPANE TANKS



NO PAD-MOUNTED EQUIPMENT OR ELECTRIC METER SHALL BE INSTALLED WITHIN 15 FEET OF THE REFILL VALVE OF A TANK CONTAINING PROPANE.


NOTES:

1. The local Area Engineer should be contacted when violations are noted.

2. The Area Engineer will contact the appropriate governmental agency to report violation.



VaalEnavouv	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Mar-13	Nov-07	JD		I-7.2	PAGE I-7.2



Fire Resistant Barriers Attached Directly To Wall

In locations where basic clearances cannot be met, a fire resistant barrier shall be installed either by the customer or at the customer's expense to reduce the required clearance to combustible walls, doors air intakes or windows. The barrier shall be constructed of non-combustible material certified to have a 2 hour fire rating. It shall be of sufficient strength and have stability to resist tipping and satisfy local building ordinances. If a specific ruling regarding fire ratings is necessary, contact the local fire protection district. Engineering will coordinate the construction and location of the barrier, however the customer is responsible for all maintenance. The barrier will satisfy the following dimensional requirements:

- **H** = Height in inches of oil filled equipment.
- **W** = Width in inches of oil filled equipment.
- **C** = Height of barrier required to obtain a projected height of two times the height of the oil filled equipment on the building wall (2xH).
- D = Width of barrier required to obtain a projected width of two times the width of the oil filled equipment on the building wall (2xW).


2	
U	


Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Dec-07	Mar-04	DR		I-7.3	PAGE I-7.3

LOCATION OF PAD-MOUNTED TRANSFORMERS

I. <u>NONCOMBUSTIBLE WALLS</u> (Included in this class would be wood framed brick veneered buildings, metal clad steel framed buildings, asbestos-cement-board walled metal framed buildings and masonary buildings and masonary buildings with a one hour fire rating.)

Oil insulated, pad-mounted transformers may be located a minimum distance of 30" from noncombustible walls if all the following clearances are maintained from doors, windows, and other building openings. A sump shall be installed for transformers if the immediate terrain is not pitched away from the building. Contact Electric Standards for sump specifications. If a combustible first floor overhang exists, a 10' distance from the edge of the transformer to the edge of the overhang (combination of vertical and horizontal distance) shall be required in addition to the other clearances shown.





0	


Vallager	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Dec-07	Mar-04	DR		I-7.3A	PAGE I-7.3A

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-4 Attachment B.2., Pages 171 of 180

LOCATION OF PAD-MOUNTED TRANSFORMERS NEAR BUILDINGS


C. WINDOWS OR OPENINGS OTHER THAN AIR INTAKE

First Story
 Oil insulated pad-mounted transformers
 shall not be located within a zone
 extending 10' outward and 3' to either
 side of a building window or opening
 other than an air intake.



 Second Story
 Oil insulated, pad-mounted transformers shall not be located less than 5' from any part of a second story window or opening other than an air intake.

Oil filled equipment shall not be placed below an operating window on any floor. No exceptions will be made!






VeelEnewer	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy*	Jan-13	Nov-07	JD		I-7.4	PAGE I-7.4

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-5 Grachment B.2., Pages 172 of 180


LOCATION OF PAD-MOUNTED TRANSFORMERS NEAR BUILDINGS

II. COMBUSTIBLE WALLS

(Included in this class would be wood buildings and metal clad buildings with wood frame construction.) Oil insulated, pad-mouted transformers shall be located a minimum 10' from the building wall in additon to the clearance from building doors, windows, and other openings set forth for noncombustible walls. A sump shall be installed for transformers if the immediate terrain is not pitched away from the building. Contact Customer Service and Technical Support for sump specifications. If a combustible first floor overhang exists, a 10' distance from the edge of the transformer to the edge of the overhang (combination of vertical and horizontal distance) shall be required in addition to the other clearances as shown.




III. BARRIERS (Included in this class are reinforced concrete, brick, or concrete block barrier walls with a 3 hour fire rating.) If the clearance specified above cannot be obtained, a fire resistant barrier shall be constructed in lieu of the separation. The barrier (when required) is provided by the customer. The following methods of construction are acceptable.



A. NONCOMBUSTIBLE WALLS

The barrier shall extend to a projection line from the corner of the pad-mounted to the furthest corner of the window, door, or opening in question.



I-7.5




Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-6 Cachment B.2., Pages 173 of 180

LOCATION OF PAD-MOUNTED TRANSFORMERS NEAR BUILDINGS

B. COMBUSTIBLE WALLS

The barrier shall extend 3' beyond each side of the oil insulated, pad-mounted transformer. The height of the barrier shall be 3' above the top of the pad-mounted transformer. If a combustible first floor overhang exists, the 24" specified shall be measured from the edge of the overhang rather than from the building wall.



IV. FIRE ESCAPES

Oil insulated, pad-mounted transformers shall be located such that a minimum clearance of 20' is maintained from fire escapes at all times.

Exception: Oil insulated, pad-mounted transformers may be located closer to a fire escape than the 20' minimum when a fire resistant barrier is constructed around the transformer (side walls and roof). The barrier shall extend a minimumof 1' beyond the transformer. The transformer andbarrier shall not in any way obstruct the fire escape exit. 10' clearance is required in front of padmount transformer doors. Adequate transformer accessibility and ventilation must be provided. If transformer is installed underneath a fire escape, maintain 10' vertical clearance.

V. DECORATIVE COMBUSTIBLE ENCLOSURE


Decorative combustible enclosures (fence) installed by the customer around oil insulated, pad-mounted transformers adjacent to a combustible building wall shall not extend more than 24" beyond the transformer towards the combustible wall. 10' clearance required in front of pad-mounted transformer doors. Adequate transformer accessibility and ventilation must be provided.

VI. NONCOMBUSTIBLE AND COMBUSTIBLE WALLS - FIRE RESISTANT BARRIERS

The examples of combustible and noncombustible walls and fire resistant barriers obtained from March & McLennan Inc., Protection Consultants, and apply to building exposure to a fire located outside of the building.


|--|

Vool Enorman (*	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Nov-07	Mar-04	DR		I-7.6	PAGE I-7.6



Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-7 Grachment B.2., Pages 174 of 180

CLEARANCE OF COMPANY OWNED SECONDARIES AND SERVICE DROPS



the following: (a) Insulated service drops 12.5'

residential driveways only may be reduced to


(b) Insulated drip loops of service drops 10.5'

may be reduced to 10'-6".




VoolEnour	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Jan-08	Mar-04	DR		I-7.7	PAGE I-7.7


CLEARANCE OF COMPANY OWNED SECONDARIES AND SERVICE DROPS




NESC 234-C-3 EXCEPTION #2: Where not more than 6' measured (horizontally) service drop of 300 volts or less may pass over 4' of overhang if a minimum of 18" of clearance is maintained. If the service crosses more than 6' of roof, then 3' of clearance is required after the first 6'



<u>NESC 234-1:</u> A horizontal clearance of not less than 3' for triplex and 5'-6" for open wire must be maintained from window. Above window a 0" vertical clearance is allowed.



<u>NESC 234-1:</u> Open wire over 750 volts to ground 13'-6"; open wire up to 750 volts to ground 11'-5"; triplex/quad 11'-0".




<u>NESC 234-1:</u> Conductors shall have a horizontal clearance of 3' for triplex and 5'-6" for open wire.

|--|

VaclEnarrours	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Acel Energy*	Dec-07	Mar-04	DR		I-7.7A	PAGE I-7.7A

OBSTRUCTION AND BUMPER PROTECTION CLEARANCE REQUIREMENTS FOR PAD-MOUNTED EQUIPMENT




2' minimum, non door-side for switch equipment

- (2) 10' minimum, door-side for pad-mounted equipment except primary metering
- (3) 4" diameter (slugged)
- (4) 3-1/2" diameter with helix
- (5) 4' minimum height
- (6) 3' minimum depth
- (7) The shaded area shown above must be level and free from obstructions.

0	X
---	---

Vool Cooren (*	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy *	Mar-13	Jan-13	JD		I-7.9	PAGE I-7.9




- 1. The 5' side clearance is access for cabinet replacement or access to low voltage enclosures and switch operators.
- 2. The 10' operating clearance is for switching and maintenance on the door sides of all cabinets.
- 3. Local Design/Construction management or Area Engineering shall be consulted for clearance issues, traffic set back, and sight triangle requirements from local regulatory agencies.
- 4. The shaded area shown above must be level and free of obstructions.
- 5. In areas where there will be above ground metal equipment within 6 ft of switchgear, the NESC requires the equipment to be grounded and the grounds bonded. Install 8 ft of #4 Cu bonding wire 3 ft to the side, 6 in back from the front of the pad and buried 12 in deep. Connect the coil to the ground rod lug, not the switchgear.



VeelEnergy	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
Xcel Energy [®]	Mar-13	Jan-13	JD		I-7.10	PAGE I-7.10


Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-1 14 Chment B.2., Pages 178 of 180

SETTING DEPTHS FOR CUSTOMER OWNED POLE



POLE SETTING DEPTHS

Length of Poles	25'	30'	35'	40'
Depth of Setting in Firm Soil (Standard Depth)	5'-6"	5'-6"	6'-0"	6'-0"



NOTES:


Total Setting Depth = Standard Setting Depth + X


- 1. Settling depth on slopes or by ditches equals the standard setting depth plus the distance between the groundline and the lowest ground within 3 feet of the pole.
- 2. Poles will lean if extra setting depth is not used.


	VeelCreeker	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
0	Xcel Energy [*]	Mar-13	Jan-13	JD		I-7.11	PAGE I-7.11

Docket No. E999/CI-15-755 Information Request MPUC-005 DRAWING CR-12tochment B.2., Pages 179 of 180

CLEARANCE REQUIREMENTS FOR ELECTRIC METERS IN ENCLOSED SPACES








- 1. Area within dashed lines shall be clear of all obstructions.
- 2. 18" clearance shall be maintained to either side of the center line of the meter socket per NEC ®.
- 3. 36", 42" or 48" clearance shall be maintained in front of meter socket per NEC®.
- 4. Height of working clearance shall be per NEC®.




COMPANY OWNED SERVICES CLEARANCE FROM SWIMMING POOLS 212°F CONDUCTOR TEMPERATURE

Type of Structure Under or Next to Wire	Neutrals, Guys Messengers; Surge protection Wires and Communications	Duplex, Triplex Quadraplex, Lashed 0 - 750 V	Open Supply Conductors 0 - 750 V	Primary Conductors 750 V - 22 kV
<u>Clearance In Any</u> <u>Direction To:</u> Edge of pool, water	22'-0" (Note 1)	22'-6" (Note 1)	23'-0"	25'-0"
surface, <u>Base</u> of diving platform or anchored raft. (Dimension A)	18'-0" (WI)	18'-0" multiplex (WI)	25'-0" open wire (WI)	27'-0" (WI)
Clearance In Any Direction To: Diving platform or Tower	14'-0" (Note 6)	14'-6" (Note 6)	15'-0" (Note 6)	17'-0" (Note 6)
(Dimension B)		16'-0" (WI)	16'-0" (WI)	18'-0" (WI)
Hot Tubs and Whirlpool Spas (Notes 4 and 5)	10'-6"	11'-0"	11'-6"	13'-6"



Clearances of Underground Secondary Service Lateral to Patios and Pools



*These dimensions are minimum unless cable is in conduit

- 1. 0-750 volts except open wire HORIZONTALLY greater than 10 feet from the edge of the pool or diving platform NEED ONLY a vertical clearance of 12.5 feet in pedestrian only traffic areas.
- 2. The above table is for both above and below grade pools.
- 3. Values from <u>NESC</u> Table 234-3, Figure 234-3.
- 4. For hot tubs and whirlpool spas, clearance is the same as clearance from balconies, decks and areas accessible to pedestrians. Clearance would be from the highest point a person could stand to the conductor (see Drawing CR-70).
- 5. For hot tubs and whirlpool spas clearance is less than swimming pools since long handled cleaning equipment and rescue poles are not used.
- 6. For horizontal clearance add 2 feet for conductor swing.

	Issued	Replaces	Drawn by	Approved	File	STANDARD FOR ELECTRIC INSTALLATION AND USE
(cei Energy	Jan-13	Jan-08	JD		I-7.13	PAGE I-7.13